

ESTIMATE OF QUANTITIES  
 Quantities Shown are App. Estimate Only and are Subject to Increase or Decrease  
 TO BE CONTRACTED

ITEM NO.	PROJ. NO. STP-170(53)	PROJ. NO. STP-170(56)	TOTAL	UNIT	ITEM
200 0001	20	20	40	HOUR	SURVEY CREW
202 2802	4,300	---	4,300	SQYD	REMOVAL OF BITUMINOUS SURFACE (COLD MILLING)
202 3103	376	274	650	CUYD	REMOVAL OF COMPOSITE SURFACE
202 3400	---	10	10	SQYD	REMOVAL OF SIDEWALK
202 3600	40	150	190	LINFT	REMOVAL OF CURB AND GUTTER
202 4202	---	2	2	EACH	REMOVAL OF TRAFFIC SIGNAL CONTROLLER CABINET
202 4203	4	1	5	EACH	REMOVAL OF TRAFFIC SIGNAL POLE
202 6600	50	260	310	EACH	REMOVAL OF PAVEMENT MARKER
302 0100	460	320	780	TON	TYPE 1 CLASS B AGGREGATE BASE
402 4020	180	150	330	TON	PLANTMIX BITUMINOUS SURFACE AGGREGATE (TYPE 2)
402 4300	21	18	39	TON	ASPHALT CEMENT, GRADE AC-30
403 2500	14	170	184	TON	PLANTMIX BITUMINOUS OPEN-GRADED SURFACE AGGREGATE (1/2-INCH)
405 5430	3	3	6	TON	EMULSIFIED ASPHALT, TYPE SS-1H (DILUTED)
502 0102	42	8	50	CUYD	CLASS A CONCRETE (ISLAND PAVING)
613 1102	10	---	10	LINFT	CLASS A CONCRETE CURB (TYPE 2)
613 1105	1,947	123	2,070	LINFT	CLASS A CONCRETE GLUE DOWN CURB (TYPE B)
613 1305	300	---	300	LINFT	CLASS A CONCRETE CURB AND GUTTER (TYPE 5)
613 1404	10	---	10	SQYD	CLASS A CONCRETE SIDEWALK (4-INCH)
613 1944	70	12	82	SQYD	CLASS A CONCRETE RAMP (4-INCH)
621 1001	1	---	1	EACH	REMOVE & RESET MONUMENT
623 0115	275	575	850	LINFT	1-1/2-INCH CONDUIT
623 0120	245	280	525	LINFT	2-INCH CONDUIT
623 0130	900	660	1,560	LINFT	3-INCH CONDUIT
623 1002	660	330	990	LINFT	NO. 2 CONDUCTOR
623 1006	40	40	80	LINFT	NO. 6 CONDUCTOR
623 1008	890	420	1,310	LINFT	NO. 8 CONDUCTOR
623 1010	1,235	1,240	2,475	LINFT	NO. 10 CONDUCTOR
623 1012	200	---	200	LINFT	NO. 12 CONDUCTOR
623 1014	410	900	1,310	LINFT	NO. 14 CONDUCTOR
623 1110	235	---	235	LINFT	10 CONDUCTOR NO. 14 CABLE
623 1125	1,700	695	2,395	LINFT	25 CONDUCTOR NO. 14 CABLE
623 1220	---	310	310	LINFT	3 CONDUCTOR NO. 20 CABLE
623 2035	6	3	9	EACH	NO. 3-1/2 PULL BOX
623 2050	12	4	16	EACH	NO. 5 PULL BOX
623 2070	1	1	2	EACH	NO. 7 PULL BOX
623 3104	1	4	5	EACH	SODIUM VAPOR LUMINAIRE, 400 WATT
623 3602	---	1	1	EACH	ILLUMINATED STREET NAME SIGN, DOUBLE FACE (6-FOOT)
623 3604	1	1	2	EACH	ILLUMINATED STREET NAME SIGN, DOUBLE FACE (8-FOOT)
623 4350	1	4	5	EACH	STEEL POLE, TYPE 35
623 6206	---	1	1	EACH	SIGNAL HEAD (12-INCH) 1W3C, BRACKET
623 6208	1	---	1	EACH	SIGNAL HEAD (12-INCH) 2W3C, BRACKET
623 6209	1	---	1	EACH	SIGNAL HEAD (12-INCH) 3W3C, BRACKET
623 6211	3	6	9	EACH	SIGNAL HEAD (12-INCH) 1W3C, MAST ARM
623 6233	---	4	4	EACH	SIGNAL HEAD (12-INCH) 2W3C/5C, BRACKET
623 6235	---	4	4	EACH	SIGNAL HEAD (12-INCH) 1W5C, MAST ARM(M-5)
623 6501	---	1	1	EACH	PEDESTRIAN SIGNAL HEAD 1W

FED. RD. REG. NO.	STATE	PROJECT NO.	COUNTY	SHEET NO.
9	NEVADA	STP-170(53) STP-170(56)	CLARK	3B