

ESTIMATE OF QUANTITIES (Continued)

ITEM NO.	PROJ. NO. STP-170(53)	PROJ. NO. STP-170(56)	TOTAL	UNIT	ITEM
623 6502	---	5	5	EACH	PEDESTRIAN SIGNAL HEAD 2W
623 6601	3	8	11	EACH	PEDESTRIAN PUSH BUTTON WITH SIGN
623 7000	15	49	64	EACH	LOOP DETECTOR (6-FOOT X 6-FOOT)
623 7001	1	1	2	EACH	LOOP DETECTOR (A)
623 7002	3	---	3	EACH	LOOP DETECTOR (B)
623 7005	---	2	2	EACH	EMERGENCY VEHICLE DETECTOR
623 7006	8	12	20	EACH	LOOP DETECTOR AMPLIFIER CHANNELS (NEW CABINET)
623 7100	1,590	2,020	3,610	LINFT	LEAD-IN CABLE FOR LOOP DETECTORS
623 7500	1	1	2	EACH	TRAFFIC ACTUATED CONTROLLER
623 8501	1	---	1	EACH	REMOVE AND RESET SIGNAL POLE
623 8755	6	45	51	SQFT	TRAFFIC SIGNAL SIGNS
624 0200	200	---	200	HOURL	FLAGGER
624 0205	50	50	100	HOURL	UNIFORMED TRAFFIC CONTROL OFFICER
624 0540	30	---	30	HOURL	RENT EQUIPMENT (LOADER)
624 0550	40	---	40	HOURL	RENT EQUIPMENT (DUMP TRUCK)
624 0600	10	---	10	HOURL	RENT EQUIPMENT (BACKHOE)
625 0110	345	345	690	SQFT	RENT CONSTRUCTION SIGNS
625 0114	100	100	200	EACH	RENT TRAFFIC CONES
625 0117	10	10	20	EACH	RENT BARRICADE WARNING LIGHTS (TYPE A)
625 0122	---	7	7	EACH	RENT CONSTRUCTION BARRICADES (TYPE IIIB)
625 0302	2	2	4	EACH	RENT ARROW BOARD (TYPE B)
625 0416	75	75	150	EACH	RENT TRAFFIC DRUMS
627 0110	45	---	45	SQFT	PERMANENT SIGNS (GROUND MOUNTED) (METAL SUPPORTS)
627 0140	7	---	7	SQFT	PERMANENT SIGNS, REMOVE
628 0100	---	---	LS	---	MOBILIZATION
633 0100	64	266	330	EACH	NON-REFLECTIVE PAVEMENT MARKERS
633 0200	132	203	335	EACH	REFLECTIVE PAVEMENT MARKERS
633 0330	150	---	150	EACH	TEMPORARY LANE LINE MARKERS (YELLOW)
634 2100	216	251	467	SQFT	PERMANENT PAVEMENT MARKING FILM (TYPE 1) (VARIES)
634 2108	485	493	978	LINFT	PERMANENT PAVEMENT MARKING FILM (TYPE 1) (8-INCH)
634 2112	721	2,099	2,820	LINFT	PERMANENT PAVEMENT MARKING FILM (TYPE 1) (12-INCH)
634 2124	890	500	1,390	LINFT	PERMANENT PAVEMENT MARKING FILM (TYPE 1) (24-INCH)

FED. RD. REG. NO.	STATE	PROJECT NO.	COUNTY	SHEET NO.
9	NEVADA	STP-170(53) STP-170(56)	CLARK	3C