

ITEM NO.	ITEM	TOTAL	USE TOTAL	UNIT
627-0110	PERMANENT SIGNS (GROUND MOUNTED) (METAL SUPPORTS)	45.00	45.00	SQ. FT.
627-0140	PERMANENT SIGNS, REMOVE	6.25	7.00	SQ. FT.

SIGN GENERAL NOTES

1. Sign numbers shown on sign summary are taken from the Manual on Uniform Traffic Control Devices (1988), Standard Highway Signs and Nevada's Supplement (1992).
2. Posts lengths pertain to the type of post as shown on the sign summary. If the Contractor chooses one of the other types shown in our Standard Plans, the Contractor must furnish a sign summary depicting the appropriate post and corresponding post length. This sign summary must be approved by the Traffic Engineering Division prior to the fabrication of these alternate posts.
3. Installation numbers with a D signify do not disturb.
4. Installation numbers with an R signify removal.
5. All sign removals shall be stockpiled for pickup by State Forces.
6. Distance from edge of travel way to near edge of sign shall be minimum as shown on Standard Sheet T-31.1.1.
7. Post lengths for all ground mounted signs are calculated to the nearest inch. All single post lengths are based on the use of a sign island. See Standard Sheet T-31.1.1.
8. Sign islands will not be required for all new installations.
9. Type III Reflective Sheeting shall be used on all installations.

FED. AID DIST. NO.	STATE	PROJECT NO.	COUNTY	SHEET NO.
9	NEVADA	STP-170(53)	CLARK	TS-2
		STP-170(56)		