

QUANTITIES

SHEET NO. 7 8 9

STREET IMPROVEMENTS:

NO. LEGEND		DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET									
1.		2" AC. PAVEMENT W/4" TYPE 2, 6" TYPE 1 GB	SY	4458		2087	2371							
2.		STD. "L" TYPE CURB & GUTTER W/6" TYPE 1 GB	LF	1897		803	1094							
3.		3.5' CONC. SIDEWALK W/5" TYPE 2 GB	SF	3750		1739	2011							
4.	* *	CONC. DRIVEWAY W/8" TYPE 2 GB	SF	2800		980	1820							
NOTE: NATIVE MATERIAL TO BE USED IN LIEU OF IMPORTED TYPE 1														
** NOTE: APPROXIMATE DRIVEWAY QUANTITY. FINAL QUANTITY TO BE DETERMINED FROM MODEL SCHEDULE SHOWN ON THE PLOT PLAN. THIS QUANTITY IS BASED ON A 16' BOTTOM + 4' X WIDTH OF SIDEWALK. (70.0 S.F. PER DRIVEWAY)														

WATER:

1.		8" A.C.P.	LF	881	881									
2.		8" GATE VALVE W/VALVE BOX & COVER	EA	1	1									
3.		3/4" SERVICE	EA	40	40									
4.		METER BOX	EA	40	40									
5.		5/8" METER (INSTALLATION BY LVVWD)	EA	40	40									
6.		STD. F.H. W/6" G.V. & 6" ACP LATERAL	EA	1	1									
7.		CONNECT TO EXIST. 8" WATER	EA	2	2									
8.		REMOVE EXIST. 10" WATER	LF	50	50									

SEWER:

1.		STANDARD MANHOLE	EA	2	2									
2.		8" P.V.C.	LF	953	255	698								
3.		4" P.V.C. LATERAL	LF	1043	1043									
4.		CONNECT TO EXIST. 8" SEWER	EA	2	2									
5.		REMOVE EXIST. 8" SEWER & PLUG @ MANHOLE	LF	29	29									

STREET LIGHTS:

1.		150 W. HPS LUMINAIRE W/CONC. POLE & MISSION BELL STREET LIGHT FIXTURES	EA	5	5									
2.		#3 1/2 PULL BOX W/METAL COVER	EA	1	1									

MISCELLANEOUS:

1.		6" D-3 STREET NAME SIGN	EA	2	2									
EXCAVATION CUT 19,000 FILL 6,400														
NOTE: EXCAVATION QUANTITIES ARE RAW QUANTITIES DO NOT INCLUDE SUBSIDENCE & SHRINKAGE FACTOR														

NOTE TO CONTRACTOR
QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

REVISIONS
NO. DESCRIPTION DATE

RECOMMENDED
DAVID P. HUCKLE
DATE 4-2-88

DESIGNED
DAVID P. HUCKLE
DATE 4-2-88

1555 SOUTH RAINBOW BLVD., LAS VEGAS, NEVADA 89102

G.C. WALLACE, INC.
Engineering/Architecture

LEWIS HOMES OF NEVADA
CARMEL POINT No. 5 By LEWIS HOMES

ESTIMATE OF QUANTITIES

SHEET 6 OF 11 SHEETS

JOB NO. 55443.8680