

QUANTITIES

SHEET NO. 7 8 9 10

STREET IMPROVEMENTS:

NO. LEGEND		DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET									
1		3 3/4" A.C. PAVE W/4" TYPE 2, 9" TYPE 1 * G.B.	S.Y.	2,747										
2		2" A.C. PAVE W/4" TYPE 2, 6" TYPE 1 * G.B.	S.Y.	5,416										
3		STD. 1" TYPE CURB & GUTTER W/6" TYPE 1 * G.B.	L.F.	3,062										
4		6" CONC. SIDEWALK W/5" TYPE 2 G.B.	S.F.	2,962	517	2,603	2,813							
5		3 1/2" CONC. SIDEWALK W/5" TYPE 2 G.B.	S.F.	5,167	2,962	1,217	1,323							
6	* *	CONC. DRIVEWAY W/5" TYPE 2 G.B.	S.F.	3,900		2,510	2,637							
7		6" VALLEY GUTTER W/10" TYPE 1 * G.B.	S.F.	421		1,750	1,750							
8		8" VALLEY GUTTER W/10" TYPE 1 * G.B.	S.F.	796	796	421								
	*	NOTE: NATIVE MATERIAL TO BE USED IN LIEU OF IMPORTED TYPE 1.												
	* *	NOTE: FINAL DRIVEWAY QUANTITY TO BE DETERMINED FROM THE MODEL SCHEDULE SHOWN ON THE PLOT PLAN. QUANTITIES SHOWN IS APPROXIMATE. IT IS BASED ON A 16' BTM PLUS 4' X WIDTH OF SIDEWALK.												

WATER:

1		STD. FH W/6" G.V. & 6" A.C.P. LATERAL	EA.	2	2									
2		6" A.C.P.	L.F.	1,361	1,361									
3		6" GATE VALVE W/VALVE BOX & COVER	EA.	1	1									
4		3/4" SERVICE	EA.	50	50									
5		METER BOX	EA.	50	50									
6		3/8" METER (INSTALLATION BY L.V.V.W.D.)	EA.	50	50									
7		8" A.C.P.	L.F.	163	163									
8		8" GATE VALVE W/VALVE BOX & COVER	EA.	2	2									
9		2" BLOW-OFF ASSEMBLY	EA.	1	1									

SEWER:

1		4" PVC LATERAL	L.F.	1,343	1,343									
---	--	----------------	------	-------	-------	--	--	--	--	--	--	--	--	--

STREET LIGHTS:

1		250 W. HPS LUMINAIRE W/11 GA. POLE	EA.	5	5									
2		100 W. HPS LUMINAIRE W/11 GA. POLE	EA.	6	6									
3		#3 1/2 PULL BOX W/METER COVER	EA.	1	1									

MISCELLANEOUS:

1		STREET NAME SIGN	EA.	2	2									
2		STOP & STREET NAME SIGN	EA.	1	1									
3														

NOTE TO CONTRACTOR
QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

DESCRIPTION

REV

DATE

3784

6/1/16

R.E. NO.

DATE

STATE OF NEVADA

REGISTERED PROFESSIONAL ENGINEER

IN THE STATE OF NEVADA

CIVIL

1100 East Sahara Ave. • Las Vegas, Nevada 89104 • 732-3330

G.C. WALLACE

Consulting Engineers, Inc.

LEWIS HOMES OF NEVADA

CARMEL POINT NO. 2 BY LEWIS HOMES

ESTIMATE OF QUANTITIES

JOB NO. 5543.8530

SHEET 6

OF 10 SHEETS