

**MATCHLINE 'E' SEE SHEET 4 OF 6
'F' FOR CONTINUATION**

MATCHLINE 'F' SEE BELOW LEFT
 'F' FOR CONTINUATION

DESERT FOOTHILLS DR
 (PUB. LDG)

12' TYP.

392' 2-3"

551' 2-3"

24"

STUB &
 CAP 2-3"
 CONDUIT

N

MATCHLINE 'G' SEE SHEET 6 OF 6
 'G' FOR CONTINUATION

FOR CONTINUATION

LEGEND		
1		INSTALL B-36 PULL BOX (24"x36"x24")
2		EXISTING B-36 PULL BOX (24"x36"x24")
3		INSTALL B-50 PULL BOX (13"x24"x24")
4		EXISTING B-50 PULL BOX (13"x24"x24")
5		INSTALL B-100 PULL BOX (24"x36"x24")
6		EXISTING B-100 PULL BOX (24"x36"x24")
7		INSTALL T-200 CATV VAULT (30"x48"x36")
8		EXISTING T-200 CATV VAULT (30"x48"x36")
9		INSTALL T-400 CATV VAULT (36"x60"x36")
10		EXISTING T-400 CATV VAULT (36"x60"x36")
11		INSTALL T-600 CATV VAULT (48"x72"x36")
12		EXISTING T-600 CATV VAULT (48"x72"x36")
13		INSTALL NEW CATV PEDESTAL
14		EXISTING NEW CATV PEDESTAL
15		R&R S/W SLAB(S)
16		POTHOLE
17		SIDEWALK/DIRT TRENCH INSTALL
18		ASPHALT/STREET TRENCH INSTALL
19		PROPOSED BORE
20		EXISTING CATV CONDUIT(S)
21		PROPOSED OVERHEAD FIBER OPTIC CABLE OR COAX INSTALL
22		EXISTING OVERHEAD FIBER OPTIC CABLE OR COAX
23		U.G. FIBER/COAX PULL
24		RIGHT OF WAY LINE
25		LOT/PROPERTY LINE
26		EDGE OF PAVEMENT
27		EXISTING NVE PULL BOX
28		EXISTING TELCO PULL BOX
29		EXISTING TELCO MANHOLE
30		EXISTING TELCO POLE
31		EXISTING NVE POLE
32		EXISTING NVE TRANSMISSION POLE
33		EXISTING JOINT POLE
34		EXISTING JOINT POLE WITH TRANSFORMER
35		POLE ANCHOR
36		EXISTING NVE TRANSFORMER TRANSFORMER PAD
37		SNWA TEST STATION
38		COX POWER SUPPLY (49"x24"x52")
39		INSTALL RHINO CABINET
40		RISER POLE/QUADRANT DETAIL RISER OWNERSHIP NOTED
41		RAILROAD
42		EXISTING MANHOLE (SS),(SD)...ECT
43		1in CONDUIT
44		2in CONDUIT

UTILITY LOCATIONS SHOWN
HEREON ARE APPROXIMATE ONLY.
IT SHALL BE THE CONTRACTOR'S
RESPONSIBILITY TO DETERMINE
THE EXACT HORIZONTAL AND
VERTICAL LOCATION OF ALL
EXISTING UNDERGROUND AND
OVERHEAD UTILITIES PRIOR TO
COMMENCING CONSTRUCTION.
NO REPRESENTATION IS MADE
THAT ALL EXISTING UTILITIES ARE
SHOWN HEREON. THE ENGINEER
ASSUMES NO RESPONSIBILITY
FOR UTILITIES NOT SHOWN OR
UTILITIES NOT SHOWN IN THEIR
PROPER LOCATIONS.

TOTAL BORE	
TOTAL DIRT TRENCH	
TOTAL ASPHALT TRENCH	
TOTAL TRENCH	
SIDEWALK REMOVAL/REPLACE	
TOTAL S/W PANELS	
TOTAL LINEAR FOOTAGE	

**AVOID OVERHEAD POWER
LINE CONTACT**

**CALL
BEFORE YOU
OVERHEAD**

1-702-227-2929
**NEVADA POWER ENVIRONMENT AND
SAFETY SERVICE DEPARTMENT**



COX
17700 VEGAS DRIVE
LAS VEGAS, NEVADA 89106
PHONE: (702) 545-1606
FAX: (702) 545-2606

APPROVAL [Signature] 12/30/2013
DATE

PERMIT #	40505130000318300
DRAWN BY:	
CMR	
DATE:	11/13/13
SCALE:	
1:20	
NOODE:	
—	
W.O.#	
—	
TECH #	
420-6819	
APPROVED BY:	
MANDY MOORE	

SHEET No: 5

SHEET 5 OF 6

Valley Blueprint 12/10/2013