


1. COURSES SHOWN ON THIS PLAN ARE COMPUTED BASED ON TOP OF FINISHING WALL (TFW) MINUS TOP OF FOOTING (TF). TOP FOOTING IS FINISHED GRADE AT THE FACE OF WALL MINUS 4 INCHES.
2. RETAINING WALLS 3- FEET OR LESS MAY BE PAVESTONE STACKING BLOCK OR OWNER APPROVED EQUAL.
3. RETAINING WALLS 4- FEET OR LESS MAY BE CONSTRUCTED PER CLARK COUNTY STANDARD DRAWING B-100-2 OR DESIGNED BY OTHERS.
4. RETAINING WALLS GREATER THAN 4- FEET MUST BE DESIGNED BY OTHERS.
5. ROCKERY RETAINING WALLS MUST BE DESIGNED BY OTHERS AND COMPLY WITH SOUTHERN NEVADA BUILDING OFFICIALS GUIDELINES.



CLV# 107V5035
H#57782

[illegible]

TITLE	SECTION SHEET
PROJECT	BUFFALO-PEAK APARTMENTS CITY OF LAS VEGAS, NEVADA



$I = \int F \cdot dt$

CIVIL ENGINEERS • PLANNERS
 5135 CAMINO AL NORTE, SUITE 204
 NORTH LAS VEGAS, NEVADA 89031
 PHONE (702) 853-6702
 FAX (702) 853-6703

OV-1423
 REH
 01/05/15
 NO SCALE



Impulse

Civil Engineering & Planning

W.O. # : _____

BY :	SHEETS
DATE :	4 of 19
SCALE :	