

## QUANTITY ESTIMATES - ONSITE (PUBLIC)


| ITEM # | DESCRIPTION                                   | UNIT       | QUANTITY  | TOTAL       |
|--------|-----------------------------------------------|------------|-----------|-------------|
| 1      | 2" ASPHALTIC CONCRETE PAVING                  | \$2.90 SY  | 13,385 SY | \$38,816.50 |
| 2      | 3" ASPHALTIC CONCRETE PAVING                  | \$4.35 SY  | 584 SY    | \$2,540.40  |
| 3      | TYPE I GRAVEL BASE                            | \$7.60 CY  | 2,700 CY  | \$20,520.00 |
| 4      | TYPE II GRAVEL BASE                           | \$7.60 CY  | 1,550 CY  | \$11,780.00 |
| 5      | CURB AND GUTTER ("L" TYPE)                    | \$4.15 LF  | 479 LF    | \$1,987.85  |
| 6      | CURB AND GUTTER (30" ROLL)                    | \$4.15 LF  | 6,433 LF  | \$26,696.95 |
| 7      | CURB AND GUTTER ("A" TYPE)                    | \$4.15 LF  | 95 LF     | \$394.25    |
| 8      | VALLEY GUTTER                                 | \$3.35 SF  | 4,139 SF  | \$13,865.65 |
| 9      | SIDEWALK (5")                                 | \$1.85 SF  | 13,974 SF | \$25,851.90 |
| 10     | HANDICAP RAMP                                 | \$250 EA   | 16 EA     | \$4,000.00  |
| 11     | STREETLIGHT (STANDARD BASE)                   | \$1710.00  | 24 EA     | \$41,040.00 |
| 12     | 24" RCP STORM DRAIN                           | \$65.00 LF | 88 LF     | \$5,720.00  |
| 13     | 20.5' TYPE "C" MODIFIED DROP INLET (7 GRATES) | \$12500 LS | 1 EA      | \$12,500.00 |
| 14     | STORM DRAIN MANHOLE                           | \$855 EA   | 1 EA      | \$855.00    |
| 15     | 4" SEWER                                      | \$9.50 LF  | 2,332 LF  | \$22,154.00 |
| 16     | 8" SEWER                                      | \$14.25 LF | 3,448 LF  | \$49,134.00 |
| 17     | SEWER MANHOLES UNDER 6 FEET                   | \$855 EA   | 17 EA     | \$14,535.00 |
| 18     | SEWER MANHOLES OVER 6 FEET                    | \$1710 EA  | 1 EA      | \$1,710.00  |
| 19     | 8" WATER MAIN                                 | \$14.25 LF | 3,194 LF  | \$45,514.50 |
| 20     | 12" WATER MAIN                                | \$24.25 LF | 132 LF    | \$3,201.00  |
| 21     | FIRE HYDRANT                                  | \$1710 EA  | 7 EA      | \$11,970.00 |
| 22     | WATER SERVICE TO LOTS                         | \$235 EA   | 88 EA     | \$20,680.00 |
| 23     | POWER TO LOTS                                 | \$475 EA   | 88 EA     | \$41,800.00 |
| 24     | TELEPHONE TO LOTS                             | \$250 EA   | 88 EA     | \$22,000.00 |
| 25     | MISC. TRENCHING (CONDUIT)                     | \$5.00 LF  | 3288 LF   | \$16,440.00 |
| 26     | PULLBOX                                       | \$100 EA   | 9 EA      | \$900.00    |
| 27     | STREET / STOP SIGNS                           | \$100 EA   | 6 EA      | \$600.00    |
| 28     | SERVICE POINT                                 | \$200 EA   | 1 EA      | \$200.00    |
| 29     | EXCAVATION AND EMBANKMENT                     | \$2.40 CY  | 36,000 CY | \$86,400.00 |
| 30     | EXCAVATION AND EMBANKMENT                     | LUMP SUM   | 17 EA     | \$2,500.00  |

DRAWN BY:

DESIGNED BY:

**CHECKED BY:**

PROJECT NO:



11/25/98

SHEET  
C4  
4 OF 19 SHEETS

DRAWING NO.  
107Y-4585

# Pulte Homes

**CB Carter Burgess**  
Consultants in Planning, Engineering, Architecture,  
Construction Management and Related Services  
2955 East Sunset Road, Suite 105  
Las Vegas, NV 89120  
(702) 798-1007 Fax (702) 798-7056  
An American Favorite (702) 256-7800

**QUANTITY  
SHEET**

ARBOR  
VIEW[illegible]

