FED.ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	COUNTY	CONTROL SECTION	SHEET NO	TOTAL SHEETS
7	NEVADA	00GG-1(21)	—	CLARK	CL. 16	19	57

STRUCTURE LIST

STATION	DESCRIPTION	STRUCTURE EXCAVATION	BACKFILL	DRAIN BACKFILL	DRAINAGE EXCAVATION	REMOVE CULVERT HEADWALLS	REMOVE CULVERT PIPE	RELAY CULVERT PIPE	REINFORCED CONCRETE PIPE 12"	15"	18"	24"	30"	33"	36"	39"	42" STAND. STRENGTH	42" EXTRA STRENGTH	36" RCP MANHOLE SHAFT	36"X24" REDUCER CONE (MANHOLES)	6"X24" TOP RING (MANHOLES)	8"X24" TOP RING (MANHOLES)	6" TILE UNDERDRAIN	6" SEWER PIPE	10" SEWER PIPE	CLASS A CONCRETE	CLASS B CONCRETE	CLASS A CONC. CURB & GUTTER	CLASS A CONC. SIDEWALK		REINFORCING STEEL	STRUCTURAL STEEL ITEM N°47	STRUCTURAL STEEL ITEM N°61	STRUCTURAL STEEL RAIL	3-PLY MEMBRANE WATERPROOFING	REMOVE CONCRETE	REMOVE TREES		REMOVE BUILDING	REMOVE FENCE	RECONSTRUCT FENCE	CONSTRUCT FENCE	BEAM-TYPE METAL GUARD RAIL	MOVE POLES	MISCELLANEOUS WORK					
96 + 00 ± TO 98 + 00 ±	REMOVE PORTIONS OF EXISTING FENCE FOR SHOOFLY AND SPUR RT.																																																
	RECONSTRUCT AFTER ABANDONING SHOOFLY.																																															
96 + 00 97 + 28 ±	CONSTRUCT 228 LIN. FT. TYPE A-32-2B FENCE RT. ALONG R/W LINE.																																															
96 + 36 ±	REMOVE 24" X 20' C.M.P. LT.						20																																									
96 + 97 ±	REMOVE 24" X 50' C.M.P.					2	50																																									
96 + 62.75	NEW 12" X 10' R.C.P. CONSTRUCT DROP INLET LT. (SEE SHEETS NO. 41 & 43).	6	5						10																																								
97 + 50	CONSTRUCT GRADEE FOR SHOOFLY (SEE SHEET NO. 27).																																															
97 + 00	CONSTRUCT SEWER MANHOLE LT. (SEE SHEET NO. 47).	4	4																2.00	1	1	1				0.40								95																	
97 + 68	REMOVE DOUBLE 24" X 45' CONCRETE PIPE.					2	90																																									
97 + 70	NEW 30" X 60' R.C.P. CONSTRUCT DROP INLET RT. (SEE SHEETS NO. 41 & 44).	81	65		5								69													0.93					40		258															
97 + 75	CONSTRUCT JUNCTION BOX LT. (SEE SHEETS NO. 41 & 44).	12	8																							2.11					167																	
97 + 50	LAY TRACK ON SHOOFLY. REMOVE, RESET, AND ADJUST TRACKS AS SHOWN ON SHEET NO. 27. (BY RAILROAD).																																															
97 + 75 98 + 30	NEW 42" X 52' R.C.P. LT. (STANDARD STRENGTH).	64	40														52																																
97 + 90	REMOVE FLASHING LIGHT SIGNAL AND CONTROL BOXES RT. (BY RAILROAD).																																															
98 + 00 ± 98 + 00 ±	CONSTRUCT RAILROAD GRADE CROSSINGS LT. ON SHOOFLY, MAIN TRACK AND TRACK 40. (SEE SHEETS NO. 25 & 26). (SPECIAL DETOURS - FORCE ACC'T.).																																															
98 + 30 101 + 00	NEW 42" X 269' R.C.P. (STANDARD STRENGTH).	650	517														269																																
98 + 30	NEW 18" x 18' R.C.P.: CONSTRUCT DROP INLETS LT. & RT. (SEE SHEETS NO. 42 & 44).	25	18								18															3.14					197		1043																
98 + 32.34	CONSTRUCT CONCRETEE AND STEEL UNDERPASS AS SHOWN ON UNDERPASS DETAILS. (SEE SHEETS NO. 28 TO 42). STRUCTURE NO. B-470.	687	593																							240.00	40.00				179.283	355.183		231.58	20.55														
98 + 40 ± 102 + 48 ±	REMOVE 470 LIN. FTT. FENCE RT. RECONSTRUCT 420 LIN. FT. ALONG NEW SOUTHERLY R/W LINE.																																															
98 + 70	REMOVE FLASHING LIIGHT SIGNAL LT. (BY RAILROAD).																																															
98 + 80	REMOVE SEWER MANHOLE RT.																																															
99 + 00	PROTECT TRIPLE CULLVERT UNDER RAILROAD LT.																																															
99 + 12 ± 102 + 88.44	CONSTRUCT 370 LIN.. FT. TYPE A-32-2B FENCE LT. ALONG R/W LINE																																															
100 + 00	CONSTRUCT SEWER MANHOLE LT. (SEE SHEET NO. 47).	5	4																																														
100 + 01.14	NEW 12" X 18' R.C.P. CONSTRUCT DROP INLET LT. (SEE SHEETS NO. 41 & 43).	4	4							18									3.00	1	1					0.40								95																	
																										0.60					28		25																
100 + 45 ± 101 + 00	REMOVE 30 LIN. FT.. FENCE LT. RECONSTRUCT AFTER DISCONTINUING DETOUR.																																															
102 + 88.44	NEW 42" X 185' R.C.P. (EXTRA STRENGTH).	937	830																																														
101 + 35 ± 102 + 00	REMOVE 86' ± SEWER PIPE. PLUG END OF PORTION REMAINING IN PLACE.																189																																
101 + 67 ± 102 + 47 ±	CONSTRUCT ISLAND RT. (SEE SHEETS NO. 2 & 16).					65																																										
																											3.96																							
	SIDEWALK LEFT																																															
91 + 10																																																
96 + 83.73	CONSTRUCT SIDEWALK..																											43.86																						
98 + 14.49	CONSTRUCT SIDEWALK ON WALL.																											7.69																						
100 + 00.15	CONSTRUCT SIDEWALK ON WALL.																											6.43																						
102 + 88.44	CONSTRUCT SIDEWALK..																											22.83																						

S1506

107-V3689