

MANHOLE SCHEDULE

MH. #	C STATION	COORDINATES		TMH ELEV	INVERT ELEVATIONS	
		NORTHING	EASTING		IN	OUT
45	23+00.00 (GILCREASE AVENUE)	26817870.3540	736712.0837	2817.7±	2810.62	2810.62
46	20+07.72 (GILCREASE AVENUE)	26817874.3815	736419.8271	2828.1±	2821.14	2820.94
47	11+20.82 (GARDEN ROCK ST.) 11+47.69 (FALLOWDEER AVE.)	26817998.5135	736590.7288	2825.0±	2816.81	2816.61
48	11+81.98 (GARDEN ROCK ST.) 10+19.83 (WILDERD AVENUE)	26818061.5504	736590.2915	2822.2±	2815.20	2815.00
49	12+85.52 (GARDEN ROCK ST.) 11+58+50 (KALAHARI AVENUE)	26818160.3695	736569.4172	2824.1±	2816.11	2815.91
50	14+23.52 (GARDEN ROCK ST.) 10+10.00 (KUDDO AVENUE)	26818298.3662	736568.4598	2824.0±	2817.00	2816.80
51	15+15.46 (GARDEN ROCK ST.) 10+05.00 (TONYVILLE AVE)	26818390.2972	736567.8221	2822.7±	2815.70	2815.50
52	15+83.52 (GARDEN ROCK ST.) 11+22.50 (MARKHORN AVE.)	26818458.3623	736567.3499	2824.3±	2817.30	2817.10
53	15+26.20 (GARDEN ROCK ST.)	26818501.0421	736567.0538	2824.7±	-----	2817.70
54	11+57.18 (WILDERD AVE.) 9+95.14 (EDMONTON ST.)	26818059.8012	736727.6370	2818.5±	2810.41	2810.21
55	11+86.98 (WILDERD AVE.) 11+17.67 (DESERTDEER ST.)	26818059.4218	736757.4333	2817.2±	2809.15	2808.95
56	13+17.18 (WILDERD AVE.) 9+95.31 (DRYDUST ST.)	26818057.7637	736887.6241	2812.1±	2804.51	2804.31
57	13+46.98 (WILDERD AVE.) 11+17.84 (DESERTBUCK ST.)	26818057.3843	736917.4204	2811.0±	2803.19	2802.99
58	10+10.00 (DESERTBUCK ST.)	26817949.5525	736915.9344	2811.0±	-----	2804.00
59	10+10.00 (DESERTDEER ST.)	26817951.7573	736755.9496	2817.2±	-----	2810.20
60	11+12.50 (EDMONTON ST.)	26818177.1465	736729.2541	2818.4±	-----	2811.11
61	11+12.50 (DRYDUST ST.)	26818174.9418	736889.2389	2812.1±	-----	2805.22
62	10+10.00 (SOLIDHORN ST.)	26818273.3001	736889.5943	2810.1±	-----	2803.31
63	10+10.00 (PRONGHORN ST.)	26818275.5306	736729.6098	2816.0±	-----	2809.00
64	10+10.00 (MARKHORN AVE.)	26818457.5472	736449.8527	2827.0±	-----	2820.00
65	10+10.00 (KUDDO AVE.)	26818297.5510	736450.9627	2826.1±	-----	2819.10
66	10+10.00 (KALAHARI AVE.)	26818159.3393	736420.9208	2825.1±	-----	2818.10
67	10+10.00 (FALLOWDEER AVE.)	26817997.5583	736453.0439	2824.5±	-----	2817.64
68	11+68.35 (TONYVILLE AVE.) 10+00.00 (RAM ST.) 11+22.50 (PRONGHORN ST.)	26818388.0200	736731.1600	2816.0±	2808.33	2808.13
69	13+28.35 (TONYVILLE AVE.) 10+00.00 (RAMCHARGER ST.) 11+22.50 (SOLID HORN ST.)	26818385.7894	736891.1445	2810.3±	2802.63	2802.43
70	10+24.72 (RAMCHARGER ST.)	26818410.6153	736883.7980	2810.6±	2802.96	2802.76
71	10+24.72 (RAM ST.)	26818412.8458	736723.8136	2816.7±	2808.66	2808.46
72	11+12.50 (RAM ST.)	26818500.6162	736725.0373	2816.1±	-----	2809.19
73	11+12.50 (RAMCHARGER ST.)	26818498.3857	736885.0218	2810.4±	-----	2803.49

QUANTITY ESTIMATE

PROJECT: 6177 ANTELOPE UNIT 2 ACRES: 8.86±
 LOCATION: HUALAPAI WAY / GILCREASE AVE.
 NUMBER OF LOTS: 110 CALCULATED BY: ESI

ITEM	DESCRIPTION	PUBLIC		PRIVATE	
		QUANTITY	UNIT	QUANTITY	UNIT
1	4" SEWER SERVICE LATERALS TO LOTS	~	LF	1690	LF
2	8" SEWER	3314	LF	~	LF
3	12" SEWER	~	LF	~	LF
4	SEWER	~	LF	~	LF
5	SEWER MANHOLES UNDER 6 FEET	~	EA	~	EA
6	SEWER MANHOLES OVER 6 FEET	29	EA	~	EA
7	SEWER MANHOLE ADJUSTMENTS	~	EA	~	EA
8	6" WATER MAIN	1240	LF	~	LF
9	8" WATER MAIN	824	LF	~	LF
10	10" WATER MAIN	~	LF	~	LF
11	12" WATER MAIN	~	LF	~	LF
12	WATER MAIN	~	LF	~	LF
13	WATER SERVICE TO LOTS	110	EA	~	EA
14	FIRE HYDRANT	4	EA	~	EA
15	FIRE HYDRANT RELOCATION	~	EA	~	EA
16	CURB & GUTTER (TYPE "L", "A" AND "ROLL")	600	LF	~	LF
17	VALLEY GUTTER (8" WD)	~	SF	~	SF
18	DRIVEWAY	8250	SF	~	SF
19	SIDEWALK (4")	600	SF	~	SF
20	HANDICAP RAMP	2	EA	~	EA
21	SIDEWALK UNDERDRAIN	2	EA	~	EA
22	TYPE I GRAVEL BASE	489	CY	~	CY
23	TYPE II GRAVEL BASE	271	CY	~	CY
24	2" ASPHALTIC CONCRETE PAVING	~	SY	~	SY
25	3" ASPHALTIC CONCRETE PAVING	2467	SY	~	SY
26	4" ASPHALTIC CONCRETE PAVING	~	SY	~	SY
27	OPEN GRADE	~	SY	~	SY
28	POWER TO LOTS	110	EA	~	EA
29	TELEPHONE TO LOTS	110	EA	~	EA
30	PULLBOX	1	EA	~	EA
31	STREETLIGHT (STANDARD BASE)	4	EA	~	EA
32	STREETLIGHT (BREAKAWAY BASE)	~	EA	~	EA
33	SURVEY MONUMENTS	1	EA	~	EA
34	FLOOD CONTROL	~	LS	~	LS
35	EXCAVATION & EMBANKMENT	~	CY	~	CY
36	MISC. TRENCHING	~	LS	~	LS
37	TRAFFIC SIGNAL	~	LS	~	LS
38	STREET / STOP SIGNS	1	EA	~	EA
39	GAS TO LOTS	110	EA	~	EA
40	CABLE TO LOTS	110	EA	~	EA
41	MISCELLANEOUS	~	EA	~	EA

GREYSTONE HOMES
 CITY OF LAS VEGAS, NEVADA
 3785 E. SUNSET #B1
 LAS VEGAS, NEVADA 89120
 (702) 498-7700

QUANTITIES SHEET
 ANTELOPE UNIT 2

DRAWN BY: KCH AUG 2003
 DESIGNED BY: KCH AUG 2003
 CHECKED BY: CZ AUG 2003
 PROJECT NO: 6362-2 SCALE: N/A
 HORIZ. N/A
 VERT. N/A

PROFESSIONAL ENGINEER - STATE OF NEVADA
AARON M. MAMACHUKA
 CIVIL
 No. 75079
 EXP. 6/30/04
 1/24/04

SHEET **C4**
 4 OF 25 SHEETS
 DRAWING NO. **10744781-2**

Avoid cutting underground utility lines. It's costly.
Call before you Dig
 1-800-227-2600

Avoid overhead power line contact. It's costly.
Call before you Overhead
 1-702-593-6111