



- SEWER CONSTRUCTION NOTES**
1. 48" SANITARY SEWER MANHOLE, PER DCS SD-1.
  2. INSTALL SEWER LINE IN TRENCH SECTION, PER DCS SD-16.
  3. PROVIDE LOCKING MANHOLE COVER & COLLAR, PER DCS SD-3 & SD-3A.
  4. SANITARY SEWER DEEP MANHOLE, SEE DETAIL ON C-16.
  5. SANITARY SEWER DROP MANHOLE, PER DCS SD-8. 4" LOCK LINED.
- (DESIGN AND CONSTRUCTION STANDARDS FOR WASTEWATER COLLECTION SYSTEMS = DCS)

ALL SEWER PIPE MAIN  
8" SDR-35 PVC

SEWER AS-BUILT  
UNDERGROUND, IN  
11-23-04

Call before you Dig.  
1-800-227-2600  
UNDERGROUND UTILITY LOCATING SERVICE

1-702-593-6111

**3205 ZONE RESERVOIR EXPANSION**

**OFF-SITE SEWER PLAN**

LAS VEGAS VALLEY WATER DISTRICT

G.C. WALLIACE, INC.  
Engineers/Planners/Surveyors  
1855 SOUTH RAINBOW BLVD., LAS VEGAS, NEVADA 89146  
TELEPHONE: (702) 884-2660 • FAX: (702) 884-2289

VERIFY SCALE  
1/2" = 0' 1/2"

BAR REPRESENTS ONE AND ONE-HALF INCHES ON ORIGINAL

GRAPHIC SCALE  
1" = 150.0' (1:150)  
1" = 450.0' (1:450)

REVISIONS:

|          |                    |                |
|----------|--------------------|----------------|
| DATE     | BY                 | REVISION       |
| 08/19/02 | R. A. BERGER       | DRAWN          |
| 08/19/02 | M. W. MAIZE        | CHECKED        |
| 3/18/04  | L. STEVEN ANDERSON | RECOMMENDED BY |
| 3/18/04  | L. STEVEN ANDERSON | ACCEPTED BY    |
| 3/18/04  | L. STEVEN ANDERSON | DATE           |
| 3/18/04  | L. STEVEN ANDERSON | DATE           |

DESIGN MANAGER: rberger  
10:40:20 02-24-04

CONTRACT NUMBER  
**C1046**

DRAWING NUMBER C6  
SHEET 12 OF 95

REVISED OFF-SITE SEWER ALIGNMENT AND PROFILE  
1046C06.DWG Plot @ XX/XX/XX XX:XX