

A. 8721 Millsboro

Reenie Benbow 01/05/90



INSTALLATION CARD

WESTERN ONE KOTE STUCCO SYSTEM  
WESTERN STUCCO PRODUCTS CO. INC.



Job Address:

8721 Millsboro  
Las Vegas, NV 89128  
6017 Sgt. Lot 78

ICBO Evaluation Service, Inc.  
Report No. 3899

Date of Job Completion

12-28-88

Plastering Contractor


Name: NEVADA STATE PLASTERING

Address: 4224 Losee Road, Suite G • North Las Vegas, NV 89030

Telephone Number 649-8822

Approved Contractor License Number as  
Issued by Western Stucco Products 49

This is to certify that the plastering system on the building exterior at the above address has been installed in accordance with the evaluation report specified above and the manufacturer's instructions.

  
Signature of authorized representative of plastering contractor

Date

Installation card must be presented to the building inspector after completion of work and before final inspection.

No 018868

Reenie Benbow

01/05/90

## Builders Insulation Statement

**CertainTeed**

Sep 21 Job 6017

8721 Millsboro Dr.

## InsulSafe III®

Model 4121

Insul-Safe III® has been installed with the manufacturer's recommendations to provide a value of R 30 using 27 bags of insulation to cover 1143 square feet of area at a minimum thickness of 1 1/2 inches.

Debbie Booth

Insulation Contractor (Sign)

Company Name

Date

Builder (Sign)

Company Name

Date

### Batts and Blanket

| R Value | Insulation Thickness |
|---------|----------------------|
| R-38    | 12"                  |
| R-30    | 10"                  |
| R-22    | 6 1/2"               |
| R-19    | 6 1/4"               |
| R-13    | 3 1/2"               |
| R-11    | 3 1/2"               |

Meets ASTM C 665, replacing Federal Specification HH-I-521F.

Fiber glass batts or rolls have been installed in accordance with the manufacturer's recommendation to provide an R-value of 30 in the ceiling 13 in the exterior walls, N/A in the floor or crawl space perimeter. R-30 in the walls.

Debbie Booth

Insulation Contractor (Sign)

Company Name

Date

Builder (Sign)

Company Name

Date

**CertainTeed Corporation**  
P.O. Box 860, Valley Forge, PA 19482

Code No. 30-24-092

### Thermal Performance — Attic Blowing Application

- In accordance with the chart below, you must install the minimum number of bags per 1,000 sq. ft. of net area for each R-Value listed.
- The maximum net coverage must not exceed that specified for each R-Value.
- The installed insulation must be at or above the specified minimum thickness for each R-Value.
- Failure to install the required minimum weight per sq. ft. of insulation at or above the minimum thickness will result in reduced R-Value.
- This product should not be mixed with other blown insulations or the thermal claims will become invalid.

"R" means resistance to heat flow. The higher the R-Value, the greater the insulation power. To get the marked R-Value, it is essential that this insulation be installed properly. If you do-it-yourself, get instructions and follow them carefully. Instructions do not come with this package.

**CAUTION: RECESSED LIGHT FIXTURES—TO PREVENT OVERHEATING, DO NOT INSULATE ON TOP OR WITHIN 3" OF SUCH DEVICES. DOES NOT APPLY TO TYPE IC LIGHT FIXTURES OR TO FLUORESCENT FIXTURES WITH THERMALLY PROTECTED BALLASTS.**

| R-VALUE<br>To obtain a thermal resistance (R) of: | BAGS PER 1000 SQ. FT.<br>Bags per 1000 sq. ft. of net area: | MAXIMUM SQ. FT. PER BAG<br>Contents of bag should not cover more than: (sq. ft.) | MINIMUM WEIGHT POUNDS PER SQ. FT.<br>Weight per sq. ft. of installed insulation should not be less than: (lbs.) | MINIMUM THICKNESS<br>Should not be less than: (inches) |
|---------------------------------------------------|-------------------------------------------------------------|----------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------|--------------------------------------------------------|
| R-49                                              | 34.3                                                        | 29                                                                               | .858                                                                                                            | 19 1/4"                                                |
| R-44                                              | 31.1                                                        | 32                                                                               | .778                                                                                                            | 17 3/4"                                                |
| R-38                                              | 26.6                                                        | 38                                                                               | .665                                                                                                            | 15 1/2"                                                |
| R-30                                              | 20.8                                                        | 48                                                                               | .521                                                                                                            | 12 1/2"                                                |
| R-26                                              | 18.1                                                        | 55                                                                               | .452                                                                                                            | 11"                                                    |
| R-22                                              | 15.0                                                        | 67                                                                               | .374                                                                                                            | 9 1/4"                                                 |
| R-19                                              | 13.2                                                        | 76                                                                               | .330                                                                                                            | 8 1/4"                                                 |
| R-13                                              | 9.0                                                         | 111                                                                              | .225                                                                                                            | 5 3/4"                                                 |
| R-11                                              | 7.4                                                         | 136                                                                              | .184                                                                                                            | 4 3/4"                                                 |

R-Values are determined in accordance with ASTM C 687 and C 518. Conforms to ASTM C 764 which replaces Federal Specification HH-I-1030B.

### Framing Adjustment

To compensate for framing members the number of bags per 1000 sq. ft. of net area should be reduced as follows:

| Joist Size | Bags to Deduct / 1000 sq. ft. Joists 16" O.C. | Bags to Deduct / 1000 sq. ft. Joists 24" O.C. |
|------------|-----------------------------------------------|-----------------------------------------------|
| 2" x 4"    | .7                                            | .5                                            |
| 2" x 6"    | 1.0                                           | .7                                            |
| 2" x 8"    | 1.3                                           | .9                                            |
| 2" x 10"   | 1.6                                           | 1.0                                           |

© 1989 CertainTeed Corporation 4/89