

GENERAL NOTES

1. All construction shall be in accordance with the standard drawings and "Uniform Standard Specifications for Public Works Construction", issue of January, 1966, of the Clark County area, Nevada, unless otherwise specified by note on the plans or as directed by the engineer.
2. All utility companies shall be notified by the contractor at least 48 hours prior to beginning construction.
3. The owning utility company shall be responsible for the removal or relocation of all power poles, telephone poles, jointly-owned poles and relative appurtenances that interfere with required improvements as shown on the plans, and in accordance with CLV Std. Dwg. 440, 441, & 400.
4. The Las Vegas Valley Water District shall be responsible for the removal or relocation of all water meters that interfere with required improvements as shown on the plans and in accordance with CLV Std. Dwg. 5005.
5. The Southwest Gas Company shall be responsible for the removal or relocation of all gas lines and relative appurtenances that interfere with required improvements as shown on the plans.
6. The contractor shall be responsible for the vertical adjustment of all sanitary sewer manholes to the required finish grade as shown on the plans and in accordance with Section 512 of the "Uniform Standard Specifications for Public Works Construction".
7. All barricading and temporary traffic control devices or methods to be used during construction shall be done in accordance with the City of Las Vegas "Traffic Barricade Manual", issue of July, 1966, with current revisions, available from the Division of Traffic Engineering, 221 Las Vegas Blvd. No.
8. Existing improvements, trees, shrubs, walls, fences, signs, structures, etc. within the street right-of-way that will interfere with construction shall be removed as directed by the engineer.
9. All replacement, reconstruction, or relocation of existing improvements, sprinkler systems, shrubs, fences, walls, signs, steps, sidewalks, driveways, etc. shall be done as directed by the engineer.
10. The contractor shall backfill, grade & clean-up all cut or fill slopes to meet existing conditions. Where lawns are existing the contractor shall re-seed and/or sod the affected area to achieve a condition equal to, or better than, conditions previously existing, except lawns existing within the street right-of-way.
11. Existing private owned mail boxes within the street right-of-way that will interfere with construction shall be removed and relocated by the property owners.
12. Adjustment of all water valve covers, other than those at fire hydrants, are the responsibility of the Las Vegas Valley Water District.
13. All water line to be installed under this contract shall be placed such that the top of pipe is not within 20 inches of subgrade as shown by line and grade herein or as directed by the engineer.

LEGEND

1. See CLV Std Dwg. D-1, D-1.1, D-1.2, and D-1.3 for standard legend symbols, except as shown below.
2. All abbreviations shown on the plans conform to Section 2 of the Uniform Standard Specifications.

	Required concrete curb and gutter.
	Existing asphaltic concrete curb to be removed.
	Existing concrete curb and gutter to remain in place except as noted.
	Existing concrete block wall to remain in place.
	Type of pipe and diameter shown on plans when known.
	Water or gas main valve.
	Existing Elevation Required Elevation
	City of Las Vegas
	Special Improvement District
	1 1/2" Temporary A.C. Pavement
	Gas Line, existing
	Water Line, existing
	Sanitary Sewer, existing
	Storm Sewer, required
	Existing A.C. to remain
	Telephone Conduit

SUMMARY OF APPROXIMATE QUANTITIES

ITEM NUMBER	DESCRIPTION	UNIT	QUANTITIES					
			RSU	CLV	CLVSD			TOTAL
121.118D	14"x23" Lo Hed RCP	LF	515					515
122.112	12" CMP 16 GA.	LF	34					34
122.218	18" PART CIRCLE CULVERT	LF	241					241
122.312	12" C.M.P. FLARED END SECTION	EA	1					1
125.204	4" A.C.P.	LF		865				865
201.100	REMOVE A.C. PAVEMENT	SY	237					237
200.120	REMOVE 24" CMP	LF	61					61
200.120	REMOVE 31"x50" CMAD	LF	50					50
200.120	REMOVE CONCRETE SIDEWALK	SF	680	65				745
200.120	REMOVE "L" TYPE CURB & GUTTER	LF	519	11				530
200.120	REMOVE COMMERCIAL DRIVEWAY	SF	448					448
333.400	BITUMINOUS PENETRATION TREATMENT	SY	43					43
200.120	REMOVE CATCH BASIN	EA	1					1
200.120	REMOVE ALLEY GUTTER	SF		216				216
201.100	EXCAVATION	CY	20389	222	2726			23337
201.100	SAWCUT	LF	3895	2812	639			7346
302.100	TYPE I GRAVEL BASE	CY	11896	16	2954			14866
302.200	TYPE II GRAVEL BASE	CY	5462	10	640			6112
333.100	BITUMINOUS FOG SEAL	SY	1750	2423	1353			3526
333.500	1/2" OPEN GRADE PLANT MIX	SY	99221	58564	3738			161523
334.000	VARIABLE A.C. OVERLAY	SY	9551					9551
334.901	A.C. CURB	LF	100					100
334.003	1-1/2" A.C. PAVEMENT	SY	2186					2186
334.004	2" A.C. PAVEMENT	SY			743			743
334.005	2-1/2" A.C. PAVEMENT	SY	472	2418	610			3500
334.006	3" A.C. PAVEMENT	SY	40707	16	3738			44461
340.014	24" "L" TYPE CURB & GUTTER	LF	136	31	7864			8031
340.013	18" "L" TYPE CURB & GUTTER	LF	10193					10193
340.114	CONCRETE SIDEWALK	SF	851	65	2180			3096
340.144	ISLAND CONCRETE	SF	13048					13048
340.226	COMMERCIAL DRIVEWAY	SF	512		2560			3072
340.319	VALLEY GUTTER	SF		279				279
340.326	ALLEY GUTTER	SF		216				216
500.200	DROP INLET	EA	3					3
500.300	OUTLET STRUCTURE	EA	1					1
500.500	JUNCTION BOX	EA	2					2
512.120	ADJUST MANHOLE	EA		1				1
530.100	BARRICADE	LF		64				64
560.500	FIRE HYDRANT	EA		5				5
340.1446	GREEN COLOR COATING FOR CONC. MEDIAN IS.	SF		13048				13048
340.144	adjust pull boxes	EA		2				2
334.0036	Green Color Coating For Asphalt Surfaced Median Island	SY		3217				3217
334.903	1-1/2" A.C. Island Pavement	SY	3217					3217

CITY OF LAS VEGAS NEVADA			
DEPARTMENT OF PUBLIC WORKS			
SERVICES DIVISION			
Decatur - Sahara to Charleston			
Oakley - 700'w/Decatur to 1400'e/Deca.			
W.O. NO. 7610	F.B.K. NO.	DATE	DRAWING NO.
SC. (H)	SC. (V)	05.03.70	107V-737
DES. G. BILLINGSLEY		7/28/69	FILE NO.
DR. GAPPY			
APPROVED BY DIRECTOR OF PUBLIC WORKS			
			SHEET 2 OF 37