

QUANTITIES

SHEET NO. →

6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET																		
					6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
1		3" AC PAVEMENT	SY	103,673	4,110	3,866	4,784	5,712	5,132	5,333	2,912	5,960	6,512	5,540	4,169	5,425	5,078	6,400	6,400	6,400	6,108	6,400	6,812
2		TYPE 2 GRAVEL BASE (4")	CY	13,348	540	542	629	767	677	704	382	790	856	734	554	713	725	871	845	872	879	845	918
3		STD. 24" L TYPE CURB & GUTTER	LF	38,434	1,497	1,396	1,750	2,142	1,888	2,000	1,055	2,291	2,390	2,124	1,632	2,071	1,869	2,374	2,400	2,382	2,409	2,400	2,364
4		4' CONCRETE SIDEWALK	SF	27,480	6,200	5,040	7,280	8,960															
5		5' CONCRETE SIDEWALK	SF																				
6			SF																				
7		8' CONCRETE SIDEWALK	SF	125,440						7,680	8,000	4,320	9,280	9,120	8,640	6,720	8,480	6,880	9,120	9,600	9,280	9,440	9,600
8		10' CONCRETE VALLEY GUTTER	SF	4,964		290																	1,014
9		CONCRETE DRIVEWAY	SF	615		615																	

WATER:

1		8" ACP WATER MAIN	LF	2829			11	64				16	86	70			102	73	142	113	207	493
2		10" ACP WATER MAIN	LF	4493			977	1175					828	667						81	11	754
3		12" ACP WATER MAIN	LF	8893								1,181	365		901	1,122	192	1,207	1,192	1,182	1,193	353
4		8" GATE VALVE W/BOX	EA	30			2	2				1	3	2			2	3	3	3	3	6
5		10" GATE VALVE W/BOX	EA	6									1							1	1	4
6		12" GATE VALVE W/BOX	EA	10								1	1		1		2		2	2	1	4
7		6" ACP WATER MAIN	LF	675									60	493	120							
8		6" GATE VALVE W/BOX	EA	6								2	1	1	2							
9		2" WATER METER	EA	51	1		2	2	4	1	4	4	5	2	4	3	1	4	3	4	4	3
10		3" WATER METER	EA	3								1	1								1	
11		6x3 FNCT	EA	3									1									
12		4" WATER METER	EA	1								1	1									

SEWER:

1		48" MANHOLE	EA	58	4	3	5	4				4	2	3	4	5	1	3	4	3	5	4	3	1
2		8" PVC SEWER MAIN	LF	12,065	806	728	1030	76			897	570	589	1,271	1,191		215	1050	1,223	1,292	831	1,218	1,200	280
3		10" PVC SEWER MAIN	LF	4275				1194													461	1,218	1,200	202
4		12" PVC SEWER MAIN	LF																					
5		15" PVC SEWER MAIN	LF																					
6		24" RCP SEWER MAIN	LF																					
7		27" RCP SEWER MAIN	LF																					

STREET LIGHTS:

1	⊙	100 WATT HPS LUMINAIRE	EA	110	4	4	6	7	6	5	4	7	4	6	5	6	6	6	7	7	7	6	7
2	⊙	250 WATT HPS LUMINAIRE	EA																				
3	□	PULL BOX	EA	4	1								1								1		

MISCELLANEOUS:

1		19" x 30" LOW HEAD CONC. PIPE	LF	368																			92
2		TYPE "A" DROP INLET L=15'	EA	8																			2
3		CONC. BUBBLER STRUCTURE (4x7' 10")	EA	4																			1
4		6" CONC. APRON	SF	108																			27

NOTE TO CONTRACTOR
 QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

JOB NO. 560.009 2-14-87

REVISIONS NO. DESCRIPTION DATE
 SHEET NO. → 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
 STREET IMPROVEMENTS:
 WATER:
 SEWER:
 STREET LIGHTS:
 MISCELLANEOUS:
 G.C. WALLACE, INC. Engineering/Architecture
 ESTIMATE OF QUANTITIES
 SHEET 3 OF 43 SHEETS
 1074-1248-1