QUANTITIES

REVISIONS NO	DESCRIPTION	DATE

SHEET NO. →	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET																		
1		3" AC PAVEMENT	SY	26,842	6,400	6,400	6,400	1,436												2,588	3618		
2		TYPE 2 GRAVEL BASE (4")	CY	7,014	860	857	899	217				429	545	458	736	703	708	597					
3		STD. 24" "L" TYPE CURB & GUTTER	LF	14,352	2,385	2,399	2,366	525				643	724	776	1,182	1,200	1,200	952					
4		4' CONCRETE SIDEWALK	SF																				
5		5' CONCRETE SIDEWALK	SF	32,500								2,900	3,500	4000	5700	6000	6000	4400					
6			SF																				
7		8' CONCRETE SIDEWALK	SF	29,360	9,280	9,360	8,960	1,760															
8		10' CONCRETE VALLEY GUTTER	SF	2,760				920							920			920					
9		5' GRAVEL SHOULDER - TYPE 2	CY	307																137	170		
10		4" AC PAVEMENT	SY	34,186								3,510	4,532	3,814	5,867	5,867	5,867	4,720					

WATER:

1		8" ACP WATER MAIN	LF	1070										200		288	310	266					
2		14" ACP WATER MAIN	LF	549			349	200															
3		8" GATE VALVE W/BOX	EA	15										2	1	3	5	3					
4		12" GATE VALVE W/BOX	EA	1			1																
5		6" ACP WATER MAIN	L.F.	45			45																
6		6" GATE VALVE W/BOX	EA.	1			1																
7		2" WATER METER	EA.	6			1							1		1	1	2					
8		10" GATE VALVE W/BOX	EA	2										1	1								
9		14" GATE VALVE W/BOX	EA	1				1															
10		14" x 12" REDUCER	EA	1			1																
11		10" ACP WATER MAIN	LF.	2498								625	725		405	743							

SEWER:

1		48" MANHOLE	EA	31	2		1	1	3	3	2	3	1	2	4	3	3	3					
2		8" PVC SEWER MAIN	LF	2406	1,198		385	229	16	135	127	24	8	58	55	71	79	24					
3		10" PVC SEWER MAIN	LF																				
4		12" PVC SEWER MAIN	LF	73					10									63					
5		15" PVC SEWER MAIN	LF	5342										834	1200	1200	1200	908					
6		21" RCP SEWER MAIN	LF	4068					1168	1200	1200	500											
7		24" RCP SEWER MAIN	LF	1339								600	739										
8		CONCRETE ENCASEMENT	LF	40																			
9		18" PVC SEWER MAIN																					

STREET LIGHTS:

1		100 WATT HPS LUMINAIRE	EA	23	7	6	8	2															
2		250 WATT HPS LUMINAIRE	EA	43								4	4	6	8	7	8	6					
3		PULL BOX	EA	3	1	1						1											

MISCELLANEOUS:

1		19"x30" LOW HEAD CONC. PIPE	LF	728		364	364																
2		TYPE "A" DROP INLET L=15'	EA	4		2	2																
3		CONC. BUBBLER STRUCTURE (4'x11' ID)	EA	2		1	1																
4		6" CONC. APRON	SF	62		31	31																

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

REV	DATE	DESCRIPTION
1	2/26/87	PAVED. SEWER QUANTITIES
2	4/7/87	REVISED QUANTITIES
3	1/15/87	REVISED PROJECT TITLE

RECOMMENDED 1-19-88 DATE
R.E. NO. 2143

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

R A HOMES
DESERT SHORES - PHASE 1
ESTIMATE OF QUANTITIES

SHEET 4 OF 43 SHEETS

JOB NO. 660.005 2-14-87

9/78 DIETERICH-POST 6532B

107Y-1248-1