

JOB NO. 701.028

8194 DIETERICH-POST 83328

NOTES:

- STREETS AND UTILITIES UNDER CONSTRUCTION BY OTHERS SEE SPECIFICATIONS SECTION 1028 FOR CONDITION OF SITE DURING CONSTRUCTION OF THIS CONTRACT. SITE WILL BE ROUGH GRADED TO WITHIN 6-INCHES OF FINISHED GRADE FOR THIS CONTRACT.
- SET VALVE BOXES AND OTHER SURFACE APPURTENANCES TO FINISHED GRADE AS SHOWN ON PROFILE.
- SEE DETAIL 2/11 FOR TYPICAL TRENCH SECTION.
- STA. 4+50 TO STA. 28+75 (SCHEDULE A). SEE SPECIFICATIONS FOR COMPLETION REQUIREMENTS. PROVIDE TEMPORARY TEST HEAD AT STA. 4+50, AND STA. 28+75.

VAULT LID
31'-0" E/ELEG.
VAULT MH.
23'-0" N/SFC

BLOW OFF
16'-0" N/SFC
20'-0" E/ELEG.
VAULT LID

PLAN

SCALE: 1" = 40'

PROFILE

SCALE: HORIZ. - 1" = 40'
VERT. - 1" = 4'



PIPE CURVE DATA				
CURVE	RADIUS	LENGTH	TANGENT	DELTA
A	2607.00	90.00	45.00	90° 58' 41"
B	1280.00	570.00	289.80	26° 30' 52"
C	1280.00	844.13	438.05	37° 47' 06"
D	2607.00	115.00	57.51	2° 31' 39"

ROADWAY CURVE DATA				
CURVE	RADIUS	LENGTH	TANGENT	DELTA
7	1265.00	579.39	294.87	26° 14' 33"
8	2622.00	140.44	70.24	3° 04' 08"

LAS VEGAS VALLEY WATER DISTRICT

PRESSURE TEST DATE 12-15-88
STATE HEALTH SAMPLE DATE 12-22-88
INSPECTOR DAVID MATHIS

DEL E. WEBB COMMUNITIES INC.

2745 ZONE PIPELINE PHASE II

PLAN & PROFILE

STA. 4+1500 TO STA. 11+00.00

SHEET

4

OF 13 SHEETS

CONTRACT NO. 504

565-165

G.C. WALLACE, INC.
Engineering/Architecture

1555 SOUTH RAINBOW BLVD. LAS VEGAS, NEVADA 89102

RECOMMENDED
DATE 6/15/88
R.E. NO. 6722
DATE 6/15/88
L. STEVEN ANDERSON
A. J. JORDAN
C. J. JORDAN
K. J. JORDAN
K. J. JORDAN

DESCRIPTION

REV

DATE