STRUCTURE LIST

FED. ROAD DIV NO	STATE	PROJECT NO	COUNTY	CONTROL SECTION	STATE ROUTE	SHEET NO	TOTAL SHEETS
7	NEVADA	I-015-1(31)41	CLARK	03-083		138	

M-7

SHEET NO.	ITEM NO	STATION	LINE	RT OR LT.	DESCRIPTION	DRAINAGE EXCAVATION	STRUCTURE EXCAVATION	BACKFILL	CABLE END ANCHOR	REINFORCED CONCRETE PIPE 18" CLASS III	18" CLASS V	24" CLASS III	24" CLASS V	30" CLASS III	36" CLASS III	48" CLASS III	18" PRECAST END SECTION	TYPE 4 MANHOLE	TYPE 4 MODIFIED MANHOLE	18" CMP (DIPPED)	10" STEEL PIPE (BLACK)	6" STEEL PIPE (BLACK)	6" GATE VALVE	STRUCTURAL STEEL GRATES	STRUCTURAL STEEL	FURNISHING STEEL PILES	DRIVING STEEL PILES	METAL PILE SPLICES	BRIDGE RAIL TYPE H	FINE SURFACE FINISH	6" ASBESTOS CEMENT PIPE CONDUIT	10" ASBESTOS CEMENT PIPE CONDUIT	HEADLIGHT GLARE SCREEN	STANDARD STEEL GUARDRAIL	DOUBLE METAL BEAM BARRIER RAIL	SINGLE METAL BEAM BARRIER RAIL	TEMP. PAINTED GUARDRAIL	MESH REINFORCEMENT (6"x6")	REINFORCING STEEL	CLASS A CONCRETE MAJOR	MINOR	SIDEWALK	DRIVEWAY	SCORED SHOULDER STRIP	TYPE 1 CURB AND GUTTER	TYPE 2 CURB AND GUTTER	TYPE 7 CURB AND GUTTER	SLOPE PAVING	PNEUMATICALLY PLACED CONCRETE MORTAR (3")	PLANTMIX SHOULDER DIKE
36	104		ES		RAMP ES OVERCROSSING, FINE SURFACE FINISH.																										876																					
	* 105	12+39 14+83	ES	RT.	GUARDRAIL.				1																										252.0																
	106	12+41 19+50	ES	LT.	TYPE I CURB AND GUTTER.																																						709							
	107	15+75 17+10	ES	RT.	PLANTMIX DIKE.																																														135
	108	12+22 17+10	ES	RT.	SCORED CONCRETE SHOULDER STRIP.																																					488							
	109	4+75 8+94	ES	RT.	GUARDRAIL.																														419.0															
	110	4+75 9+15	ES	RT.	SCORED CONCRETE SHOULDER STRIP.																																					440							
	111	4+75 6+75	ES	RT.	PLANTMIX DIKE.																																														200
	112	13+00 14+75	SW	RT.	GUARDRAIL.				1																										177.0																
	113	5+32 9+00	ES	LT.	TYPE I CURB AND GUTTER.																																						368							
	* 114	7+00 9+02	ES	LT.	GUARDRAIL.				1																										202.0																
	* 115	4+50 5+26	NE	RT.	GUARDRAIL.				1																										76.0																
	116	4+50 12+00	NE	RT.	SCORED CONCRETE SHOULDER STRIP.																																					750							
	117	4+50 12+00	NE	RT.	PLANTMIX DIKE.																																														717
	* 118	5+98 12+00	NE	LT.	GUARDRAIL.				2																										666.9																
	119	4+69 11+85	NE	LT.	TYPE I CURB AND GUTTER.																																						786							
	120	7+00 15+00	NW	RT.	PLANTMIX DIKE.																																														800
	121	7+00 15+00	NW	RT.	SCORED CONCRETE SHOULDER STRIP.																																					800							
	122	17+44 to 17+94 & 10+47 to 10+97	SW NW	RT. LT.	TYPE 7 CURB AND GUTTER																																								103				
	123	13+00 17+44	SW	RT.	SCORED CONCRETE SHOULDER STRIP.																																					457							
	124	13+00 22+29	SW	LT.	TYPE I CURB AND GUTTER.																																						929							
	125	2+50 9+15	WS	LT.	TYPE I CURB AND GUTTER.																																						668							
	126	7+00 10+47	NW	LT.	TYPE I CURB AND GUTTER.																																						347							
	1	4+90	WS		10" x 34' ACP CONDUIT.																											34																			
	3	13+25	ES		10" x 34' ACP CONDUIT.																											34																			
	4	10+55	NE		10" x 34' ACP CONDUIT.																											34																			
	6	11+50	NW		6" x 55' ACP CONDUIT.																										55																				
	7	7+00	ES		6" x 34' ACP CONDUIT.																										34																				
37	* 101	3+42 8+93	SW	LT.	GUARDRAIL.				1																										552.0																
		16+00	SE	LT.																																															
	102	8+95 16+00	SW	LT.	TYPE I CURB AND GUTTER.																																						957							
	104	19+50 16+00	SE	RT.	PLANTMIX DIKE.																																														350
	* 105	29+00 22+09 to	SE	RT.	GUARDRAIL.																														1300.0																
	106	22+59 & 5+39 to 5+89	SE SW	LT. RT.	TYPE 7 CURB AND GUTTER.																																								106				
	107	25+00 29+00	SE	RT.	PLANTMIX DIKE.																																														400
	108	16+00 29+00	SE	RT.	SCORED CONCRETE SHOULDER STRIP.																																					1300							
	* 109	6+90 8+92	SW	RT.	GUARDRAIL.				1																										202.0																
	110	5+89 9+05	SW	RT.	SCORED CONCRETE SHOULDER STRIP.																																					330							
	111	10+77 13+00	SW	RT.	SCORED CONCRETE SHOULDER STRIP.																																					230							
	112	10+90 13+00	SW	LT.	TYPE I CURB AND GUTTER.																																						210							
	* 113	10+88 13+00	SW	RT.	GUARDRAIL.																														212.0																
	114	1+75 11+50	WN	RT.	SCORED CONCRETE SHOULDER STRIP.																																					975							
	115	1+74 11+42	WN	LT.	TYPE I CURB AND GUTTER.																																						1041							
		~~[illegible]~~			59038																																														

138

09N3833

DESIGN DEPARTMENT

	BY	DATE
DESIGN		
DRAWING		
TRACING		
CHECKED BY		
DATE		