

58913

ESTIMATE OF QUANTITIES
Freeway Station 425+79 to 504+49
Expressway Station 85+69 to 124+23
Quantities Shown are Approximate Only and are Subject to Increase or Decrease
TO BE CONTRACTED

ITEM NO.	I-015-1(31)41,F-006-1(23)	TOTAL	UNIT	ITEM
509 0485	1	1	each	48-inch Precast Reinforced Concrete Manhole, Type 4 Modified
511 0110	436	436	cu yd	Class A Concrete Slope Pavement
513 1301	16,970	16,970	lin ft	Class A Concrete Curb and Gutter (Type 1)
513 1302	2,180	2,180	lin ft	Class A Concrete Curb and Gutter (Type 2)
513 1307	2,100	2,100	lin ft	Class A Concrete Curb and Gutter (Type 7)
513 1404	540	540	sq yd	Class A Concrete Sidewalk (4-inch)
513 1506	50	50	sq yd	Class A Concrete Driveway (6-inch)
513 1706	13,510	13,510	lin ft	Class A Concrete Scored Shoulder Strip (6-inch)
516 2720	11,490	11,490	lin ft	72-inch Chain Link Fence
516 5100	5	5	each	10-foot Metal Drive Gate
518 0100	23,640	3,580	lin ft	Painted Guardrail
518 0101	402	402	lin ft	Temporary Painted Guardrail
518 0300	150	150	lin ft	Reconstruct Guardrail
518 1100	2,218	769	lin ft	Painted Metal Beam Barrier Rail (single)
618 1300	1,620	3,084	lin ft	Painted Metal Beam Barrier Rail (Double)
618 9400	47	9	each	Cable End Anchor
619 0100	273	273	each	Culvert Markers and Guide Posts
621 0100	8	8	each	Reference Monuments
623 0300	Lump Sum	Lump Sum	Lump Sum	Traffic Signal and Highway Lighting System
624 0200	8,500	100	hr	Flagman
625 0110	497	497	sq ft	Rent Construction Signs
625 0111	120	120	lin ft	Rent Construction Barricades (Class 1)
625 0113	60	60	each	Rent Construction Barricades (Class 2)
626 0110	72	68	sq ft	Temporary Signs
626 0111	400	400	lin ft	Temporary Barricades (Class 1)
627 0110	978	978	sq ft	Permanent Signs (Metal Supports)
627 0120	255	255	sq ft	Permanent Signs (Timber Supports)
627 0130	4,657	800	sq ft	Permanent Sign Panels (Overhead)
627 0135	Lump Sum	Lump Sum	Lump Sum	Permanent Overhead Sign Support Structures
628 0100	Lump Sum	Lump Sum	Lump Sum	Mobilization
632 0100	2,730	3,110	lin ft	Headlight Glare Screen
633 0100	5,650	1,880	each	Non-Reflective Pavement Markers
633 0200	470	160	each	Reflective Pavement Markers
637 0100	112	112	ton	Dust Palliative

FED. RD. REG. NO.	STATE	PROJECT NO.	COUNTY	CONTROL SECTION	STATE ROUTE	SHEET NO.	TOTAL SHEETS
7	NEVADA	I-015-1(31)41 F-006-1(23)	CLARK	03-083	03-065	12-A	Ref. Sh. B-6

107V3833