STATION	LOCATION	SIGN NO.	PANEL SIZE	AREA SQ. FT.	GROUND MOUNTED SIGNS: SUPPORT TYPE	NO. OF POSTS	TYPE	LENGTH	FOOTING LENGTH	POSTS - OVERHEAD SIGNS: NO. OF POSTS	LEFT: TYPE	"a" ELEV	"b" ELEV	RIGHT: TYPE	"a" ELEV	"b" ELEV	BOTTOM OF FRAME ELEV.	SIGN PANEL LETTER SIZE	REMARKS
CHARLESTON BLVD		M7-1	18"x 12"	1.50	C	1	3" PIPE	13'-3"	3'-0"										TRAILBLAZER ASSEMBLY
LAS VEGAS BLVD SEE SIGN LAYOUT		M6-1(S)	21"x 9"	1.32															
		G-7	21"x 18"	2.63															
		M4-1(RT)	21"x 15"	2.19															
MAIN ST. SEE SIGN LAYOUT		M7-1	18"x 12"	1.50	C	1	3" PIPE	13'-3"	3'-0"										TRAILBLAZER ASSEMBLY
		M6-1(S)	21"x 9"	1.32															
		G-7	21"x 18"	2.63															
		M4-1(RT)	21"x 15"	2.19															
102 + 70± CHAR	LT	M7-1	18"x 12"	1.50	LOCATE SIGN ASSEMBLY ON EXISTING LIGHT POLE.														TRAILBLAZER ASSEMBLY
		MG-1(S)	21"x 9"	1.32															
		G-7	21"x 18"	2.63															
		M4-3	21"x 15"	2.19															
91 + 70 CHAR	LT	G-26	9'-6"x 6'-6"	61.75	A	2	8x5¼ WF 17.0#	12'-9"	4'-6"									24" SHIELD, 10" CAPS, 10" CAPS	
88 + 90± CHAR	℄	R4-7	24"x 30"	5.00	C	1	2½" PIPE	11'-3"	3'-0"										
		R3-2	24"x 30"	5.00															
85 + 70± CHAR	℄	MG-1(S)	21"x 9"	1.32	C	1	3" PIPE	12'-3"	3'-0"										
		G-7	21"x 18"	2.63															
		M4-1(LT)	21"x 15"	2.19															
83 + 60 CHAR	RT	M7-1	18"x 12"	1.50	C	1.	3" PIPE	13'-3"	3'-0"										TRAILBLAZER ASSEMBLY
		M6-1(S)	21"x 9"	1.32															
		G-7	21"x 18"	2.63															
		M4-1(RT)	21"x 15"	2.19															
HIGHLAND DR																			
120 + 00 HD	LT	R3-7(LT)	30"x 30"	6.25	C	1	3" PIPE	11'-6"	3'-0"										
121 + 00 HD	RT	W27R	36"x 36"	9.00	C	1	3" PIPE	13'-3"	3'-0"										
122 + 50 HD	LT	W27R	36"x 36"	9.00	C	1	3" PIPE	13'-3"	3'-0"										
123 + 50 HD	LT	W21R	18"x 18"	2.25	C	1	2½" PIPE	11'-0"	3'-0"										SIGN LOCATED FACING WALL ST.
127 + 60 HD	℄	R4-7	24"x 30"	5.00	C	1	2½" PIPE	11'-6"	3'-0"										LOCATE SIGN IN CENTER OF MEDIAN FACING NBT
134 + 00 HD	LT	M7-1	18"x 12"	1.50	C	1	3" PIPE	13'-3"	3'-0"										
		M6-1(S)	21"x 9"	1.32															
		G-7	21"x 18"	2.63															
		M4-3	21"x 15"	2.19															
FREEWAY																			
401 + 00 FWY	MED.	W-55(R)	5'-0"x 5'-0"	25.00	A	1	6x6 WF 15.5#	13'-4"	3'-0"										
401 + 00 FWY	RT	W-55(R)	5'-0"x 5'-0"	25.00	A	1	6x6 WF 15.5#	13'-4"	3'-0"										
"B" 349+00 TO "B" 360+20	RT																		REMOVE BARRICADES AND RESET AT 410+50 Fwy TO 427+25 Fwy. RT (NO DIRECT PAYMENT)
"B" 359+25	LT																		REMOVE BARRICADES AND RESET AT 410+50 Fwy LT. (NO DIRECT PAYMENT)
410+50 Fwy TO 427+25 Fwy	RT																		6-12' BARRICADES (CLASS I)

*OVERHEAD

SUMMARY

TOTAL SIGN AREA (METAL SUPPORT) = 1402 Sq. Ft.
TOTAL SIGN AREA (OVERHEAD) = 755 Sq. Ft.
TOTAL LENGTH BARRICADE, CLASS I = 72 Lin. Ft.

GENERAL NOTES:

1. Footing Length shown for Type C Post is embedded length.
2. Pipe length shown for Type C Post includes embedded length.
3. All Interstate Route Shields are Interstate Nevada 15
4. For Frame Spans and Position of Overhead Signs on Roadway see Sign Layout Sheet.
5. "a" Elev. is Bottom of Base Plate Elevation.
6. "b" Elev. is Bottom of Footing Elevation

DE LEUW, CATHER & COMPANY

SCALE

DESIGNED BY

SIGN DATA SHEET
INSTALLATIONS 63 TO 77
LAS VEGAS FREEWAY

STATE OF NEVADA
DEPARTMENT OF HIGHWAYS

79

107V 3834

Ref. Sheet J-9

FED. ROAD DIV. NO.	STATE	PROJECT NO.	COUNTY	CONTROL SECTION	STATE ROUTE	SHEET NO.	TOTAL SHEETS
7	NEVADA	I-15-1 (25)50	CLARK	03-083		117	130