REMOVALS, CLEARING AND FENCING

FREEWAY STA. 361+72 TO 433+00

FED. ROAD DIV. NO.	STATE	PROJECT NO.	COUNTY	CONTROL SECTION	STATE ROUTE	SHEET NO.	TOTAL SHEETS
- 7 -	NEVADA	I-015-1(22)40	CLARK	03-083		125	130

SHEET NO.	ITEM NO	STATION	LINE	RT. OR LT.	DESCRIPTION	REMOVALS: CURB & GUTTER (LIN. FT.)	REMOVALS: CULVERT PIPE (LIN. FT.)	REMOVALS: CONCRETE SIDEWALK (SQ. YDS.)	REMOVALS: DROP INLETS (EA.)	CLASS "A" CONC.	ABANDON WELLS (EA.)	6' CHAIN LINK FENCE (LIN. FT.)	10' DRIVE GATES (EA.)	URBAN CLEARING (L.S.)	RECONSTRUCT FENCE (LIN. FT.)
17	14	430+50	FWY	L	REMOVE CONCRETE BLOCK BUILDING REMOVED REMOVED										
"	15	430+30	"	℄	REMOVE 5' CONCRETE MASONRY WALL REMOVED REMOVED										
"	16	430+50	"	R	REMOVE CONCRETE BLOCK BUILDING REMOVED REMOVED										
"	17	431+15	"	℄	REMOVE FRAME WOOD BUILDING REMOVED REMOVED										
"	18	431+00	"	R	REMOVE CONCRETE BLOCK BUILDING REMOVED REMOVED										
"	19	432+60	"	℄	REMOVE CONCRETE BLOCK BUILDING REMOVED REMOVED										
"	20	432+00	"	℄	REMOVE FRAME BUILDING REMOVED REMOVED										
"	21	432+35	"	℄	REMOVE SIDEWALK REMOVED REMOVED										
"	22	432+50	"	L	REMOVE CONCRETE BUILDING & SIGNS REMOVED REMOVED										
"	23	432+60	"	R	REMOVE SERVICE STATION APPURTENANCES REMOVED REMOVED									LS	
"	24	432+90	"	R	REMOVE CONCRETE SLABS									LS	
"	25	0+53 TO 1+53	Western	R	REMOVE VALLEY GUTTER	106									
"	26	0+84 TO 1+53	"	L	" " "	69									
"	27	85+30 TO 4+20	CHAR Western	R R	CONSTRUCT 30' PLANTMIX DETOUR WITH 6" TYPE I GRAVEL BASE AND 2" PLANTMIX SURFACE (EQUIPMENT HOURS)										
"	28	85+23	CHAR	R	REMOVE AND RELOCATE TRAFFIC SIGNAL POLE "E" BEFORE CONSTRUCTION OF DETOUR SEE SHEET No. 122										
"	31	88+90 TO 91+10	CHAR	R	REMOVE CURB GUTTER AND SIDEWALK.	235		122							
"	35	85+50 TO 91+10	CHAR	R	REMOVE EXISTING 24"x 560' CM.P AND R.C.P. AND DROP INLET (88+88 CHAR. 38' RT.)		560		1						
"	37	424+50 TO 432+95	FWY	L&R	REMOVE EXISTING FENCE WITHIN R.O.W. (NO DIRECT PAYMENT)										
"	38	AS NOTED	AS NOTED		131+20 WALL S.L. 40' L.T., 124+25 HD 39' R.T., 131+05 WALL S.L. 40' R.T., 130+55 HD 49' RT. - 10' METAL DRIVE GATES (STATE FORCES USE ONLY)								4		
					TOTAL	620	560	239	1		4	9612	9	LS	414
					USE	620	560	239	1		4	9612	9	LS	420

59320

STATE OF NEVADA
DEPARTMENT OF HIGHWAYS

107V3834 86

STRUCTURE LIST

REMOVALS, CLEARING & FENCING - 2

LAS VEGAS FREEWAY

DE LEUW, CATHER & COMPANY | SCALE ... DESIGNED BY. R.C.