STATION	LOCATION	SIGN NO.	PANEL SIZE	AREA SQ.FT.	GROUND MOUNTED SIGNS: SUPPORT TYPE	NO. OF POSTS	TYPE	LENGTH	FOOTING LENGTH	POSTS - OVERHEAD SIGNS: NO. OF POSTS	LEFT: TYPE	"a" ELEV	"b" ELEV	RIGHT: TYPE	"a" ELEV	"b" ELEV	BRACKET TRUSS	SIGN PANEL LETTER SIZE	REMARKS
SAHARA AVE.																			
9 + 05 SA	℄	R4-7	24" x 30"	5.00	C	1	2½" PIPE	11'-3"	3'-0"										SIGN ON MEDIAN FACING E. B. TRAFFIC
11+ 95 ± SA	LT.	R3-2	24" x 30"	5.00	LOCATE		SIGN ON	SIGNAL	POLE										SIGN ON MEDIAN FACING E. B. TRAFFIC
12 + 60 SA	LT.	R3-1	24" x 30"	5.00	C	1	2½" PIPE	11'-3"	3'-0"										SIGN FACING W. B. TRAFFIC
13 + 20 SA	℄	R4-7	24" x 30"	5.00	LOCATE		SIGN ON	SIGNAL	POLE										SIGN ON MEDIAN FACING E. B. TRAFFIC
13 + 55 SA	℄	R3-7(LT)	30" x 30"	6.25	C	1	3" PIPE	11'-3"	3'-0"										SIGN ON MEDIAN FACING E. B. TRAFFIC
15 + 22 SA	℄	R3-7(LT)	30" x 30"	6.25	C	1	3" PIPE	11'-3"	3'-0"										SIGN ON MEDIAN FACING W. B. TRAFFIC
15 + 25 SA	RT.	(I)M6-1(N)	21" x 9"	1.32	C	1	3" PIPE	13'-2"	3'-0"										ROUTE MARKER ASSEMBLY FACES E.B.T
		G-7	24" x 24"	4.00															
		(I)M4-1(LT)	21" x 15"	2.19															
15 x 62 ± SA	℄	R4-7	24" x 30"	5.00	LOCATE		SIGN ON	SIGNAL	POLE										R4-7 FACING W.B. TRAFFIC.
19 + 30 ± SA	LT.	(I)M6-1(S)	21" x 9"	1.32	C	1	4" PIPE	14'-2"	4'-0"										DOUBLE ROUTE MARKER ASSEMBLY FACING WEST BOUND TRAFFIC.
		G-7	24" x 24"	4.00															PLACE IN FRONT OF EXIST. LIGHT STD.
		(I)M4-3	21" x 15"	2.19															SIGN LOCATED ON LEFT OF POST
		(I)M6-1(N)	21" x 9"	1.32															
		G-7	24" x 24"	4.00															
		(I)M4-2(RT)	21" x 15"	2.19															SIGN LOCATED ON RIGHT OF POST
20 + 50 SA	LT.	G-11	12'-6" x 5'-0"	62.50	A	2	8"x5¼" WF 17.0#	11'-3"	4'-6"									TYPE B ARROW, 10.67" UC 8" LC	SIGN FACING W. B. TRAFFIC
38 + 00 SA	LT.	M7-1	18" x 12"	1.50	C	1	3" PIPE	12'-11"	3'-0"										LOCATE APPROX. NORTH OF TAM DR. FACING WEST BOUND TRAFFIC.
		G-7	21" x 18"	2.63															
		M4-3	21" x 15"	2.19															
DELETED																			
DELETED																			
RAMP RC																			
3 + 50 RC	LT	W55(RT)	60" x 60"	25.00	A	1	6"x6" WF 15.5#	13'-3"	3'-0"										
RAMP RD																			
4 + 70 ± RD	RT.	W52	48" x 60"	20.00	LOCATE		SIGN ON	LIGHT	STANDARD										30 M.P.H.
9 + 20 RD	RT.	G-13	13'-0" x 4'-0"	52.00	A	2	6"x6" WF 15.5#	10'-3"	4'-0"									10.67" UC 8" LC; 8" CAPS	
13 + 00 RD	RT	W3-3	36" x 36"	9.00	C	1	3" PIPE	13'-3"	3'-0"										
16 + 50 RD	RT.	G-12	16'-0" x 5'-0"	80.00	A	2	8"x5¼" WF 17.0#	11'-3"	4'-6"									SINGLE LINE TURN ARROW, 10.67" UC 8" LC; TYPE B ARROW @ 30°	
1 + 45 RD L	RT	R5-1	24" x 24"	4.00	LOCATE		SIGN ON	SIGNAL	STANDARD										SIGN ON ISLAND FACING & PARALLEL TO SAHARA AVENUE
FREEWAY																			
380 + 00 FWY	RT.	W4-1	48" x 48"	16.00	C	1	4" PIPE	15'-5"	4'-0"										SIGN FACING N. D. TRAFFIC.
381 + 75 FWY	RT.	R3-3	24" x 24"	4.00	C	1	2½" PIPE	11'-0"	3'-0"										SIGN FACING N. B. TRAFFIC.
382 + 60 FWY	LT.	G-5	6'-0" x 5'-0"	30.00	A	1	6"x6" WF 15.5#	11'-3"	3'-0"										LOCATE IN GORE, FACING S. B. TRAFFIC
387 + 94 FWY	LT.	G-14	14'-6" x 6'-6"	94.25	A	2	8"x6½" WF 24.0#	12'-9"	5'-0"									16" UC 12" LC; TYPE A ARROW, 45°	
392 + 50 FWY	RT.	(I)M6-1(N)	30" x 15"	3.13	C	1	4" PIPE	14'-3"	4'-0"										CONFIRMATORY ROUTE MARKER ASSEMBLY
		G-7	36" x 36"	9.00															
394 + 00 FWY	MED.	G-17	14'-0" x 8'-0"	112.00	A	2	8"x6½" WF 24.0#	15'-6"	5'-0"									16" UC 12" LC; 10" NUM. (FRACTION)	SIGN ON MEDIAN FACING N. B. TRAFFIC
396 + 00 FWY	RT.	G-17	14'-0" x 8'-0"	112.00	A	2	8"x6½" WF 24.0#	14'-3"	5'-0"									16" UC 12" LC; 10" NUM.	
397 + 50 FWY	LT.	(I)M6-1(S)	30" x 15"	3.13	C	1	4" PIPE	14'-3"	4'-0"										CONFIRMATORY ROUTE MARKER ASSEMBLY
		G-7	36" x 36"	9.00															
398 + 50 FWY	MED.	G-18	16'-6" x 5'-0"	82.50	A	2	8"x5¼" WF 17.0#	12'-0"	4'-6"									13.33" UC, 10" LC; 12" CAPS, 12" NUM.	SIGN ON MEDIAN FACING S. B. TRAFFIC
400 + 50 FWY	LT.	G-18	16'-6" x 5'-0"	82.50	A	2	8"x5¼" WF 17.0#	11'-3"	4'-6"									13.33" UC, 10" LC; 12" CAPS, 12" NUM.	
408 + 00 FWY	RT.	G-19S	18'-0" x 120"	180.00*						2	III	72.05	66.50	III	70.75	64.13	89.88	35" x 30" SHD, 12" NUM; 16" UC, 12" LC; 10" CAP	15" NUM; STANDARD DOWN ARROW.
		G-20 S	14'-0" x 120"	140.00*														16" UC, 12" LC; STD. DOWN ARROW	2 BALLAST BOXES
411 + 32 FWY	LT.	R3-3	24" x 24"	4.00	C	1	2½" PIPE	11'-0"	3'-0"										SIGN FACING S. B. TRAFFIC.
413 + 50 FWY	LT.	W4-1	48" x 48"	16.00	C	1	4" PIPE	15'-5"	4'-0"										SIGN FACING S. B. TRAFFIC
RAMP HS																			
1 + 10 HU	RT.	R1-2	36" x 36" x 36"	4.50	C	1	2½" PIPE	11'-9"	3'-0"										SIGN FACING HU TRAFFIC

*OVERHEAD

SUMMARY OF CULVERT MARKERS, WARNING & GUIDE POSTS

Type.	No.
Single White	93
Single Amber	163
Horizontal (W6IR)	11
Total	267
Hazard Markers	10

GENERAL NOTES:

1. Footing Length shown for Type C Post is embedded length.
2. Pipe length shown for Type C Post includes embedded length.
3. All Interstate Route Shields are Interstate Nevada 15
4. For Frame Spans and Position of Overhead Signs on Roadway see Sign Layout Sheet.
5. "a" Elev. is Bottom of Base Plate Elevation.
6. "b" Elev. is Bottom of Footing Elevation

Ref Sheet J-7

FED. ROAD STA. NO.	STATE	PROJECT NO.	COUNTY	CONTROL SECTION	STATE ROUTE	SHEET NO.	TOTAL SHEETS
7	NEVADA	I-015-1 (32) 106	CLARK	03-083		115	130

DE LEUW, CATHER & COMPANY ENGINEERS

SCALE

DESIGNED BY M.A.S.

STATE OF NEVADA
DEPARTMENT OF HIGHWAYS

77

SIGN DATA SHEET INSTALLATIONS 1 TO 33

LAS VEGAS FREEWAY

107V3834