

FED. ROAD DIST. NO.	STATE	PROJECT NO.	COUNTY	SHEET NO.	TOTAL SHEETS
7	NEVADA	-015-1 (22)40	CLARK	08-083	23

Reference Sheet No. E-4

- ① 0 + 00 RD to 3 + 00 RD, Rt., 387 + 94 Fwy. to 391 + 50 Fwy., Lt., 4' F.B. Ditch
- ② 387 + 50 Fwy. to 392 + 00 Fwy., Lt., Ditch from 392 + 00 Fwy. to 397 + 00 Fwy., Lt., 6' F.B. Ditch
- ③ 387 + 50 Fwy., 76' Lt., Precast End Section 18"x24" RCP, S = .0012, U.I.E. 57.73, L.I.E. 57.84
- ④ 387 + 50 Fwy., 6' Mod. Type 2 D.I., 1 opening, Ent. 59.49 P.C. Paved Approach Ditch Ditch dike, see sheet 45
- ⑤ 395 + 58 Fwy., 88' Lt., Precast End Sections Grouted riprap thru ditch.
- ⑥ 18"x24" RCP, S = .012, U.I.E. 52.44, L.I.E. 52.16
- ⑦ 395 + 58 Fwy., 63' Lt., Std. Type 3 D.I., G.E. 57.32
- ⑧ 18"x 60" RCP, S = .0126, U.I.E. 53.22, L.I.E. 52.45
- ⑨ 395 + 58 Fwy., 6' Mod. Type 2 D.I., 2 openings, Ent. 55.75, P.C. Paved Approach Ditches
- ⑩ 18"x 60" RCP, S = .0126, U.I.E. 54.00, L.I.E. 53.29
- ⑪ 395 + 58 Fwy., 63' Rt., Std. Type 3 D.I., G.E. 57.32
- ⑫ NOT USED

- ⑩1 395 + 50 Fwy. to 397 + 00 Fwy., 63' Lt., Construct P.M. Dike
- ⑩2 395 + 50 Fwy. to 397 + 00 Fwy., 63' Rt., Construct P.M. Dike
- ⑩4 390 + 90 Fwy., 4" x 140" A.C.P. Conduit

