QUANTITY ESTIMATES

ITEM #	DESCRIPTION	UNIT	UNIT PRICE	PUBLIC	PRIVATE
1	ASPHALTIC CONCRETE PAVING	SY	N/A		14,958
2	TEMP. ASPHALTIC CONCRETE PAVING	SY	N/A	125	–
3	CURB & GUTTER	LF	N/A	–	5266
4	TYPE II AGGREGRATE BASE	CY	N/A	–	2688
5	CONCRETE VALLEY GUTTER	SF	N/A	56	416
6	POWER TO LOT	EA	N/A	–	1
7	TELEPHONE TO LOT	EA	N/A	–	1
8	STREET/STOP SIGN	EA	N/A	–	1
9	6" SEWER	LF	N/A	–	86
10	8" SEWER	LF	N/A	–	396
11	48" MANHOLE	EA	N/A	–	3
12	3" WATER LINE	LF	N/A	–	249
13	8" WATER LINE	LF	N/A	–	1264
14	2" WATER METER AND RPPA	EA	N/A	2	–
15	8" DCDA	EA	N/A	1	–
16	FIRE HYDRANTS	EA	N/A	1	2
17	RIP-RAP APRON	SF	N/A	3330	–
18	MANHOLE RIM ADJUSTMENT	EA	N/A	1	–

REV	DATE	BY	REVISION

PHGSA, LLC.
3111 S. MARYLAND PARKWAY
LAS VEGAS, NEVADA 89109

VPOINT
DESIGNING FOR THE FUTURE
PLANNERS · CONSULTING ENGINEERS · SURVEYORS
1000 WHITNEY RANCH DRIVE · HENDERSON, NEVADA 89014 · (702) 240-4415

DRAWN BY: BLOOM 03/03
DESIGNED BY: BLOOM 03/03
CHECKED BY: TRUDI 03/03
PROJECT NO: 098-E050 NTS

SHEET: QUANTITY AND SCHEDULE SHEET

TITLE: IRS DISTRICT OFFICE

REGISTERED PROFESSIONAL ENGINEER — TRUDI LIM — CIVIL — No. 12508 — STATE OF NEVADA
Exp. 12/05 — 2-22-03

SHEET C4
4 OF 8 SHEETS

DRAWING NO. 107V3860

59912