



- NOTES & LEGEND:**
- ① REMOVE CONCRETE SLAB AND CURB
 - ② REMOVE EXISTING PAVEMENT, COMPACT SUBGRADE
 - ③ REMOVE AND RESET STREET LIGHT
 - ④ RAISE WATER METER VAULT TO GRADE
 - ⑤ REMOVE/REPLACE EXISTING CONCRETE BUMPER BLOCKS & PARKING STALL STRIPING (9 EACH)
 - ⑥ 100mm (MIN) TYPE II AGGREGATE BASE
 - ⑦ NEW 75mm HOTMIX BITUMINOUS PAVEMENT
 - ⑧ CONSTRUCT CONCRETE COMMERCIAL DRIVEWAY (OPTION A) PER USD No. 226
 - ⑨ TBM REF. ELEVATION 621.824 (METRIC)=2047.17 (ENGLISH) ON CLV SURVEY OF 03/11/02
 - ⑩ MATCH NEW AC ELEVATION WITH INVERT OF DRAIN OPENING IN BLOCK WALL (DO NOT BLOCK OPENING)
 - ⑪ CONSTRUCT AC DRIVEWAY
- (621.XXX) APPROXIMATE EXISTING ELEVATION
621.XXX NEW PAVEMENT ELEVATION

DATE	4/2/02
REVISIONS	REVISED PLAN • 1205 S. WESTERN
PROJECT #	31604
DESIGN BY	SCH
SCALE (V)	DATE JANUARY 16, 2002
SCALE (H)	1:100
FLD. BK. #	N/A

PARSONS BRINCKERHOFF
Las Vegas, Nevada

DEPARTMENT OF PUBLIC WORKS
I-15 FREEWAY CHANNEL
UPN CHANNEL PARKING LOT
GRADING PLAN

DRAWING No. 23A
R-27A
241

43259

Call before you Dig.
1-800-277-2600
UNDERGROUND SERVICE (USA)

Call before you Overhead
563-6111
OVERHEAD SERVICE (USA)

METRIC

K:\1604\ADDEN\SHITS\16-27.GMM.DWG CHANEWM 04\05\02 10:23