



REMOVAL ITEMS	
T	REMOVE MANHOLE
CONSTRUCTION ITEMS	
1	"Xm" 3+115.000, 2.400m LT TO "Xm" 3+124.574, 0.255m LT "Xm" 3+223.343, 21.858m RT TO "Xm" 3+242.839, 21.881m RT "Xm" 3+242.839, 21.881m RT TO "Xm" 3+260.000, 21.800m RT CONSTRUCT 750mm SANITARY SEWER PIPE (MICROTUNNEL)
2	"Xm" 3+115.000, 6.000m LT TO "Xm" 3+128.000, 6.000m LT "Xm" 3+223.343, 9.980m RT CONSTRUCT TYPE I SANITARY SEWER MANHOLE
3	"Xm" 3+115.000, 2.400m LT TO "Xm" 3+223.343, 21.858m RT CONSTRUCT TYPE I T-LOCK LINED SANITARY SEWER MH
4	"Xm" 3+223.343, 9.980m RT TO "Xm" 3+223.343, 21.858m RT CONSTRUCT 450mm SANITARY SEWER PIPE
5	"Xm" 3+110.000, 1.430m LT TO "Xm" 3+115.000, 2.400m LT "Xm" 3+115.000, 2.400m LT TO "Xm" 3+115.000, 6.000m LT "Xm" 3+115.000, 6.000m LT TO "Xm" 3+115.000, 6.000m LT "Xm" 3+128.000, 6.000m LT CONSTRUCT 250mm SANITARY SEWER PIPE

DATE	3/30/00
REVISIONS	ADDITION 2
RECORD DRAWING	4/29/02
PROJECT #	31604
DESIGN BY	KFN
DATE	DEC 17, 1999
SCALE (V)	1:50
SCALE (H)	1:250
F.L.D. BK. #	N/A

APPROVED FOR CONSTRUCTION

LAS VEGAS VALLEY WATER DISTRICT DATE

Call before you Dig. 1-800-277-2600 UNDERGROUND SERVICE (USA)

Call before you Overhead 563-6111 OVERHEAD SERVICE (USA)

DEPARTMENT OF PUBLIC WORKS

I-15 FREEWAY CHANNEL

UTILITY RELOCATION (CHARLESTON BLVD)

"Xm" 3+110 TO "Xm" 3+260

