


115672

**OVERALL FLOOR PLAN**

SCALE : 1/16" = 1'-0"



**PLAN NOTES**

P	DESCRIPTION
P1.	DASHED LINE INDICATES STRUCTURE ABOVE TELEPHONE
P2.	NEW CONCRETE STAIR AND WALL TO MATCH EXISTING.
P3.	ALIGN WALL BETWEEN WINDOWS.
P4.	AUDITORIUM WALLS SHALL BE WITH 2" THICK FABRIC ACOUSTICAL WALL PANELS
P5.	SEE INTERIOR ELEVATIONS
P6.	CLERESTORY AUDITORIUM AND PLATFORM WINDOW SHALL HAVE MOTORIZED BLACKOUT SHADES
P7.	NEW ACCESSIBLE RAMP AND RAILING
P8.	FIRE EXTINGUISHER CABINET. SEE 14/A9.01.
P9.	NEW STAIR AND HANDRAIL
P10.	MECHANICAL/MOTORIZED LIFT TO PLATFORM
P11.	RELOCATED ELECTRICAL PANEL SYSTEM. SEE ELECTRICAL DRAWINGS.
P12.	NEW CASEWORK
P13.	NEW TWO-BAY SINK. SEE PLUMBING DWGS.
P14.	NEW REFRIGERATOR - N.L.C.
P15.	NEW CMU WALL ENCLOSURE. SEE 5/AS2.01
P16.	STEEL BOLLARD. SEE DETAIL SHEET AS2.01
P17.	CONCRETE PIER. SEE STRUCTURAL DWGS.
P18.	GATE ENCLOSURE-SEE DETAIL 6/AS2.01
P19.	LINE OF EXISTING SKYLIGHT TO BE RESTORED.
P20.	REMOVABLE RAILING FOR TRUCK DELIVERY. SEE DETAIL 1/A1.33.
P21.	PROVIDE HORIZONTAL MANUAL WINDOW BLIND AT THIS WINDOW.
P22.	EXISTING CONCRETE COLUMN TO REMAIN.
P23.	DRINKING FOUNTAIN. SEE PLUMBING DWGS.
P24.	EXISTING FOUNTAIN TO BE RENOVATED.
P25.	EXISTING COVERED BREZEWAY
P26.	EXISTING CONSTRUCTION TO BE REMOVED AND/OR RESTORED WITH DOORS AND/OR WINDOWS TO MATCH HISTORIC ERA- REFER TO WINDOW AND DOOR SCHEDULE FURNITURE SHOWN ON PLAN SHALL BE TENANT FURNISHED AND TENANT INSTALLED
P27.	NEW SINK. SEE PLUMBING DWGS.
P28.	EXISTING BASEMENT STAIR TO REMAIN.
P29.	INFILL STAIRWELL & GAP WITH CONC. SLAB.
P30.	EXISTING CONCRETE WALL TO BE REMOVED SAND AND FINISH EXISTING CONCRETE WALL FOR PAINT
P31.	NEW BABY CHANGING STATION. ALIGN FACE OF NEW PARTITION WITH FACE OF EXISTING CONCRETE
P32.	NEW COUNTER TRASH DISPOSAL.
P33.	ACCESS LADDER AND HATCH SEE 5/7.31
P34.	NEW CONCRETE. SEE 11/AS2.01.
P35.	1" RECESS INFILL PER 4/A9.05
P36.	LINES INDICATE DIRECTION OF WOOD PLANK FLOORING. SEE STRUCTURAL DWGS.
P37.	RECONSTRUCT SEGMENT OF PARTIAL HEIGHT WALL TO MATCH ADJACENT EXISTING WALL REMOVE DOOR. INFILL OPENING WITH CONCRETE. FLUSH TO EXTERIOR WALL. MATCH EXISTING FINISH AND TEXTURE.
P38.	PATTERNED GLASS WINDOW PER SPEC.
P39.	EXISTING METAL GATE
P40.	ROOF DRAIN SEE DETAIL 3/7.31
P41.	INSTALL NEW CABINET DOORS ON EXISTING CABINET. SEE DETAIL 5/A8.02
P42.	STAGELAM HIGH TRAFFIC FLOORING
P43.	EXISTING CONCRETE PAD TO REMAIN
P44.	EXISTING DIVIDED LIGHT TRANSOM/DOOR ASSEMBLY
P45.	CONCRETE SUMP PIT W/ STEEL GRATE
P46.	FURR OVER WINDOW.
P47.	
P48.	
P49.	


**GENERAL NOTES**

- DIMENSIONS ARE TO FACE OF STUD. FACE OF MASONRY OR FACE OF CONCRETE UNLESS NOTED OTHERWISE.
- INFORM ARCHITECT OF ANY DISCREPANCIES BEFORE BEGINNING OF WORK OF FLOOR
- PRIOR TO CONSTRUCTION, CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS. IN AREAS REQUIRING REPAIR AND/OR REMOVAL, CONTRACTOR SHALL PATCH AND PREP SURFACES FOR NEW FINISH
- PATCH ALL HOLES IN EXTERIOR CONCRETE WALLS INCLUDING LADDER HOLES, CONDUIT, AND PIPE HOLES, ETC. CAUSED BY DEMO. REPAIR AND PAINT ALL CRAWL SPACE VENT GRILLES - TYPICAL.


**WALL TYPES**

- A** WALL TYPE SYMBOL - SEE SHEET A2.32 & A2.33 FOR WALL TYPES
- NOTES**
- WALL TYPES WITH AN "S" SUBSCRIPT INDICATE FIBERGLASS ACOUSTICAL INSULATION FULL HEIGHT AND DEPTH OF PARTITION NOTED AND REQUIRES THE GYP. BOARD TO EXTEND FROM TOP OF FLOOR SLAB TO UNDERSIDE OF STRUCTURE ABOVE ON ONE SIDE OF PARTITION THAT OTHERWISE WOULD NOT EXTEND TO THE STRUCTURE ABOVE.
  - PROVIDE HEAVY GAGE METAL STUDS IN LIEU OF LIGHT GAGE METAL STUDS AT WALLS WITH ANY WALL HUNG TYPE ATTACHMENTS AND/OR SUPPORTING ATTACHMENTS SUCH AS WALL SINKS, GRAB BARS, WALL CABINETS AND OTHER MISC. EQUIPMENT.
  - ALL WALLS IN WET AREAS SHALL HAVE 5/8" TYPE "X" WATER-RESISTANT GYPSUM BOARD IN LIEU OF 5/8" TYPE "X" (REGULAR) GYPSUM BOARD.
  - ALL INTERIOR PARTITIONS ARE NON-BEARING.
  - WALLS WITH SUBSCRIPT "T" INDICATES WALLS WITH THERMAL INSULATION FOR THE FULL HEIGHT OF THE WALL.

**WALL LEGEND**



**BUILDING MAP**



**CLV COMMENTS**  
14-2007

**KCA ARCHITECTURE**  
KYLE GARIBAY  
ARCHITECT  
400 SOUTH POLARIS AVENUE  
LAS VEGAS, NEVADA 89102  
WWW.KCAARCHITECTURE.COM  
PHONE: (702) 336-3800  
FAX: (702) 336-3800

**HERITAGE ARCHITECTURE & PLANNING**  
PHONE: 69-29-7888

**VTN NEVADA**  
PHONE: 702-727-7200

**STRUCTURAL - BARKER DROTTER ASSOCIATES**  
STRUCTURAL ENGINEERS  
PHONE: 702-30-8000

**MECHANICAL - PLUMBING - ELECTRICAL - FIRE SAFETY - ACOUSTICAL - GENERAL LIGHTING**  
**JBA CONSULTING ENGINEERS**  
PHONE: 702-30-9000

**STAGE LIGHTING & DESIGN - COME LIGHTING DESIGN GROUP**  
PHONE: 89-23-2343

**LANDSCAPE - JZWUNGO & ASSOCIATES**  
PHONE: 702-25-7000

**COST ESTIMATING - RIDER HUNT LEVITT & BAILEY**  
PHONE: 702-27-4888

**ADA ACCESSIBILITY ENDELMAN AND ASSOCIATES**  
PHONE: 266-346462

**CITY OF LAS VEGAS**

**FIFTH STREET SCHOOL REHABILITATION BUILDING DEPARTMENT SUBMITTAL**

**CITY OF LAS VEGAS REDEVELOPMENT AGENCY**

**OWNER: CITY OF LAS VEGAS DEPARTMENT OF PUBLIC WORKS ARCHITECTURAL SERVICES**

400 EAST STEWART AVENUE  
LAS VEGAS, NEVADA 89102  
PHONE: (702) 226-6535  
FAX: (702) 384-6535  
TDD: (702) 386-9308

**ED C.**  
**OVERALL FLOOR PLAN**  
DATE: 12/12/2006  
SCALE: 1/16" = 1'-0"  
SHEET NO. 513-65E

**A1.01**