


### PLAN NOTES

P	DESCRIPTION
P1.	DASHED LINE INDICATES STRUCTURE ABOVE
P2.	TELEPHONE
P3.	NEW CONCRETE STAIR AND WALL TO MATCH EXISTING.
P4.	ALIGN WALL BETWEEN WINDOWS. AUDITORIUM WALLS SHALL BE WITH 2" THICK FABRIC ACOUSTICAL WALL PANELS SEE INTERIOR ELEVATIONS
P5.	CLERESTORY AUDITORIUM AND PLATFORM WINDOW SHALL HAVE MOTORIZED BLACKOUT SHADES
P6.	NEW ACCESSIBLE RAMP AND RAILING
P7.	FIRE EXTINGUISHER CABINET. SEE 14/A9.01.
P8.	NEW STAIR AND HANDRAIL
P9.	MECHANICAL/MOTORIZED LIFT TO PLATFORM
P10.	RELOCATED ELECTRICAL PANEL SYSTEM. SEE ELECTRICAL DRAWINGS.
P11.	NEW CASEWORK
P12.	NEW TWO-BAY SINK. SEE PLUMBING DWGS.
P13.	NEW REFRIGERATOR - N.I.C.
P14.	NEW CMU WALL ENCLOSURE. SEE 5/AS2.01.
P15.	STEEL BOLLARD. SEE DETAIL SHEET AS2.01
P16.	CONCRETE PIER. SEE STRUCTURAL DWGS.
P17.	GATE ENCLOSURE-SEE DETAIL 5/AS2.01
P18.	LINE OF EXISTING SKYLIGHT TO BE RESTORED.
P19.	REMOVEABLE RAILING FOR TRUCK DELIVERY. SEE DETAIL 1/A1.33.
P20.	PROVIDE HORIZONTAL MANUAL WINDOW BLIND AT THIS WINDOW.
P21.	EXISTING CONCRETE COLUMN TO REMAIN.
P22.	DRINKING FOUNTAIN. SEE PLUMBING DWGS.
P23.	EXISTING FOUNTAIN TO BE RENOVATED.
P24.	EXISTING COVERED BREZZEWAY
P25.	EXISTING CONSTRUCTION TO BE REMOVED AND/OR RESTORED WITH DOORS AND/OR WINDOWS TO MATCH HISTORIC GRA - REFER TO WINDOW AND DOOR SCHEDULE
P26.	FURNITURE SHOWN ON PLAN SHALL BE TENANT FURNISHED AND TENANT INSTALLED
P27.	NEW SINK. SEE PLUMBING DWGS.
P28.	EXISTING BASEMENT STAIR TO REMAIN
P29.	INFILL STAIRWELL & CAP WITH CONC. SLAB.
P30.	EXISTING CONCRETE WALL TO BE REMOVED SAND AND FINISH EXISTING CONCRETE WALL FOR PAINT
P31.	NEW BABY CHANGING STATION.
P32.	ALIGN FACE OF NEW PARTITION WITH FACE OF EXISTING CONCRETE
P33.	NEW COUNTER TRASH DISPOSAL
P34.	ACCESS LADDER AND HATCH SEE 5/A7.31
P35.	NEW CONCRETE. SEE 11/AS2.01.
P36.	1" RECESS INFILL PER 4/A9.05
P37.	LINE INDICATE DIRECTION OF WOOD PLANK FLOORING. SEE STRUCTURAL DWGS.
P38.	RECONSTRUCT SEGMENT OF PARTIAL HEIGHT WALL TO MATCH ADJACENT EXISTING WALL
P39.	REMOVE DOOR, INFILL OPENING WITH CONCRETE. FLUSH TO EXTERIOR WALL MATCH EXISTING FINISH AND TEXTURE.
P40.	PATTERNED GLASS WINDOW PER SPEC.
P41.	EXISTING METAL GATE
P42.	ROOF DRAIN SEE DETAIL 3/A7.31
P43.	INSTALL NEW CABINET DOORS ON EXISTING CABINET. SEE DETAIL 5/A8.02
P44.	STAGELAM HIGH TRAFFIC FLOORING
P45.	EXISTING CONCRETE PAD TO REMAIN
P46.	EXISTING DIVIDED LIGHT TRANSOM/DOOR ASSEMBLY
P47.	CONCRETE SUMP PIT W/ STEEL GRATE
P48.	FURR OVER WINDOW.
P49.	

- ### GENERAL NOTES
- DIMENSIONS ARE TO FACE OF STUD, FACE OF MASONRY OR FACE OF CONCRETE UNLESS NOTED OTHERWISE.
  - INFORM ARCHITECT OF ANY DISCREPANCIES BEFORE BEGINNING WORK.
  - PRIOR TO CONSTRUCTION, CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS. IN AREAS REQUIRING REPAIR AND/OR REMOVAL, CONTRACTOR SHALL PATCH AND PREP SURFACES FOR NEW FINISH.
  - ALL HOLES IN EXTERIOR CONCRETE WALLS INCLUDING LADDER HOLES, CONDUIT, AND PIPE HOLES, ETC. CAUSED BY DEMO. REPAIR AND PAINT ALL GRAM. SPACE VENT GRILLES - TYPICAL.

- ### WALL TYPES
1. WALL TYPE SYMBOL - SEE SHEET A2.32 & A2.33 FOR WALL TYPES
- NOTES
- WALL TYPES WITH AN 'S' SUBSCRIPT INDICATE FIBERGLASS ACOUSTICAL INSULATION FULL HEIGHT AND DEPTH OF PARTITION NOTED AND REQUIRES THE GYP. BOARD TO EXTEND FROM TOP OF FLOOR SLAB TO UNDERSIDE OF STRUCTURE ABOVE ON ONE SIDE OF PARTITION THAT OTHERWISE WOULD NOT EXTEND TO THE STRUCTURE ABOVE.
  - PROVIDE HEAVY GAGE METAL STUDS IN LIEU OF LIGHT GAGE METAL STUDS AT WALLS WITH ANY WALL HUNG TYPE ATTACHMENTS AND/OR SUPPORTING ATTACHMENTS SUCH AS WALL SINKS, GRAB BARS, WALL CABINETS AND OTHER MISC. EQUIPMENT.
  - ALL WALLS IN WET AREAS SHALL HAVE 5/8" TYPE 'X' WATER-RESISTANT GYPSUM BOARD IN LIEU OF 5/8" TYPE 'X' (REGULAR) GYPSUM BOARD.
  - ALL INTERIOR PARTITIONS ARE NON-BEARING.
  - WALLS WITH SUBSCRIPT 'T' INDICATES WALLS WITH THERMAL INSULATION FOR THE FULL HEIGHT OF THE WALL.

- ### WALL LEGEND
- FRAMED INTERIOR PARTITION
  - EXISTING CONCRETE PARTITION
  - NEW CONCRETE PARTITION
  - FURRED CONCRETE PARTITION
  - 1 HOUR RATED FRAMED INTERIOR PARTITION PER U.L. DESIGN W20005. SEE DETAIL 11/A9.06.



**PLAN CHECK**  
OWNER COMMENTS  
OWNER COMMENTS

**KCA ARCHITECTURE**  
455 SOUTH POLARIS AVENUE  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 251-1000  
FACSIMILE: (702) 251-1000

**HERITAGE ARCHITECTURE & PLANNING**  
1000 S. RAY  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 735-7700

**BARBER DROTAR ASSOCIATES**  
STRUCTURAL ENGINEERS  
1000 S. RAY  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 735-7700

**SEA CONSULTING ENGINEERS**  
MECHANICAL - PLUMBING - ELECTRICAL  
FIRE SAFETY - ACOUSTICAL - GENERAL LIGHTING  
1000 S. RAY  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 735-7700

**CDM LIGHTING DESIGN GROUP**  
1000 S. RAY  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 735-7700

**JWZLUNGO & ASSOCIATES**  
1000 S. RAY  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 735-7700

**LETT & BAILEY**  
1000 S. RAY  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 735-7700

**ADA ACCESSIBILITY**  
BROOKMAN AND ASSOCIATES  
1000 S. RAY  
SUITE 100  
LAS VEGAS, NV 89101  
PHONE: (702) 735-7700

**CITY OF LAS VEGAS**  
REDEVELOPMENT AGENCY

**RECEIVED**  
FEB 08 2007  
CITY OF LAS VEGAS  
BUILDINGS DEPT.

OWNER: CITY OF LAS VEGAS  
DEPARTMENT OF PUBLIC WORKS  
ARCHITECTURAL SERVICES

450 EAST STEWART AVENUE  
LAS VEGAS, NEVADA 89101  
PHONE: (702) 528-4824  
FACSIMILE: (702) 528-4826  
TDD: (702) 528-4826

FILE: GALLERY PLAN  
DATE: 12/2/2006  
SCALE: 1/4" = 1'-0"  
DWG NO: 513-65E

A1.12