GENERAL NOTES:

1. ALL WATER PIPING SHALL BE INSTALLED ON THE INTERIOR SIDE OF THE BUILDING.
2. THE CUTTING, NOTCHING AND BORING OF HOLES IN FLOOR JOIST AND WALL STUDS SHALL BE IN ACCORDANCE WITH THE LATEST APPROVED EDITION OF THE INTERNATIONAL BUILDING CODE.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR THE COORDINATION OF ALL PLUMBING ROUGH-IN LOCATIONS. REFER TO ARCHITECTURAL DRAWINGS FOR FIXTURES AND EQUIPMENT LOCATIONS.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CUTTING AND PATCHING AS REQUIRED TO ACCOMMODATE HIS WORK.
5. ALL SANITARY DRAINAGE AND GREASE WASTE PIPING SHALL BE SLOPED AT 1/4" PER FOOT, UNLESS OTHERWISE NOTED.
6. PLUMBING CONTRACTOR SHALL COORDINATE ROUTING OF PIPING WITH ALL OTHER TRADES PRIOR TO COMMENCING WORK.
7. ALL PLUMBING FIXTURES SHALL BE WATER CONSERVATION TYPE AS MANDATED BY LOCAL BUILDING DEPARTMENT.
8. PRIOR TO INSTALLATION OF SEWER AND WATER PIPING BELOW GRADE COORDINATE EXACT LOCATIONS AND DEPTHS OF BURIAL WITH CIVIL AND FOUNDATION DRAWINGS AND CORRESPONDING ENGINEERS.
9. REFER TO THE PLUMBING DETAILS THAT APPLY TO THE WORK ON THIS DRAWING. THESE DETAILS PROVIDE GUIDANCE AS TO INSTALLATION INTENT AND DO NOT NECESSARILY SHOW ALL COMPONENTS REQUIRED.

SHEET NOTES:

1. REFER CIVIL FOR CONTINUATION.
2. FIRE RISER BY DESIGN-BUILD FIRE PROTECTION CONTRACTOR.
3. 4" WASTE AND 2" VENT UP.
4. 2" WASTE AND 2" VENT UP.
5. 4" VENT UP THROUGH ROOF.
6. 2" VENT UP.
7. NOT USED.
8. UNDERGROUND 1500 GALS. CAPACITY GREASE INTERCEPTOR, REFER TO DETAIL H/P02.
9. UNDERGROUND SAMPLING BOX WITH SEWER MANHOLE COVER, REFER TO DETAIL C/P02.
10. GROUND CLEANOUT.
11. 2-WAY GROUND CLEANOUT.
12. 3" VENT UP.
13. ROUTE WH-1 PTRV RELIEF DRAIN WITH 2" AIR GAP OVER FD-1.
14. ROUTE WH-1 DRAIN WITH 2" AIR GAP OVER FD-1.
15. ROUTE LINE SIZED INDIRECT WASTES FROM BEER TOWER SYSTEM (ITEM #3), AND ICE CHEST STATION (ITEM #20) TO FD-1.
16. ROUTE LINE SIZED INDIRECT WASTE FROM UNDERBAR 3-COMPARTMENT POT SINK (ITEM #1) TO FD-1.
17. ROUTE LINE SIZED INDIRECT WASTES FROM WORK TABLE TOP CUSTOM SINK (ITEM #2), AND HAND SINK (ITEM #3) TO FD-1.
18. ROUTE LINE SIZED INDIRECT WASTE FROM BEER DISPENSER (ITEM #22) TO FD-1.
19. ROUTE LINE SIZED INDIRECT WASTE FROM STEAM TABLE 2-COMPARTMENT SINK (ITEM #38) TO FD-1.
20. ROUTE LINE SIZED INDIRECT WASTE FROM 2-COMPARTMENT PREP. SINK (ITEM #69) TO FD-1.
21. ROUTE LINE SIZED INDIRECT WASTES FROM 3-COMPARTMENT POT SINK (ITEM #14) AND ICE MACHINE (ITEM #17) TO FD-1.
22. BUILT-IN BLOWER-COIL IN WALK-IN FREEZER PROVIDED BY FOOD SERVICE CONTRACTOR.
23. BUILT-IN BLOWER-COIL IN WALK-IN COOLER PROVIDED BY FOOD SERVICE CONTRACTOR.
24. ROUTE COPPER CONDENSATE LINES 1" OFF THE WALL FROM BLOWER-COILS IN WALK-IN FREEZER AND COOLER TO FD-1. PROVIDE RUNNING "Y-TRAP" IN-LINE OUTSIDE OF WALK-INS. TERMINATE DRAINS WITH 4" AIR GAP OVER FD-1.
25. INSULATE CONDENSATE DRAINS INSIDE WALK-IN FREEZER AND COOLER BOXES. PROVIDE HEAT TAPE ON CONDENSATE LINES WITHIN THE WALK-IN FREEZER BOX.
26. 3/4" CONDENSATE UP TO AC UNIT.
27. 1" CD DOWN ALONG WALL. TERMINATE WITH 4" AIR GAP OVER FD-1
28. LINE SIZE WASTE INSIDE PEDESTAL, DOWN TO 2" P-TRAP AND WASTE.
29. 2" VENT THROUGH ROOF.
30. EXTEND LINE SIZE WASTE UP IN WALL TO WCO.
31. LINE SIZE DRAIN UP TO MAU-1 DRAIN CONNECTIONS (VERIFY PIPING CONFIGURATION FOR AUTO DRAIN AND OVERFLOW).
32. ROUTE 1 1/2" DRAIN IN CEILING SPACE (1/4"/ FT. SLOPE) TOWARDS WATER HEATER ROOM. DROP DRAIN IN WALL AND STUB OUT OF WALL AT 12" AFF, TERMINATE WITH 4" AIR GAP OVER FD-1.
33. INSTALL AT 1/8" PER FOOT SLOPE, ONLY ON INDICATED 4" SANITARY PIPING.
34. 3" WASTE UP, FLOOR TROUGH (ITEM # 85).

123213

STADIUM CLUB
PLUMBING FLOOR PLAN - WASTE AND VENT
SRP-3A
1/4" = 1'-0"

NORTH BUILDING #1
NORTH BUILDING #2

RECORD DRAWING

THESE MODIFIED OR RECORD DRAWINGS HAVE BEEN PREPARED, IN WHOLE OR IN PART, ON THE BASIS OF INFORMATION COMPILED AND FURNISHED BY THE CONTRACTOR OR OTHERS INVOLVED WITH THE PROJECT. MSA ENGINEERING CONSULTANTS IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH HAVE BEEN INCORPORATED INTO THIS DOCUMENT AS A RESULT. CAREFUL EXAMINATION OF ACTUAL EXISTING CONDITIONS SHOULD BE UNDERTAKEN PRIOR TO EXCAVATION, CUTTING, MODIFICATION, OR CONNECTION OF SUBSEQUENT CONSTRUCTION.

01-31-2010

REVISIONS

architecture interiors planning engineering
Dekker Perich Sabatini
6860 Bermuda Road, Ste. 100
Las Vegas, Nevada 89119
702.436.1006
fax 436.1050
info@dpsdesign.org

MSA #E.081665
MSA ENGINEERING CONSULTANTS
3010 E. Windmill Lane
Las Vegas, NV. 89123
T: (702) 896-1100
F: (702) 896-1133
email: msa@msa-lv.com

CITY OF LAS VEGAS
FREEDOM PARK RENOVATION
850 NORTH MOJAVE, LAS VEGAS, NEVADA 89101
STADIUM CLUB
PLUMBING FLOOR PLAN - WASTE AND VENT

Russ Mauger
Roche Constructors, Inc.

PROFESSIONAL ENGINEER-STATE OF NEVADA
BENJAMIN YEANG
Exp. 06-30-10
MECHANICAL
No. 015978
JAN 31 2010

STAMP

RECORD DRAWINGS
01-31-2010

OWNER: CITY OF LAS VEGAS
DEPARTMENT OF PUBLIC WORKS
ARCHITECTURAL SERVICES

400 EAST STEWART AVENUE
LAS VEGAS, NEVADA 89101
PHONE: (702) 229-6551
FAX: (702) 384-4846
TDD: (702) 386-9108

DRAWN	
TITLE	
DATE	JANUARY 31, 2010
SCALE	AS NOTED
MSD NO	070354
CLV DWG NO	650.22-18
SHEET NO	SRP-3A

RECORD DRAWING

DRAWINGS AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE DESIGN PROFESSIONAL WHOSE STAMP OF IDENTIFICATION APPEARS ON THE DRAWINGS AND SPECIFICATIONS AND SHALL NOT BE REUSED BY THE CLIENT ANY PURPOSE WHATSOEVER WITHOUT THE PROFESSIONAL'S WRITTEN CONSENT. ALL REPRODUCTIONS OF THESE DRAWINGS AND SPECIFICATIONS AND ANY USE OR REPRODUCTIONS IN WHOLE OR IN PART WITHOUT WRITTEN CONSENT IS STRICTLY PROHIBITED. COPIES OF THE DRAWINGS AND SPECIFICATIONS RETAINED BY THE CLIENT MAY BE UTILIZED ONLY FOR OCCUPYING THE PROJECT FOR WHICH THEY WERE PREPARED AND NOT FOR THE CONSTRUCTION OF ANY OTHER PROJECT A A S 813.7(B)
RECORD DOCUMENTS ARE PREPARED FROM DATA AND INFORMATION SUPPLIED BY OTHERS. DEKKERPERICHSABATINI, LTD. DOES NOT CERTIFY, OR WARRANT IN ANY MANNER, THE ACCURACY OR COMPLETENESS OF THE INFORMATION PRESENTED, AND TO VERIFY THE SUITABILITY OF THE INFORMATION FOR THE PURPOSE FOR WHICH THEY INTEND TO USE THE INFORMATION. DEKKERPERICHSABATINI, LTD. IS NOT RESPONSIBLE FOR ANY PROBLEMS OR RELATED COSTS THAT MAY ARISE OUT OF THE USE OF RECORD DOCUMENTS.