



NOTE
 BM #181 Elev 2066.208
 TBM 30' W 0+00 Nail in 12" pipe - 2063.25
 Const C&G rec. at Tonopah Road

ITEM	ESTIMATE OF QUANTITIES	AMOUNT	UNITS
EXCAVATION	1232		CU YDS.
AC PAVING	2546		SQ. FT.
1" CURB & GUTTER	2554		LINE FT.

2065
 2060
 2055

c-17-61

CITY OF LAS VEGAS, NEVADA ENGINEERING DEPT.			
HASTINGS AVE. TONOPAH DR. TO ROSE ST.			
DESIGNED BY K CRAWFORD	DATE 4-5-54	SCALE AS SHOWN	BY J. E. VERT
DRAWN BY MCH	DATE 8-25-54	WORK ORDER NO. 10-94	
CHECKED BY J. D. [unclear]	DATE 7/8/54	DRAWING NO. 107-V260	
APPROVED CITY ENGR.			

2-4-147