

66913

ESTIMATE OF QUANTITIES (CONTINUED)

ITEM NO.	TOTAL	UNIT	ITEM
623 3104	2	EACH	SODIUM VAPOR LUMINAIRE, 400 WATT
623 4070	77	EACH	STEEL POLE, TYPE 7
623 4350	2	EACH	STEEL POLE, TYPE 35
623 6206	1	EACH	SIGNAL HEAD (12-INCH) 1W3C, BRACKET
623 6211	7	EACH	SIGNAL HEAD (12-INCH) 1W3C, MAST ARM
623 6233	2	EACH	SIGNAL HEAD (12-INCH) 2W3C/5C, BRACKET
623 6502	1	EACH	PEDESTRIAN SIGNAL HEAD 2W
623 6601	2	EACH	PEDESTRIAN PUSH BUTTON WITH SIGN
623 7000	62	EACH	LOOP DETECTOR (6-FOOT X 6-FOOT)
623 7007	2	EACH	LOOP DETECTOR AMPLIFIER CHANNELS (EXISTING CABINET)
623 7100	3,530	LINFT	LEAD-IN CABLE FOR LOOP DETECTORS
623 7606	1	EACH	SPECIAL CABINET
623 8310	300	LINFT	REMOVE AND RELOCATE EXISTING CABLE
623 8490	2	EACH	REMOVE AND RESET SERVICE PEDESTAL
623 8500	83	EACH	REMOVE AND RESET LIGHT POLE
623 8501	1	EACH	REMOVE AND RESET SIGNAL POLE
623 8502	1	EACH	REMOVE AND RESET TRAFFIC ACTUATED CONTROLLER
623 8505	2	EACH	REMOVE AND RESET STREET NAME SIGN
623 8510	1	EACH	REMOVE AND RESET SIGNAL HEAD
623 8755	20	SQFT	TRAFFIC SIGNAL SIGNS
624 0200	7,500	HOOR	FLAGGER
625 0110	1,620	SQFT	RENT CONSTRUCTION SIGNS
625 0114	50	EACH	RENT TRAFFIC CONES
625 0117	140	EACH	RENT BARRICADE WARNING LIGHTS (TYPE A)
625 0122	140	EACH	RENT CONSTRUCTION BARRICADES (TYPE IIIB)
625 0123	2,800	LINFT	RENT PORTABLE PRECAST CONCRETE BARRIER RAIL
625 0301	6	EACH	RENT ARROW BOARD (TYPE A)
625 0416	600	EACH	RENT TRAFFIC DRUMS
625 1000	2	EACH	RENT TEMPORARY IMPACT ATTENUATOR
627 0110	330	SQFT	PERMANENT SIGNS (GROUND MOUNTED) (METAL SUPPORTS)
627 0140	270	SQFT	PERMANENT SIGNS, REMOVE
628 0100		---	MOBILIZATION
633 0100	6,830	EACH	NON-REFLECTIVE PAVEMENT MARKERS
633 0200	3,010	EACH	REFLECTIVE PAVEMENT MARKERS
633 1008	1,600	LINFT	PERMANENT PAINTED STRIPING (SOLID WHITE)
634 2100	1,600	SQFT	PERMANENT PAVEMENT MARKING FILM (TYPE 1) (VARIES)
634 2112	4,300	LINFT	PERMANENT PAVEMENT MARKING FILM (TYPE 1) (12-INCH)
635 0200	11,000	LINFT	TEMPORARY STRIPING TAPE
635 0309	85	EACH	TEMPORARY ARROWS
636 1000	4.50	MILE	TEMPORARY PAINTED STRIPING (BROKEN WHITE)
636 1003	1	MILE	TEMPORARY PAINTED STRIPING (DOUBLE SOLID YELLOW)
636 1005	4	MILE	TEMPORARY PAINTED STRIPING (BROKEN YELLOW W/SOLID YELLOW)
636 1006	6	MILE	TEMPORARY PAINTED STRIPING (SOLID WHITE)
636 1007	6.50	MILE	TEMPORARY PAINTED STRIPING (SOLID YELLOW)
637 0001	FA	---	TEMPORARY POLLUTION CONTROL
650 0307	800	LINFT	3/4-INCH COPPER WATER PIPE
650 0310	400	LINFT	1-INCH COPPER WATER PIPE
650 0315	90	LINFT	1-1/2-INCH COPPER WATER PIPE
650 0320	120	LINFT	2-INCH COPPER WATER PIPE
650 0506	1,740	LINFT	6-INCH WATER PIPE
650 0508	2,280	LINFT	8-INCH WATER PIPE
650 0510	140	LINFT	10-INCH WATER PIPE
650 0512	5,050	LINFT	12-INCH WATER PIPE
650 0514	200	LINFT	14-INCH WATER PIPE
650 0518	40	LINFT	18-INCH WATER PIPE
650 0520	20	LINFT	20-INCH WATER PIPE
650 2006	32	EACH	6-INCH INLINE GATE VALVE ASSEMBLY
650 2008	11	EACH	8-INCH INLINE GATE VALVE ASSEMBLY
650 2010	2	EACH	10-INCH INLINE GATE VALVE ASSEMBLY
650 2033	1	EACH	8-INCH TAPPING SLEEVE (6-INCH VALVE)
650 2036	2	EACH	8-INCH TAPPING SLEEVE (8-INCH VALVE)
650 2043	3	EACH	12-INCH TAPPING SLEEVE (6-INCH VALVE)
650 2044	1	EACH	12-INCH TAPPING SLEEVE (8-INCH VALVE)
650 2046	7	EACH	12-INCH TAPPING SLEEVE (12-INCH VALVE)
650 5000	4	EACH	CONNECTION TO EXISTING WATER LINE
650 5007	25	EACH	3/4-INCH WATER SERVICE CONNECTION
650 5010	5	EACH	1-INCH WATER SERVICE CONNECTION
650 5015	1	EACH	1 1/2-INCH WATER SERVICE CONNECTION
650 5020	3	EACH	2-INCH WATER SERVICE CONNECTION
650 5102	2	EACH	VACUUM-AIR RELIEF VALVE ASSEMBLY
650 5103	14	EACH	FIRE HYDRANT ASSEMBLY
650 5325	3	EACH	ABANDON VALVE

107V3989

FED. RD. REG. NO.	STATE	PROJECT NO.	COUNTY	SHEET NO.
9	NEVADA	M-610(5)	CLARK	3 E