FED RD REG NO	STATE	PROJECT NO.	COUNTY	SHEET NO
9	NEVADA	M-610(5)	CLARK	S-6

STRUCTURE LIST

SURVEY MONUMENTS	CLASS A CONCRETE VALLEY GUTTER (TYPE A)	CURVATURE CONCRETE CURB	CLASS A CONCRETE DRIVEWAY (6-INCHES)	CLASS A CONCRETE DRIVEWAY (8-INCHES)	CLASS A CONCRETE SIDEWALK (4-INCHES)	CLASS A CONCRETE CURB AND GUTTER (TYPE 5)	CLASS A CONCRETE GLIB DOWN CURB (TYPE A)	CLASS A CONCRETE CURB (TYPE 2)	8-INCH POLYVINYL CHLORIDE PIPE (SDR-35)	6-INCH POLYVINYL CHLORIDE PIPE (SDR-35)	TYPE 4 MANHOLE (MODIFIED)	TYPE 4 MANHOLE	SPECIAL MANHOLE	DROP INLET (TYPE 10)	ADJUSTING CASINGS (METHOD C)	ADJUSTING COVERS (METHOD B)	48-INCH PRECAST REINFORCED CONCRETE MANHOLE, TYPE 1	SPECIAL DROP INLET	STRUCTURAL STEEL GRATES	30-INCH X 24-INCH OVAL REINFORCED CONCRETE PIPE, CLASS III	42-INCH X 29-INCH OVAL REINFORCED CONCRETE PIPE, CLASS III	36-INCH REINFORCED CONCRETE PIPE, CLASS III	24-INCH REINFORCED CONCRETE PIPE, CLASS III	18-INCH REINFORCED CONCRETE PIPE, CLASS III	15-INCH REINFORCED CONCRETE PIPE, CLASS III	12-INCH REINFORCED CONCRETE PIPE, CLASS III	REMOVING TREES, EACH	CLASS A CONCRETE (ISLAND PAVING)	CLASS A CONCRETE (MINOR)	CONCRETE PAVING MISCELLANEOUS AREAS (8-1/2-INCHES)	SAW AND SEAL TRANSVERSE WEAKENED PLANE JOINTS	PLANTMIXING MISCELLANEOUS AREAS	GRANULAR BACKFILL	STRUCTURE EXCAVATION	REMOVAL OF MEDIAN ISLANDS	REMOVAL OF DROP INLETS	REMOVAL OF CURB AND GUTTER	REMOVAL OF SIDEWALK	REMOVAL OF VALLEY GUTTER	REMOVAL OF CURB	REMOVAL OF BITUMINOUS SURFACE (COLD MILLING)	REMOVAL OF BITUMINOUS SURFACE	REMOVAL OF CONCRETE PAVEMENT	REMOVAL OF GUARDRAIL	REMOVE AND RESET CHAIN LINK FENCE	REMOVE AND RESET GUARDRAIL	DESCRIPTION	STATION TO STATION
																																					272		206					REMOVE CURB AND BITUMINOUS SURFACE LT.	"C" 107+21
																																															"C" 110+51
																																				178		144					REMOVE CURB AND PCC SURFACE LT.	"C" 111+05
																																															"C" 112+46
																																			128		329		744			REMOVE CURB, CURB AND GUTTER, AND BITUMINOUS SURFACE LT.	"C" 112+52
																																															"L1" 121+23
																																					387		233					REMOVE CURB AND BITUMINOUS SURFACE	"L1" 119+84 RT.
																																															"C" 119+62 LT.
																																															CONSTRUCT LANDSCAPING PLANTERS AND PATCH PCC OR PLANTMIX SURFACE
								44																										3												AT THE FOLLOWING LOCATIONS:
								75																										5												"C" 107+21.64 TO "C" 107+42 LT.
								76																										4												"C" 107+66 TO "C" 108+01 LT.
						140		155																										17												"C" 108+33 TO "C" 108+69 LT.
				34				134																																						"C" 109+01 TO "C" 110+50 LT.
				36	38			156																																						"C" 111+02 TO "C" 111+59 LT.
						55		49																										3												"C" 111+91 TO "C" 112+86 LT.
						33		80																										6												"C" 113+19 TO "C" 113+69 LT.
								82																										12												"C" 114+01 TO "C" 114+58 LT.
						6		286																										26												"C" 114+90 TO "C" 115+25 LT.
								5																										10												"L1" 118+66 RT. TO "C" 117+92 LT.
								77																																						"C" 119+26 (51' LT. TO 56' LT.)
								110																										30												"L1" 118+95 TO "L1" 119+62 RT.
																																															"L1" 119+57 TO "L1" 120+03.31 LT.
																																															REMOVE DROP INLET AT THE FOLLOWING LOCATIONS:
																																															"C" 110+23 LT.
																																															"C" 116+86 LT.
																																															"L1" 118+05 LT. (INCLUDES REMOVAL OF REINFORCED CONCRETE PIPES)
			2																																												CONSTRUCT RETAINING WALL AND PATCH PCC AND PLANTMIX SURFACE LT.	"L1" 118+35
																																															"L1" 118+70
																																															CONSTRUCT SPECIAL DROP INLET AT "L1" 129+16 LT. (SEE SHT.21)
																																															REMOVE BITUMINOUS SURFACE IN AREA OF STORM DRAIN EXCAVATION AND
																																															PATCH AT THE FOLLOWING LOCATIONS. SEE DETAIL SHEET NO. 2A.
																																															"L1" 117+80 to "L1" 118+05 LT.
																																															"L1" 144+50 to "L1" 146+50 RT.
																																															10763989
																																															REMOVE AND CONSTRUCT CONCRETE CHANNEL AT THE FOLLOWING
																																															LOCATIONS: (NO DIRECT PAYMENT - SEE SHEET 16)
																																															"L1" 147+64 (50' LT TO 55' LT.)
																																															"L1" 185+43.5 (50' LT TO 60' LT)

67038