SANITARY SEWER SCHEDULE

FED. RD. REG. NO.	STATE	PROJECT NO.	COUNTY	SHEET NO.
9	NEVADA	M-610(5)	CLARK	SD-4

SHEET NO.	STRUCTURE - LINE NO.	LOCATION STA.	LOCATION OFFSET	STRUCTURE TYPE	MANHOLES TYPE 1	ELEVATION GRATE, RIM OR COVER	INVERT IN	INVERT OUT	SLOPE FT./FT.	PVC PIPES SDR 35 6"	PVC PIPES SDR 35 8"	DUCTILE IRON PIPES CL 50 6"	REMARKS	STRUCTURE EXCAVATION	GRANULAR BACKFILL	TYPE 1 MANHOLE	REMOVAL OF CURB & GUTTER	REMOVAL OF SIDEWALK	CLASS A CONCRETE SIDEWALK (4 INCH)	CLASS A CONCRETE CURB & GUTTER (TYPE 2)
SS-3	MH-12	202+67	35'Rt.		1	1784.10	1778.19	1778.02					H=5.91'			1				
							1778.02	1776.41	.0062		260'			145.4	141.7					
SS-1	MH-11	200+03	35'Rt.		1	1784.40	1776.41	1776.31					H=8.09'			1				
							1776.31	1774.95	.0061		222'			182.6	179.4					
SS-1	MH-10	197+76.81	35'Rt.		1	1783.30	1774.95	1774.85					H=8.45'			1				
							1774.85	1773.24	.0069		233'			519.5	516.2					
SS-2	MH-9	"W"12+75	35'Lt.		1	1783.30	1773.24	1773.24					H=10.06			1				
							1773.24	1770.86	.0069		346'			832.6	827.6					
SS-2	MH-8	"W"16+25	35'Lt.		1	1779.70	1770.86	1770.86					H=8.84'			1				
							1770.86	1768.48	.0069		346'			600.3	595.4					
SS-2	MH-7	"W"19+75	35'Lt.		1	1775.80	1768.48	1768.48					H=7.32'			1				
							1768.48	1766.10	.0069		346'			635.9	631.0					
SS-2	MH-6	"W"23+25	35'Lt.		1	1775.30	1766.10	1766.00					H=9.30'			1				
							1766.00	1765.68	.0070		43'			109.4	108.8					
SS-2	MH-5	"W"23+64.1	9.5'Lt.				1765.68	1765.47					EXISTING MANHOLE. REMOVE EXISTING WEST INLET PIPE AND ATTACH 8" PVC TO MANHOLE. NO DIRECT PAYMENT.							
SS-1	MH-4	195+78	16'Rt.		1	1782.19		1777.93					H= 4.26'			1				
							1777.93	1777.09	.0030		276'			75.9	84.4					
SS-1	MH-3	192+98	16'Rt.		1	1781.33	1777.09	1777.09					H=4.24'			1				
							1777.09	1776.12	.0030		321'			92.1	98.2					
SS-1	MH-2	189+73	16'Rt.		1	1780.62	1776.12	1776.12					H=4.50'			1				
							1776.12	1775.10	.0030		336'			101.3	102.7					
SS-1	MH-1	186+33	16.4'Rt.				1775.10	1775.10					EXISTING MANHOLE. ATTACH 8" PVC TO 8" STUBOUT.							
													BEGIN SERVICE LATERALS							
SD-4	Lat.	167+44	55'Lt.				1764.16	1763.93	.0100	23'				8.9	8.7		10			10
SD-5	Lat.	173+45	55'Lt.				1767.96	1767.73	.0100	23'				6.9	6.7					
SD-5	Lat.	174+50	55'Lt.				1768.97	1768.74	.0100	23'				5.6	5.4					
SD-5	Lat.	176+44	55'Lt.				1769.94	1769.71	.0100	23'				5.3	5.1					
SD-5	Lat.	177+28	55'Lt.				1770.35	1770.12	.0100	23'				5.2	5.0					
SD-5	Lat.	184+53	55'Lt.				1775.65	1774.47	*	52'		18'	* SEE SHEET SS-3 FOR PROFILE	4.5	4.1					
SS-1	Lat.	185+32	55'Rt.				1775.43	1775.03	.0100	40'			CONCRETE ENCASE OVER 36" WATER PIPE SEE DETAIL SHEET W-8	5.0	4.7					
SS-1	Lat.	190+06	55'Lt.				1777.60	1776.89	.0100	71'				4.9	4.5					
SS-1	Lat.	191+75	55'Rt.				1777.78	1777.39	.0100	39'				3.4	3.2					
						TOTAL				317'	2729'	18'	FOR USE TOTALS, SEE STRUCTURE LIST SHEET NO. S-7 TOTAL	3344.7	3332.8	10	10			10

107V3989

67020