

SANITARY SEWER SCHEDULE

PED. NO. REG. NO.	STATE	PROJECT NO.	COUNTY	SHEET NO.
9	NEVADA	M-610(5)	CLARK	38-6

SHEET NO.	STRUCTURE - LINE			STRUCTURE TYPE			ELEVATION			LINE SIZE & LENGTH				REMARKS	QUANTITIES							
	NO.	LOCATION		MANHOLES	GRATE, RIM OR COVER	INVERT		SLOPE FT./FT.	PVC PIPES SDR 35		DUCTILE IRON PIPES CL 50		STRUCTURE EXCAVATION		GRANULAR BACKFILL	TYPE 1 MANHOLE	REMOVAL OF CURB & GUTTER	REMOVAL OF SIDEWALK	CLASS A CONCRETE SIDEWALK (4" INCH)	CLASS A CONCRETE GUTTER (TYPE B)		
		STA.	OFFSET			TYPE 1	IN		OUT	6"	8"	6"										
SS-1	Lat.	193+80	55' Lt.			1778.71	1778.00	.0100	71'				4.3	3.9								
SS-3	Lat.	202+67	55' Lt.			1779.07	1778.19	.0100	88'				23.4	22.7								
SS-3	Lat.	211+66	55' Lt.			1773.54	1773.25	.0040	73'				118.2	117.2								
SS-3	MH-13	211+66	20' Rt.	1	1785.16	1773.25	1773.15															
SD-8	Lat.	218+41	55' Lt.			1780.34	1775.72	*	57'		18'		27.7	26.7								
SD-4	Lat.	160+63	55' Rt.			1766.30	1761.79	*	69'		18'		8.1	7.6								
SD-4	Lat.	159+30	55' Lt.			1760.70	1760.49	.0100	21				15.6	15.3								
SD-4	MH-16	159+30	32' Lt.	1	1769.36	1760.49	1760.39															
SD-4	Lat.	156+50	55' Lt.			1759.98	1759.75	.0100	23				15.7	15.5								
SD-4	MH-14	156+50	32' Lt.	1	1769.40	1759.75	1759.17															
SD-3	Lat.	151+17	55' Lt.			1756.26	1756.03	.0100	23				17.1	16.9								
SD-3	MH-15	151+17	32' Lt.	1	1765.09	1756.03	1755.45															
SS-2	Lat.	W*23+25	55' Lt.			1766.42	1766.22	.0100	20				19.3	19.1								
SS-2	MH-6	W*23+25	35' Lt.			1766.22	1766.00															
						TOTAL				305'	140'	36'										
FOR USE TOTALS, SEE STRUCTURE LIST SHEET NO. S-7 TOTAL													249.4	244.7	4							

107V3989

67021