

67010

FED. RD. REG. NO.		STATE	PROJECT NO.	COUNTY	SHEET NO.
9		NEVADA	M-610(5)	CLARK	TS-17

ITEM NO.	ITEM	TOTAL	USE TOTAL	UNIT
627-0110	Permanent Signs (Ground Mounted) (Metal Supports)	326.00	330.00	Sq.Ft.
627-0140	Permanent Signs, Remove	269.25	270.00	Sq.Ft.

GENERAL NOTES

1. SIGN NUMBERS SHOWN ON SIGN SUMMARY ARE TAKEN FROM THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, 1988, EDITION, AND STANDARD HIGHWAYS SIGNS - NEVADA SUPPLEMENT.

2. POST LENGTHS PERTAIN TO THE TYPE OF POST AS SHOWN ON THE SIGN SUMMARY. IF THE CONTRACTOR CHOOSES ONE OF THE OTHER TYPES SHOWN IN OUR STANDARD PLANS, THE CONTRACTOR MUST FURNISH A SIGN SUMMARY DEPICTING THE APPROPRIATE POST AND CORRESPONDING POST LENGTH. THIS SIGN SUMMARY MUST BE APPROVED BY THE TRAFFIC ENGINEERING DIVISION PRIOR TO THE FABRICATION OF THESE ALTERNATE POSTS.

3. INSTALLATION NUMBERS WITH AN "R" SIGNIFY REMOVAL.

4. ALL SIGNAL REMOVALS SHALL BE DELIVERED TO THE CITY OF LAS VEGAS YARDS.

5. DISTANCE FROM EDGE OF TRAVEL WAY TO NEAR EDGE OF SIGN SHALL BE MINIMUM AS SHOWN ON STANDARD SHEET T-31.1.1., REV. 11.

6. POST LENGTHS FOR ALL GROUND MOUNTED SIGNS ARE CALCULATED TO THE NEAREST INCH. ALL SINGLE POST LENGTHS ARE BASED ON THE USE OF A SIGN ISLAND. SEE STANDARD SHEET T-31.1.1., REV. 11.

7. TYPE III REFLECTIVE SHEETING SHALL BE USED ON INSTALLATION NOS. 2, 3, 4, 7, 11, 12, 16, 18, 19, 20, 21, 22, 23, 25, 26 AND 30.

107V3989