QUANTITIES

REVISIONS

NO.	DESCRIPTION	DATE

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET 4	5	6	7	8	9	10
1		2" AC PAVEMENT	S.Y.	8416					2353	2671	3392
2		3¾" AC PAVEMENT	S.Y.	6008	3507	2496					
3		TYPE 2 GRAVEL BASE	C.Y.	1949	484	346			309	374	436
4		24" "L" CURB & GUTTER	L.F.	1492	631	590			31	185	55
5		24" ROLLED CURB & GUTTER	L.F.	1929					508	830	591
6		"A" TYPE CURB	L.F.	2474					695	547	1232
7		4' CONCRETE SIDEWALK	S.F.	2700		2700					
8		5' CONCRETE SIDEWALK	S.F.	3216	3216						
9		CONCRETE VALLEY GUTTER	S.F.	1901	908	432			223	338	
10		CONCRETE AT TRASH STRUCTURES	S.F.	660					180	300	180
11		CONCRETE DRIVEWAY APRONS	S.F.	3640					744	1392	1504

WATER:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10
1		1½" P.V.C.	L.F.	773				773			
2		2" P.V.C.	L.F.	132				132			
3		4" A.C.P.	L.F.	379				379			
4		6" A.C.P.	L.F.	387				387			
5		8" A.C.P.	L.F.	1196				1196			
6		10" A.C.P.	L.F.	183				183			
7		FIRE HYDRANT ASSEMBLY	EA.	7				7			
8		4" GATE VALVE	EA.	2				2			
9		6" GATE VALVE	EA.	3				3			
10		8" GATE VALVE	EA.	5				5			
11		10" GATE VALVE	EA.	1				1			
12		8" x 4" FMCT	EA.	1				1			
13		2" BLOWOFF	EA.	3				3			

SEWER:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10
1		4" PVC LATERALS	L.F.	342			342				
2		6" PVC SEWER MAIN	L.F.	1472			1472				
3		8" PVC SEWER MAIN	L.F.	55			55				
4		48" DIA. MANHOLE	EA.	7			7				
5		CLEANOUT	EA.	8			8				

STREET LIGHTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10
1		250W HPS MISSION BELL LUM. W/ CONC. POLE	EA.	8				8			

MISCELLANEOUS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10
1		12" PVC STORM DRAIN	L.F.	528			528				
2		18" RCP STORM DRAIN	L.F.	68			68				
3		MANHOLES	EA.	2			2				
4		TYPE "A" DROP INLET LENGTH 7'	EA.	1			1				
5		CATCH BASIN W/GRATE	EA.	4			4				
6		SIDEWALK DRAIN	EA.	1			1				
7		STOP SIGN	EA.	1			1				
8		STREET SIGN	EA.	1			1				
9		5' WD. DRAINAGE GUTTER	L.F.	30			30				
10		12" PVC STORM DRAIN W/ CONC. COLLAR	L.F.	14			14				
11	SEC B/8	1.5' TO 3.6' RETAINING WALL	L.F.	415					195		220
12	SEC A/8	2.4' TO 3.2' RETAINING WALL	L.F.	213						163	50
13		CLV BARRICADE	EA.	1	1						
14		STOP SIGN	EA	2				2			
15		STREET NAME	EA	2				2			

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

APPROVAL

CLV CHIEF LAND DEVELOPMENT DATE

REV DATE DESCRIPTION

RECOMMENDED FOR APPROVAL
DAVID P. N. HUCKLE
R.E. NO. 8256 DATE 4-5-88

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

LEWIS HOMES OF NEVADA
LAKESIDE CONDOMINIUMS NO. 1
ESTIMATE OF QUANTITIES

SHEET 3 OF 11 SHEETS

JOB NO. 5543.8590

20-7-40 107Y-2021-1