

# QUANTITIES

SHEET NO. → 9 10 11 12 13 14 15 16 17 18 19

## STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET											
					9	10	11	12	13	14	15	16	17	18	19	
1		2" AC. PAVE. W/4" TYPE 2, 6" TYPE 1 GB.	SY	24535				3074	3568	2914	1901	2454	2718	2582	2467	2862
2		STD. "L" TYPE CURB & GUTTER W/6" TYPE 1 GB.	LF	10420				1376	1420	1209	828	1081	1154	1093	1055	1204
3		3.5' CONC. SIDEWALK W/3" TYPE 2 GB.	SF	23551				2973	4207	4270	1627	1593	2649	2368	1861	2043
4	**	CONC. DRIVEWAY W/8" TYPE 2 GB.	SF	13009				1845	542	2062	1302	1085	1519	1519	1845	2170
5		6' VALLEY GUTTER W/10" TYPE 1 GB.	SF	3271					1657	368		417	829			
<p>** NOTE: APPROXIMATE DRIVEWAY QUANTITY. FINAL QUANTITY TO BE DETERMINED FROM MODEL SCHEDULE SHOWN ON THE PLOT PLAN. THIS QUANTITY IS BASED ON A 27' BOTTOM + 4' X WIDTH OF SIDEWALK (108.5 S.F. PER DRIVEWAY).</p>																

## WATER:

1		STD. F.H. W/6" GV. & 6" A.C.P. LATERAL	* EA.	11												
2		6" A.C.P.	* LF.	3896												
3		8" A.C.P.	* LF.	1435												
4		6" GATE VALVE W/VALVE BOX & COVER	* EA.	8												
5		8" GATE VALVE W/VALVE BOX & COVER	* EA.	5												
6		3/4" SERVICE	* EA.	128												
7		METER BOX	* EA.	128												
8		3/8" METER (INSTALLATION BY LVVWD)	* EA.	128												
9		2" BLOW-OFF ASSEMBLY	* EA.	3												
<p>* NOTE: SEE SHEETS NO. 1 &amp; 2 OF (WATER PLANS) ATTACHED TO BACK OF THIS PACKAGE</p>																

## SEWER:

1		STD. MANHOLE	EA.	20												
2		8" P.V.C.	LF.	5147				3	4	4	1	1	3	2	1	2
3		4" P.V.C. LATERAL	LF.	3483	1653	1830	780	458	610	394	655	659	456	395	631	

## STREET LIGHTS:

1		100 W HPS LUMINAIRE W/CONC. POLE	EA.	32		10	10									
2		3/2" PULL BOX W/METAL COVER	EA.	8		3	5									

## MISCELLANEOUS:

1		6" D-3 STREET NAME SIGN	EA.	12		6	10									
2		STOP SIGN	EA.	1												
3		END OF ROAD MARKER	EA.	2		1	1									
4		4" SCH. 40 PVC SLEEVE	LF.	60		60	1210									
<p>EXCAVATION: CUT 53,100 C.Y. FILL 39,850 C.Y.</p> <p>NOTE: EXCAVATION QUANTITIES ARE RAW QUANTITIES AND DO NOT INCLUDE SUBSIDENCE AND SHRINKAGE FACTOR.</p>																

**NOTE TO CONTRACTOR**  
QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

JOB NO. 5543.8620

REVISIONS  
NO. DESCRIPTION DATE

REV. DATE

DATE 1-15-23  
R.E. NO. 5256

DAVID P. N. HUCKLE

G.C. WALLACE, INC.  
Engineering/Architecture  
1535 SOUTH HANSEN WAY BRIDGESIDE, NVADA 89115

LEWIS HOMES OF NEVADA  
LEWIS HOMES - LAKES WEST NO. 1

ESTIMATE OF QUANTITIES

SHEET 8 OF 25 SHEETS