

QUANTITIES

SHEET NO. 7 8 9 10

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET									
1		2" CONC. DRIVE W/4" TYPE 2 G.R.	S.F.	50,000	14,815	22,070	19,180							
2		STD. "L" TYPE CURB & GUTTER W/6" TYPE 1 G.R.	L.F.	2,100	530	1153	909							
3		3" CONC. SIDEWALK W/5" TYPE 2 G.R.	S.F.	2,100	2057									
4		3" CONC. SIDEWALK W/5" TYPE 2 G.R.	S.F.	4,100		2289	1830							
5	*	CONC. DRIVEWAY W/5" TYPE 2 G.R.	S.F.	4,930	1080	1704	1312							
6		6" VALLEY GUTTER W/10" TYPE 1 G.R.	S.F.	430	430									
		*DRIVEWAY QUANTITY IS APPROXIMATE THE QUANTITY IS BASED ON 24 FT. X WIDTH OF THE SIDEWALK. FINAL QUANTITY SHALL BE DETERMINED FROM THE MODEL SCHEDULE SHOWN ON THE PLOT PLAN.												

WATER:

1		STD. FH. W/6" G.V. AND 6" ACP LATERAL	EA.	3	3									
2		8" A.C.P.	L.F.	141	141									
3		6" A.C.P.	L.F.	1094	1094									
4		3/4" SERVICE	EA.	41	41									
5		3/4" METER (BY L.V.V.W.D.)	EA.	53	53									
6		METER BOX	EA.	53	53									
7		6" GATE VALVE	EA.	1	1									
8		2" SERVICE W/METER BOX	EA.	1	1									
9		2" METER (BY L.V.V.W.D.)	EA.	1	1									

SEWER:

1		STANDARD MANHOLE	EA.	5	1	2	2							
2		8" PVC	L.F.	1310	230	590	470							
3		4" PVC LATERAL	L.F.	1237	1237									

STREET LIGHTS:

1		100 WATT H.P.S. LUMINAIRE W/11 GA. POLE	EA.	5	5									
---	--	---	-----	---	---	--	--	--	--	--	--	--	--	--

MISCELLANEOUS:

1		48" X 24" W-L-D DIRECTION ARROW	EA.	1	1									
2		6" O.B. STREET NAME SIGN	EA.	4	4									
3		RED END OF ROAD REFLECTOR	EA.	1	1									

APPROVAL

CLV CHIEF LAND DEVELOPMENT
AND FLOOD CONTROL

DATE

SHEET

6

OF 13 SHEETS

G. C. WALLACE
Consulting Engineers, Inc.
1100 East Sahara Ave. • Las Vegas, Nevada 89104 • 732-3330

LEWIS HOMES OF NEVADA
LEWIS HOMES - RAINBOW VISTA NO. 2
ESTIMATE OF QUANTITIES

JOB NO. 427-620

25-7-74 107Y-2032-2