

QUANTITIES

SHEET NO.

REVISIONS
NO DESCRIPTION DATE

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL
		3/4" AC PAVE W/4" TYPE 2, 4" TYPE 1* G.B.	SY	7135
		2" AC PAVE W/4" TYPE 2, 6" TYPE 1* G.B.	SY	7498
		STD. "L" TYPE CURB & GUTTER W/6" TYPE 1* G.B.	LF	4915
		6" CONC. SIDEWALK W/5" TYPE 2 G.B.	SF	9870
		3" CONC. SIDEWALK W/5" TYPE 2 G.B.	SF	1,012
		3.5" CONC. SIDEWALK W/5" TYPE 2 G.B.	SF	6,555
		CONC. DRIVEWAY W/8" TYPE 2 G.B. **	SF	3,780
		10" VALLEY GUTTER W/10" TYPE 1* G.B.	SP	556
		6" VALLEY GUTTER W/10" TYPE 1* G.B.	SP	340
		* NOTE: NATIVE MATERIAL TO BE USED IN LIEU OF IMPORTED TYPE 1		
		** NOTE: FINAL DRIVEWAY QUANTITY TO BE DETERMINED FROM THE MODEL SHOWN ON PLOT PLAN. QUANTITIES SHOWN ARE APPROXIMATE IT IS BASED ON 16' RIM PLUS 4' X WIDTH OF SW		

TOTALS BY SHEET

WATER:

		STD. FH W/6" GV & 6" A.C.P. LATERAL	EA	2
		8" ACP	LF	1247
		6" ACP	LF	239
		4" ACP	LF	87
		3/4" WATER SERVICE	EA	60
		5/8" WATER METER (INSTALLATION BY LVWD)	EA	54
		METER BOX	EA	54
		3" G.V. W/ VALVE BOX & COVER	EA	1
		2" BLOW-OFF ASSEMBLY	EA	1

SEWER:

		STD. MANHOLE	EA	14
		10" PVC	LF	627
		8" PVC	LF	1513
		4" PVC LATERAL	LF	1623
		4" WYES		

STREET LIGHTS:

		100W. HPS LUMINAIRE W/ 11 GA. POLE	EA	9
		250 W HPS LUMINAIRE W/ 11 GA. POLE	EA	10

MISCELLANEOUS:

		6" D-3 STREET NAME SIGN	EA	4
		STOP SIGN	EA	2
		W1-B TRAFFIC DELINEATORS	EA	3
		EXCAVATION	C.Y.	15,300

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

DESCRIPTION

DATE

REV

3794 2/26/67
R.E. NO. DATE

RECOMMENDED
LEONARD V. DALUNA

1555 S. HENDERSON BLVD. LAS VEGAS, NEVADA 89102

G.C. WALLACE, INC.
Engineering/Architecture



LEWIS HOMES OF NEVADA

LEWIS HOMES - RAINBOW VISTA NO. 8

ESTIMATE OF QUANTITIES

SHEET

6

OF 15 SHEETS

JOB NO. 427.580