

QUANTITIES

SHEET NO. → **3 9 10 11 12 13 14 15 16 17 18 19 25**

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET																
1	*	4" AC PAVEMENT W/4" TYPE 2, 9" TYPE 1 GB	SY	4071																	
2	*	2" AC PAVEMENT W/4" TYPE 2, 6" TYPE 1 GB	SY	7196																	
3	*	STD "L" TYPE CURB & GUTTER W/6" TYPE 1 GB	LF	6412																	
4	*	5' CONC. SIDEWALK W/5" TYPE 2 GB	SF	12683																	
5	*	4.5' CONC. SIDEWALK W/5" TYPE 2 GB	SF	8769																	
6	**	CONC. DRIVEWAY W/8" TYPE 2 GB	SF	8790																	
7	*	8' CONC. VALLEY GUTTER W/10" TYPE 1 GB	SF	3093																	
8		REMOVE EXISTING A.C. PAVEMENT	SY	373																	
9	*	3" AC PAVEMENT W/4" TYPE 2, 9" TYPE 1 GB	SY	6507																	
10		TEMP. A.C. PAVEMENT TRANSITION	SY	1176																	
NOTE:				OWNER AGREES THAT IF EXISTING NATIVE SOIL DOES NOT CONFORM TO SPECIFICATIONS FOR TYPE 1 BASE, THE OWNER SHALL IMPORT TYPE 1 BASE FOR A.C. PAVEMENT AND COMPLY WITH CITY OF LAS VEGAS STANDARDS.																	
NOTE:				FINAL DRIVEWAY QUANTITY TO BE DETERMINED FROM THE MODEL SHOWN ON THE PLOT PLAN. QUANTITIES IN THIS ESTIMATE ARE ONLY APPROXIMATE AND ARE BASED ON 16' BTM PLUS 4' X WIDTH OF THE SIDEWALK.																	

WATER:

1		STD FH W/6" G.V. & 6" ACP LATERAL	EA	5																		
2		12" ACP	LF	1532																		
3		8" ACP	LF	1055																		
4		12" GATE VALVE W/VALVE BOX & COVER	EA	5																		
5		8" GATE VALVE W/VALVE BOX & COVER	EA	5																		
6		3/4" WATER SERVICE	EA	98																		
7		3/8" METER (INSTALLATION BY L.V.V.W.D)	EA	94																		
8		METER BOX	EA	94																		
9		2" BLOW-OFF ASSEMBLY	EA	4																		
10		CONNECT TO EXIST 12" WATER	EA	1																		
11		6" ACP	LF	1225																		
12		6" GATE VALVE W/VALVE BOX & COVER	EA	3																		
OFF-SITE WATER																						
1		12" ACP	LF	1,109																		
2		12" WET TAP W/12" GATE VALVE W/B & C	EA	1																		

SEWER:

1		4' DIA. STANDARD MANHOLE	EA	12																		
2		8" PVC	LF	3590																		
3		4" PVC. SERVICE LATERAL W/PLUG	LF	2466																		
OFF-SITE SEWER																						
1		4' DIA STANDARD MANHOLE	EA	4																		
2		8" PVC	LF	770																		
3		4" PVC. WYE W/PLUG	EA	16																		

STREET LIGHTS:

1		100 W HPS. LUMINAIRE W/116A. POLE	EA	15																	
2		250 W HPS. LUMINAIRE W/116A. POLE	EA	7																	
3		#3 1/2 PULL BOX W/METAL COVER	EA	4																	

MISCELLANEOUS:

1		9" STREET SIGN NAME	EA	7																		
2		6" STREET SIGN NAME	EA	2																		
3		STOP SIGN	EA	3																		
4		10M-3R" EDGE OF ROAD MARKERS	EA	11																		
5		REMOVE & RELOCATE 10M-3R" EDGE OF ROAD MARKERS	EA	4																		
6		STREET BARRIERS	EA	6																		
EXCAVATION:																						
CUT - 23,842																						
FILL - 12,878																						

NOTE: EXCAVATION QUANTITIES ARE RAW QUANTITIES AND DO NOT INCLUDE SUBSIDENCE & SHRINKAGE FACTOR

NOTE TO CONTRACTOR
 QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

JOB NO. 427.690

REVISIONS
 NO. DESCRIPTION DATE

DATE: 7/2/97
 REV. PAIEMENT QUANTITIES TO REFLECT TEMP. A.C. PAIEMENTS: *CLM* 8/16/97

RECORDED & INDEXED
 DAVID P. NICKOLE, JR.

1555 SOUTH RAINBOW BLVD / LAS VEGAS, NEVADA 89102

G.C. WALLACE, INC.
 Engineering/Architecture

LEWIS HOMES OF NEVADA
 LEWIS HOMES - RAINBOW VISTA NO. 9

ESTIMATE OF QUANTITIES

SHEET
7
 OF 25 SHEETS

