

TOTAL ELECTRICAL QUANTITIES							
ITEM	DESCRIPTION	B-BALL	TENNIS			TOTAL	UNIT
400.0336	36 INCH TRENCH AND BACKFILL	1270	1130			2400	LF
400.0506	6' DEEP FOUNDATION		21			21	EA
400.0511	11'-6 IN. DEEP FOUNDATION	20				20	EA
400.1330	35' FLOODLIGHTING POLES 2 INCH		8			8	EA
400.1331	35' FLOODLIGHTING POLES 3 INCH		4			4	EA
400.1333	40' FLOODLIGHTING POLES 2 INCH		4			4	EA
400.1334	40' FLOODLIGHTING POLES 3 INCH		1			1	EA
400.1336	80' FLOODLIGHTING POLES	16				16	EA
400.1340	INSTALLATION TENNIS STANDARDS		21			21	EA
400.1345	40' FLOODLIGHTING POLES MODIFY		4			4	EA
400.135	1 INCH P.V.C. SCH 40 CONDUIT		729			729	LF
400.1352	1-1/4 IN. LIO TIGHT FLEX CONDUIT	250				250	LF
400.136	1-1/2 INCH P.V.C. SCH 40 CONDUIT	132	1242			1374	LF
400.137	2 INCH P.V.C. SCH 40 CONDUIT	1215	473			1688	LF
400.138	3 INCH P.V.C. SCH 40 CONDUIT		210			210	LF
400.139	4 INCH P.V.C. SCH 40 CONDUIT	70				70	LF
400.143	NO. 3-1/2 PULL BOX	17				17	EA
400.2100	5/8 IN. DIA 8' COPPERWELD GR ROD		2			2	EA
400.2400	1500 WATT FLOODLIGHT	168				168	EA
400.2410	1500 WATT QUARTZ FLOODLIGHTING		96			96	EA
400.2500	SECURITY 400 WATT FLOODLIGHTS	4				4	EA
400.2510	SECURITY 300 WATT FLOODLIGHTS		4			4	EA
400.2610	WIRE TROUGH 2 LAMP		4			4	EA
400.2611	WIRE TROUGH 4 LAMP		8			8	EA
400.2612	WIRE TROUGH 5 LAMP		4			4	EA
400.2613	WIRE TROUGH 2 PAIR 4 LAMP		5			5	EA
400.2710	ASSEMBLY 2 LAMP CLUSTER		4			4	EA
400.2711	ASSEMBLY 4 LAMP CLUSTER		8			8	EA
400.2712	ASSEMBLY 5 LAMP CLUSTER		4			4	EA
400.2713	ASSEMBLY 2 PAIR 4 LAMP CLUSTER		5			5	EA
400.3050	FLOODLIGHT PLATFORMS 'A'	2				2	EA
400.3051	FLOODLIGHT PLATFORMS 'B'	4				4	EA
400.3052	FLOODLIGHT PLATFORMS 'C'	10				10	EA
400.3055	INSTALLATION BASEBALL POLES	20				20	EA
400.3060	CABINET 12 X 18 X 4 INCH	22				22	EA
400.3061	CABINET 10 X 12 X 4 INCH	3				3	EA
400.3065	INSTALLATION CABINETS, DUPLEX	3				3	EA
400.3070	CIRCUIT BREAKER 480 V 3 POLE	1				1	EA
400.3071	CIRCUIT BREAKER 120 V 1 POLE	3				3	EA
400.3080	KEY OPERATED CONTROLS UPGRADE	1				1	EA
400.3090	PHOTO-ELEC. LIGHTING CONTROLS		1			1	EA
400.3100	SWIVEL BRACKET		1			1	EA
400.3110	150 K.V.A. 3 PHASE TRANSFORMER		1			1	EA
400.3120	SWITCHGEAR AND CONTROL CENTER		1			1	EA
400.3130	TRANSFORMER AND SWITCHGEAR PAD		1			1	EA
400.3140	KEY OPERATED CONTROLS		1			1	EA
400.4530	RELOCATE POLES AND PLATFORMS	4				4	EA
400.8500	FUSEHOLDER 2 POLE	168				168	EA
400.8501	FUSEHOLDER 1 POLE		96			96	EA
400.8510	10 AMP FUSE	336	96			432	EA
400.890	CONDUCTOR SUPPORT CABLE	2380				2380	LF
400.9004	NO. 4 MHD SOLID BARE CONDUCTOR	1450	1258			2708	LF
400.9106	NO. 6 THW CONDUCTOR	19284	12702			31986	LF
400.9108	NO. 8 THW CONDUCTOR	7574				7574	LF
400.9112	NO. 12 THW CONDUCTOR		3144	6140		3144	LF
400.9130	NO. 3/0 THW CONDUCTOR		64			64	LF
400.9140	11. 4/0 THW CONDUCTOR		1896			1896	LF
400.9312	2 COND. NO. 12 STR CU SO CORD	1512				1512	LF
999.100	CLEANING & FINAL CLEAN UP	1				1	LS

CONTRACT  
DRAWING  
MAR 5 1973

AS BUILT

NO.	DESCRIPTION	BY	DATE	APPROVAL
REVISIONS				
CITY OF LAS VEGAS NEVADA DEPARTMENT OF PUBLIC WORKS SERVICES DIVISION				
LORENZI PARK POWER & LIGHTING				
TOTAL ELECTRICAL QUANTITIES				
W.O. NO. 3114	F.B.K. NO. N/A	DATE	DRAWING NO.	
SC. (H) N/A	SC. (V) N/A	2-22-73	650.19-22	
DR. K.B.C.		2-22-73	FILE NO.	
APPROVED BY DIRECTOR OF PUBLIC WORKS			2-27-73	
<i>[Signature]</i>			SHEET E 10	

*Fjm*  
*QC*  
*2/23/73*  
*RB*  
*2/26/73*  
*NJ*  
*2-27-73*