



APPROXIMATE QUANTITIES - THIS SHEET

ITEM No.	DESCRIPTION	C.L.V.	S.I.D.	UNIT.	TOTAL
203.00.01	ROADWAY EXCAVATION	34	576	C.Y.	610
	SAWCUT A.C. PAV'T	400	860	L.F.	1260
	REMOVE AC PAV'T	219	1233	S.Y.	1452
302.00.01	TYPE I GRAVEL BASE	-	266	C.Y.	266
302.00.02	TYPE II GRAVEL BASE	25	142	C.Y.	167
401.00.03A	1/2" ASPHALT CONC. OVERLAY	-	76	T.N.	76
401.00.03B	1-1/2" A.C. SIDEWALK	19	-	T.N.	19
401.00.06	3" ASPHALTIC CONCRETE	-	224	T.N.	224
413.00.01	24" "L" TYPE C & G 6" FACE	-	720	L.F.	720
340.319	CONCRETE VALLEY GUTTER	-	502	S.F.	502
609.03.02	ADJUST SEWER MANHOLE	2	-	Eq.	2
	TACK COAT	-	130	-	130
609.03.06	ADJUST WATER VALVE	-	-	Eq.	2
406.00.01	PRIME COAT	-	452	Gal.	452
407.00.01	FOG SEAL	33	323	Gal.	356
629.00.01	RELOCATE FIRE HYDRANT	1	-	Eq.	1

BENCH MARK  
 B.M. 1617A17  
 N.W. CORNER PENNWOOD  
 & VALLEY VIEW  
 ELEV. = 2152.54 ft.

AUG. 10, 1979

CURVE DATA

No.	DELTA	RADIUS	TANGENT	LENGTH	LOCATION
①	87°02'42"	15'	14.75'	22.79'	B.C.
②	92°57'18"	15'	15.79'	24.34'	B.C.

Scale (H) 1" = 20'    Scale (V) 1" = 2'

Fid. bk. no. 7-7-4-X    Date

Design by C. KAJKOWSKI    Drawn by ARBERY/RAMIREZ

Approved by the Director of Public Services    Date 4/19/79

William Ramirez

Department of Public Services    Engineering Design Division

STREET IMPROVEMENTS

MEADE AVE S.I.D.

VALLEY VIEW TO RANCHO

STA. 4+00 TO 8+00

W.O. no. 4240

Revisions

Date

Drawing no. 107-V1017 5/18

