



CLASS "A-SPECIAL"
P.V.M.T. REPLACEMENT
BID ITEM No. II

CAUTION:
15,000 VOLT ELECTRICAL
CABLE IN SAME DITCH
AS TELEPHONE CABLE
30" COVER

NOTE:
FROM STA. 66+76 TO STA. 88+67.3 ALL EXCAVATED
MATERIAL SHALL BE DISPOSED OF BY THE CONTRACTOR
AS IT IS BEING REMOVED FROM THE TRENCH.
TOTAL DEPTH OF TRENCH SHALL BE BACKFILLED WITH
GRAVEL AS SPECIFIED.
SEE SPECS. FOR REQUIREMENTS ON OPEN TRENCH.

NOTE:
PROFILE ON SURVEY LINE

PLAN
EXISTING MANHOLE AT 25TH STREET
AND CHARLESTON BLVD.

PLAN
EXISTING MANHOLE

NOTE:
CONTRACTOR TO REMOVE BRICK AND MORTAR
DIKE IN EXISTING MANHOLE TO RELIEVE
FLOW IN 30" SEWER ON 23 RD STREET
BEFORE CONNECTING NEW SEWER AT
MESQUITE AVE.
DIKE TO BE PARTIALLY REPLACED TO
ELEVATION GIVEN BY THE ENGINEER

AS BUILT NOTE:
DIKE WAS ONLY PARTIALLY REMOVED.
TWO COURSES OF BRICK (APPROX 9")
WAS LEFT IN PLACE. THIS MUCH DIKE
WAS FOUND TO DIVIDE THE FLOW SO
THAT THE 30" PIPE AT 23RD ST. & MESQUITE
WAS FLOWING APPROX. 1/2 FULL AT PEAK FLOW
WITH ALL TIE-IN FLOWING INTO THE NEW
OGDEN-MESQUITE LINE. 12-3-1965

SCALE
HORIZONTAL - 1"=20'
VERTICAL - 1"=10'

APPROVED
DIRECTOR OF PUBLIC WORKS
R. P. SAUER 5-27-66
R. P. SAUER
SUPERINTENDENT OF SANITATION
L. A. ANTON 5-27-66
L. A. ANTON

AS BUILT

	JOHN CAROLLO ENGINEERS PHOENIX - BERKELEY LAS VEGAS, NEVADA OGDEN-MESQUITE AVE. SEWER MAIN ST. TO 23 RD. ST. PLAN & PROFILE STA. 81+60 TO 89+75		
	DESIGNED B.M.L.	CHECKED B.M.L.-PW	DATE APR 65
DRAWN DC. TD.	TRACED	REVISED	DRAWING NO. 7821B-1421.5 SHEET 10 OF 11