


CAUTION
LOCATE EXISTING POWER & GAS SERVICES PRIOR TO CONSTRUCTION.

ABANDONED VALVES
The Contractor shall abandon all existing valves where shown on the drawings by removing a minimum of the top 12 inches of the valve box and then filling the remaining portion of the valve box with concrete having a compressive strength of at least 2,000 psi. All valves to be abandoned shall be abandoned in the closed position unless shown otherwise on the drawings. The Contractor shall then backfill and repave the area disturbed during abandonment of the valve in accordance with the most current draft or edition of Uniform Standard Specifications for Public Works Construction Offsite Improvements Clark County area.

* = POWER & GAS SERVICE
NOTE: ALL LOTS WILL BE CUSTOM HOMES. SEE SHEET 25 FOR UTILITY SERVICE CONSTRUCTION.

REV	DATE	DESCRIPTION
1	7/6/87	RELOCATE EXIST. PIPE HYDRANT
2	7/6/87	ADD NOTES



G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD. LAS VEGAS, NEVADA 89102

FOOTHILLS COUNTRY CLUB UNIT NO. 2
AT PECOLE RANCH
UTILITY PLAN UNIT NO. 2

APPROVAL
[Signature]
CLV CHIEF LAND DEVELOPMENT
DATE 8-10-87

SHEET
30
OF 26 SHEETS