

PLANT SCHEDULE					
SYMBOL	BOTANICAL NAME	COMMON NAME	QTY.	SIZE	REMARKS
TREES					
	CHILOPSIS LINEARIS 'LUCRETIA HAMILTON'	DWARF PURPLE DESERT WILLOW	4	24" BOX	3 TRUNK MINIMUM W/ 1" CALIPER TRUNKS
	FRAXINUS OXYCARPA 'RAMODDII'	RAYWOOD ASH	62	24" BOX	STANDARD TRUNK W/ 1 1/2" CALIPER
	PINUS ELДАРICA	MONDEL PINE	20	24" BOX	6' TO 8' HIGH & THICKLY BRANCHED
	PISTACIA CHINENSIS	CHINESE PISTACHE	20	24" BOX	5' STANDARD TRUNK WITH 1 1/2" CALIPER
	PROSOPIS CHILENSIS	CHILEAN MESQUITE	6	24" BOX	MULTI-TRUNK W/ 1" CALIPER TRUNKS
	PYRUS CALLERYANA 'BRADFORD'	BRADFORD PEAR	17	24" BOX	STANDARD TRUNK W/ 1 1/2" CALIPER
	SOPHORA SECUNDIFLORA	TEXAS MOUNTAIN LAUREL	13	24" BOX	MULTI-TRUNK 4' HIGH W/ 3" WIDTHS
PALM TREES					
	PHOENIX DACTYLIFERA 'DESOLET NOOR'	DESOLET NOOR DATE PALM	12	25' BTH (BROWN TRUNK HEIGHT)	EVENLY MATCHED, SHOVEL CUT TRUNK OR SIMILAR
EXISTING TREES					
	EXISTING CHILOPSIS	E1 THROUGH E7	1		
	EXISTING CHILEAN MESQUITE	E8 THROUGH E9	2		
RELOCATED TREES					
	RELOCATED CHILOPSIS LINEARIS	R1 THROUGH R4	4		CONTRACTOR TO USE A 54" SPADE TO RELOCATE CHILOPSIS. IF NEW HOLES CANNOT BE CREATED BY THE SPADE, DIG THE HOLES WITH A BACKHOE. REMOVE NATIVE SOIL AND BACKFILL WITH TOPSOIL. PROVIDE 85% COMPACTION PRIOR TO RELOCATION. IF TREES HAVE LEAVES, SPRAY TREES WITH ANTI-DESICCANTS PRIOR TO DIGGING AND (2) TWO APPLICATIONS AFTER RELOCATION.
SHRUBS					
	CASSIA NEMOPHILA	DESERT CASSIA	74	5 GAL	
	LEUCOPHYLLUM FRUTESCENS 'GREEN CLOUD'	GREEN TEXAS RANGER	76	5 GAL	
	LEUCOPHYLLUM LANGMANIAE 'RIO BRAVO'	RIO BRAVO SAGE	34	5 GAL	
	MYRTUS COMMUNIS 'COMPACTA'	COMPACTA MYRTLE	126	5 GAL	
	RAPHIOLEPIS INDICA 'JACK EVANS'	DWARF INDIAN HAWTHORN	110	5 GAL	
GROUND COVERS					
	ACACIA REDOLENS 'DESERT CARPET'	TRAILING ACACIA	53	5 GAL	
	BACCHARIS PILULARIS 'THOMPSON VARIETY'	DWARF COYOTE BUSH	137	5 GAL	
	LANTANA SPECIES 'NEW GOLD'	NEW GOLD LANTANA	71	1 GAL	
	PITTOSPORUM TOBIRA 'WHEELER'S DWARF'	DWARF MOCK ORANGE	111	5 GAL	
	TRACHELOSPERMUM JASMINOIDES	STAR JASMINE	32	5 GAL	
ACCENTS					
	CAESALPINIA GILLIESII	YELLOW BIRD OF PARADISE	15	15 GAL	
	HESPERALOE PARVIFLORA	RED YUCCA	83	5 GAL	
	YUCCA RECURVIFOLIA	KEEPPING YUCCA	34	5 GAL	

GENERAL NOTES:

- CONTRACTOR IS RESPONSIBLE TO VERIFY ALL PLANT QUANTITIES. THE PLANT LIST IS PROVIDED AS A REFERENCE ONLY.
- LANDSCAPE ARCHITECT IS TO APPROVE ALL PLANT MATERIAL PRIOR TO INSTALLATION WITH PRIOR NOTICE OF 48 HOURS.
- PLANT MATERIAL IS TO HAVE IDENTIFICATION TAGS ON 10% OF TOTAL QUANTITY OF EACH SPECIES, SHOWING GENUS, SPECIES AND VARIETY, ETC.
- PROVIDE MATCHING SIZES AND FORMS OF LIKE SHRUB SPECIES AS SHOWN ON DRAWINGS.
- DECOMPOSED GRANITE 1/2" MINUS, COLOR "PINK CORAL", 2" DEPTH TYPICAL IN ALL PLANTING BEDS. DECOMPOSED GRANITE TO CONTAIN 60% FINES AND 40% AGGREGATE. CONTRACTOR TO RECEIVE VERIFICATION OF THIS FROM THE SUPPLIER AND PRESENT VERIFICATION TO THE OWNER PRIOR TO ANY CONSTRUCTION.

WHOLESALE DEALER:
KALAMAZOO MATERIALS, INC.
6475 NORTH ORACLE ROAD
TUCSON, ARIZONA 85704
ATTN: PAUL D'ALESSIO
TELEPHONE: (520) 575-4601
FAX: (520) 575-4604
- IT IS THE INTENT OF THIS DRAWING TO CREATE AN IMMEDIATE AESTHETIC APPEARANCE. THIS PROJECT MAY REQUIRE VEGETATION REMOVAL AND/OR THINNING OUT AT A FUTURE DATE.
- CONTRACTOR TO COORDINATE AESTHETIC GRADING WITH ENGINEERING GRADING TO PROVIDE SITE DRAINAGE AS DESIGNED BY ENGINEER.
- CONTRACTOR TO PROVIDE POSITIVE DRAINAGE ON ALL SIDEWALKS.

LANDSCAPE PLANTING SCHEDULE

SCALE:

DATE	REVISIONS	W.A. #	SCALE (H)	SCALE (V)	DATE	DESIGN BY	C.A.W.D.H.
DEPT. OF PARKS & LEISURE ACTIVITIES LANDSCAPE PLANTING SCHEDULE				PROJECT: LIBRARY PARK			
DRAWING NO. 13.1 650.42				11 43			

