186.00 LF 27" PIPE VCP ONLY

22.87 LF 27" PIPE 1350-D RCP OR VCP

387.01 LF 27" PIPE 1350 D RCP OR VCP

27" PIPE

25.27' @ 0.0128

27" PIPE

186.50' @ 0.0126

EXIST. PLUG

REMOVE EXIST. PLUG & CONNECT EXIST PIPE TO M.H.

EXISTING 27" PIPE

APPROX. EXIST. ℄ GRADE

UNKNOWN UTILITY

27" PIPE

271.73' @ 0.0158

50.14' @ 0.0158

50.14' @ 0.0158

HORIZ. CURVE PULL JOINTS (SEE NOTE #8 SHT 1)

TYPE "B" 1/50

M.H. #50.23

M.H. #50.35

M.H. #50.36

PROFILE

SCALE: HORIZ. 1"=30'
VERT. 1"=6'

REV	DATE	DESCRIPTION
1	1/6/94	CHANGED JOINTS ACCORDING TO
2	10/95	AS BUILT - NO REVISIONS

RE NO. DATE

REGISTERED PROFESSIONAL ENGINEER STATE OF NEVADA MICHAEL D. ROSS CIVIL

G. C. WALLACE
Consulting Engineers, Inc.
1100 East Sahara Ave. · Las Vegas, Nevada 89104 · 732-3330

JONES BOULEVARD

CAUTION
FLOWLINE OF EXIST. DRAIN DITCH. CONTRACTOR TO REROUTE DURING CONSTRUCTION AND RECONSTRUCT DITCH AFTER INSTALLATION OF PIPE

CAUTION
2-3Ø UGD. PRIMARIES

27" PIPE

MATCH LINE - SEE SHEET #25

S. 80° 11' 11" W.

S. 88° 41' 08" W.

27" PIPE

EXISTING 27" PIPE

℄ STREET ℄ SURVEY LINE

S. 89° 16' 29" W.

27" PIPE

MATCH LINE - SEE SHEET #23

EXISTING GAS LINE TO BE PROTECTED OR RELOCATED.

UNKNOWN UTILITY CAN CUT IN PAVEMENT

BENCH MARK 184.0 (SHOWN ON SHT. 23)
STA. 184+02 - 28.6' LT. &
TOP OF FIRE HYDRANT
S.E. COR. O'BANNON DR. & REDROCK ST.
C.L.V. DATUM
ELEV. 2282.10

188+92.10 16.5' RT. REMOVE PLUG & CONNECT EXIST 27" VCP INTO M.H.

℄ PIPE CURVE DATA
Δ = 03° 23' 25"
R = 1000.00'
L = 59.17'
T = 29.59'

FUTURE STREET

NORTH
SCALE: 1"=30'

O'BANNON DRIVE

AS BUILT DRAWING

Department of Public Services
SAHARA - DAKEY SEWER INTERCEPTOR
PLAN & PROFILE 185+00 TO 194+00

SHEET 24 OF 65 SHEETS

JOB NO. 412.140

9/78 DIETERICH-POST 6532B

307-V 563 33-1-156