



GENERAL NOTES

- HOUSE SERVICES SHALL COMPLY WITH WESTERN PLUMBING CODE RE: SEPARATION DISTANCE.
- ALL HOUSES TO BE SERVED INDIVIDUALLY AS PER SECTION 313 OF THE UNIFORM PLUMBING CODE.
- CONTRACTOR SHALL FURNISH THE ENGINEER WITH AS-BUILT DRAWINGS SHOWING THE EXACT LOCATIONS OF ALL HOUSE CONNECTIONS.
- CONCRETE COLLARS TO BE CONSTRUCTED AROUND ALL MANHOLES AND WATER VALVES.

ESTIMATE OF QUANTITIES

STD. MANHOLES	27 EA
12" VCP SEWER MAIN	1830 ± LF
8" VCP "	4924 ± LF
4" VCP LATERAL (ON-SITE)	2840 ± LF
4" VCP " (OFF-SITE)	405 ± LF
4" WYES - (OFFSITE)	26 EA

APPROVED

William Purvis 3/8/78
CIV CITY ENGINEER DATE

R. H. Anty 2/27/78
CIV SANITATION ENGINEER DATE

William Miller 3/2/78
CIV FIELD OPERATIONS ENGINEER DATE

Ray R 3/3/78
CIV QUALITY CONTROL ENGINEER DATE

SUBMITTED

James L. MacFarlane 1/28/78
JAMES L. MACFARLANE PE DATE
NEW CERT 357E

CONSULTING ENGINEERS • PLANNERS			
2099 PASCADUE ROAD SAN ANTONIO, TEXAS 78205			
STEWART PLACE - UNIT G-A			
MASTER SEWER PLAN (CONTINUED ON SHEET 10)			
SCALE:	WO. NO. 2877-10	DATE 1-25-78	SHEET
HORIZ: 1" = 50'	DES. JZP	REV. 6-23-78	9
VERT:	CHK.	REV.	19

Rev. 6-23-78 - RAISED ALL R.P. 1/4" 4"

18-46-117 3074-2825-6A