



- PROPOSED FACILITIES:**
- ① PROPOSED 2" PE MAIN
  - ② PROPOSED 2" PE COUPLING #140-3504
  - ③ PROPOSED 2" PE 90 DEGREE ELBOW #140-3067
  - ④ PROPOSED 2" PE FULL FLOW TEE #140-3074

**INSTALLATION REQUIREMENTS**

1. NO STONES OR LUMPS GREATER THAN 2" PERMITTED IN TRENCH 2" OR LESS IN WIDTH.

2. TRENCH WIDTH BEYOND SUBGRADE AND PIPE ZONE REQUIREMENTS FOR UTILITY INSTALLATIONS SHALL CONFORM TO THE RESPECTIVE ENTITY REQUIREMENTS.

3. COVERED HOLES MAY BE USED FOR PIPE BEDDING ONLY IF MATERIAL HAS BEEN SPECIALLY APPROVED BY THE GOVERNING AGENCY. SEE STANDARD DRAWING NO. 508 FOR PIPE BEDDING METHODS.

4. LAS VEGAS VALLEY WATER DISTRICT REQUIRES PIPE BEDDING AND BACKFILL WITHIN THE PIPE ZONE TO BE OF THE SAME MATERIAL.

**MATCHLINE - SEE SHEET 3**

RTC STD DWG 503

NO.	DESCRIPTION	BY	DATE	APPVD.

TAX CODES	UNIT NO.	UNIT TYPE	INSTL. PROPOSED	RETIRED	INSTL. COMPLETED	RETIRED

AS-BUILT DRAWING-PRESSURE TEST DATA	
TEST PRES. (PSIG)	END

VISUAL INSPECTION CERTIFICATION	
NAME	DATE

CONSTRUCTION	
INSPECTOR	FOREMAN

ISOLATION AREA	W.R. NO.
323	1990593

ENGINEER/TECH: FRANCILL RODRIGUEZ		PHONE: 702-365-2311	
ACCOUNT REP: MIKE BAILEY		PHONE: 702-528-7745	
PROJECT CONTACT: RICH RIAL		PHONE: 702-378-0527	
SHEET NO: 4 OF 4	SCALE: 1" = 40'	DATE: 10/03/2014	
DWN. BY: SEI	CHKD. BY:	APPVD. BY:	
<b>SUMMERLIN VILLAGE 23B</b>			
<b>PARCEL V UNIT 2</b>			
H# 55861		1074991-2	
H# 55861		1074991-2	