

MASONRY FINISH NOTES

1. EXTERIOR OF BUILDING: TOOLED RAKED TYP. UNLESS NOTED OTHERWISE.
2. INTERIOR OF BUILDING: ALL JOINTS TO BE SMOOTH FINISH.

KEYNOTES

- NO. DESCRIPTION
1. DRINKING FOUNTAIN, SEE PLUMBING DWGS. AND SHT. PA-2.3 FOR MTG. HTS.
 2. VENDING MACHINES, BY OWNER
 3. LOCKERS, REFERENCE SPECIFICATIONS.
 4. LINE OF METAL ROOF ABOVE, SEE ELEVATIONS.
 5. COLUMN, REF. STRUCT. DWGS.
 6. INDOOR MECHANICAL EQUIP., REF. MECH. DWGS.
 7. ELECTRICAL PANEL, REF. ELECTRICAL DWGS AND SPEC'S.
 8. OUTDOOR MECHANICAL UNIT, REF. HVAC DWGS AND SPEC'S.
 9. PRE-FAB. HANDICAPPED SHOWER ENCLOSURE, REF. SPECIFICATIONS.
 10. FURR. OUT WALL AROUND STEEL COLUMN, USE WALL TYPE NO. 1, TYP.
 11. STEEL COLUMN, PAINTED
 12. MTL. FIGURE. SEE SHEET SD-13.
 13. LINE OF FLAT ARCH ABOVE.
 14. FLOOR FINISH GRAPHICS, SEE SHEET PA-2.7.
 15. ROLL-UP DOOR HEAD ABOVE.

- [X] WINDOWS TYPES. SEE SHEET GA-6.1
FIRE EXTINGUISHER, REF. SPECS. & DETAIL 12/GA-9.5
F.E.

GENERAL NOTES


1. SEE SITE PLAN FOR HARDSCAPE & LANDSCAPE AREAS ADJACENT TO BUILDING, COORD. W/ LANDSCAPE & CIVIL DWGS.
3. SEE GEOTECH. DATA REPORT INSPECS. FOR PREP. OF SOIL.
5. SEE ELECTRICAL DRAWINGS AND SPECIFICATIONS FOR LOCATIONS OF TELEPHONE BOARD, ELECTRICAL PANELS, ETC., PROVIDE BLOCKING IN WALL & SUPPORT.
6. INTERIOR WALL FINISH TO BE LIGHT ORANGE PEEL, COORD. W/ OWNER.
8. DIMENSIONS ON DRAWINGS ARE TO FACE OF STUDS UNLESS OTHERWISE NOTED.
9. CONTRACTOR TO COMPLY WITH GEOTECHNICAL RECOMMENDATIONS AND CLARK COUNTY PUBLIC WORKS UNIFORM STANDARD SPECIFICATIONS AND DRAWINGS.
11. CONTRACTOR SHALL CHECK AND VERIFY SIZE AND LOCATION OF DUCT OPENINGS AND PLUMBING RUNS WITH SUB- CONTRACTOR BEFORE FRAMING WALLS, ROOFS, ETC.
12. CONTRACTOR SHALL PROVIDE AND LOCATE ACCESS PANELS AS REQUIRED AFTER INSTALLATION OF MECHANICAL DUCTS, PLUMBING, AND ELECTRICAL WORK.
13. CONTRACTOR TO PROVIDE PROJECT BARRICADES, SIGNS, AND SAFETY PROVISIONS-SEE SPECS'.
17. PROVIDE SPECIAL STRIPS @ TILE/CARPET AND CONCRETE TRANSITIONS, SUBMIT SAMPLES.
18. ALL EXPOSED MASONRY BOND BEAMS SHALL HAVE "U" SHAPE TYPE C.M.U. BLOCK FINISHED BOTTOM TYPICAL.
19. REF. TO ELEVATIONS AND FINISH SCHED. FOR CMU BLOCK COLOR AND TEXTURE AT ALL EXPOSED CMU LOCATIONS.
20. PROVIDE 5/8" "WATER PROOFING TYPE BOARD" IN LIEU OF GYP. BD. AT ALL PLUMBING WALLS, REF. SPECS.
21. LOCATE DOOR JAMBS 6" FROM CORNER/ENDS OF WALLS, TYP. U.N.O.
22. PROVIDE WINDOW LOUVER BLINDS AT ALL OFFICES AND STORAGE SPACES, REF. SPECS.
23. PROVIDE CORNER GUARDS AT ALL CORNERS AND WALLS IN PRO-SHOP SPACE ONLY TO 7'-0" A.F.F., REF. SPECS.

WALL LEGEND

- 1 3 5/8" - 20 GA. METAL STUDS @ 16" O.C. W/ 5/8" TYPE "X" GYP. BD. EA. SIDE EXTEND 6" PAST CLG. & BRACE PER STRUCT. DWGS. AND DETAILS
- 2 8"x8"x16" C.M.U. WALL, SEE EXTERIOR ELEV'S. & STRUCT. DWGS. WITH 2'-20 GA. FURRING CHANNELS @ 16" O.C. AND 5/8" TYPE "X" GYP. BD. ON INTERIOR SIDE, FILL CAVITY W/ 2" THICK RIGID INSUL. (PROVIDE 5/8" CEMENT BOARD WITH CERAMIC TILE FINISH OVER THIN SET AT BATHROOMS.)
- 3 8"x8"x16" C.M.U. WALL, SEE EXTERIOR ELEV'S. & STRUCT. DWGS. WITH 3 5/8" - 20 GA METAL STUDS @ 16" O.C. AND 5/8" CEMENT BOARD AND CERAMIC TILE ON INTERIOR SIDE, FILL CAVITY W/ 4" THICK BATT. INSUL. SEE STRUCTURAL DRAWINGS FOR ADDITIONAL INFORMATION.
- 4 6" - 20 GA. METAL STUDS @ 16" O.C. W/ 5/8" TYPE "X" GYP. BOARD EACH SIDE, FULL HT. TO BOTTOM OF STRUCTURE, PROVIDE R-11 BATT. INSULATION FULL HEIGHT.
- 5 3 5/8" - 20 GA. METAL STUDS, STAGGERED @ 8" O.C. (16" SPACING), W/ 5/8" CEMENT BOARD AND CERAMIC TILE ON EACH SIDE, PROVIDE 2-LAYERS OF R-13 BATT. INSUL. ONE ON EACH SIDE OF WALL. SEE STRUCT. DWGS. FOR ADDITIONAL INFORMATION.
- 6 12" - 20 GA. METAL STUDS @ 16" O.C. WITH 5/8" EXTERIOR GYP. SHEATHING, WATERPROOFING MEMBRANE AND 7/8" STUCCO SYSTEM EACH SIDE. SEE STRUCT. DWGS. FOR ADDITIONAL INFORMATION.
- 7 8"x8"x16" EXPOSED CMU WALL, SEE STRUCT. DWGS., REF. FINISH LEGEND & MASONRY NOTES.
- 8 6" - 20 GA. METAL STUDS @ 16" O.C. WITH 5/8" EXTERIOR GYP. SHEATHING, WATERPROOFING MEMBRANE AND 7/8" STUCCO SYSTEM ON EXTERIOR SIDE, AND 5/8" TYPE "X" GYP. BOARD ON INTERIOR SIDE, FULL HEIGHT, FILL CAVITY WITH R-19 BATT. INSULATION FULL HEIGHT. (DELETE GYP. BOARD @ EXTERIOR COLUMNS), SEE STRUCT. DWGS. FOR ADDITIONAL INFORMATION.
- 9 1-HR. RATED WALL: 3 5/8" - 20 GA. MTL. STUDS @ 16" O.C. FULL HEIGHT TO BOTTOM OF DECK WITH 5/8" TYPE "X" GYP. BD. EA. SIDE. REF. DETAIL 11 AND 12 SHEET GA-9.1 FOR RATED ASSEMBLIES.
- 10 6" - 20 GA. METAL STUDS @ 16" O.C. WITH 5/8" TYP "X" GYP. BOARD ON ONE SIDE AND 5/8" CEMENT BOARD WITH CERAMIC TILE FINISH ON OTHER SIDE, (5/8" CEMENT BOARD WITH CERAMIC TILE ON BOTH SIDES WHERE APPLICABLE) EXTEND WALLS FULL HEIGHT TO BOTOM OF DECK. SEE STRUCT. DWGS. FOR ADDITIONAL INFORMATION.

PRO-SHOP NOTED FLOOR PLAN

SCALE: 1/8" = 1'-0"



REVISIONS

CONSULTANT
CDA
CREATIVE DESIGN ARCHITECTURE
ARCHITECTURE PLANNING CONSULTING
2229 Maple Rose Dr. Las Vegas, NV 89134 Tel. (702) 256 6663

WASHINGTON BUFFALO PARK - PHASE 1A
WASHINGTON & BUFFALO, LAS VEGAS, NV

PRO-SHOP NOTED FLOOR PLAN

STAMP

OWNER: CITY OF LAS VEGAS
DEPARTMENT OF PUBLIC WORKS
ARCHITECTURAL SERVICES

400 EAST STEWART AVENUE
LAS VEGAS, NEVADA 89101
PHONE: (702) 229-6555
FAX: (702) 382-5232
TDD: (702) 386-9108

DRAWN	JL
FILE	PA-21
DATE	July-2003
SCALE	1/8" = 1'-0"
REV NO	031534108
CLV DWG NO	650.16-1A
SHT NO	

PA-2.1