





1. ALL STEEL PIPE USED FOR HANDRAIL SHALL BE 1-1/2" SCH 40
2. HANDPLATES SHALL BE USED FOR FASTENING HANDRAIL EXCEPT FOR FRONT HANDRAIL WHERE ANCHOR BOLTS SHALL BE USED.
3. HANDRAIL SHALL HAVE A MINIMUM OF TWO COATS OF PRIMER PAINT APPLIED AND THE FINAL COATS OF PAINT SHALL BE APPLIED IN FUTURE.
4. PAINTING SHALL BEGIN AFTER ALL WELDING IS COMPLETED.
5. WELDING SHALL BE GROUND SMOOTH TO PIPES.


$$\left(\frac{2}{5} \right)$$
 $\frac{3}{5}$ 