

QUANTITIES

SHEET NO. →

4 5 6 7

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET			
1		1 1/2" AC PAVEMENT	S.Y.	2,518	2,518			
2		TYPE II GRAVEL BASE	C.Y.	419	14	405		
3		30" ROLL TYPE CURB & GUTTER	L.F.	970		970		
4		4" SIDEWALK	S.F.	3,877		3,877		
5		HANDICAP RAMP	EA.	1		1		
6		CONCRETE DRIVEWAY	S.F.	770	770			

WATER:

1		STD. F.H. W/6" G.V. & 6" A.C.P. LATERAL	EA.	2	2			
2		8" PVC	L.F.	507	507			
3		8" GATE VALVE	EA.	1	1			
4		8"-45" BEND	EA.	2	2			
5		12" X 8" REDUCER	EA.	1	1			
6		3/4" SERVICE W/METER BOX	EA.	15	15			
7		3/4" METER BY L.V.V.W.D.	EA.	8	8			
8		5/8" METER BY L.V.V.W.D.	EA.	7	7			
9		1-1/2" IRRIGATION METER WITH RPPA	EA.	2	2			
10		12" PVC	L.F.	989	156	816		
11		12"-45" BEND	EA.	1		1		
12		12"-22.5" BEND	EA.	1		1		

SEWER:

1		8" PVC SEWER	L.F.	1,563	752	811		
2		4" LATERAL	L.F.	564	564			
3		STD. MH.	EA.	7	3	4		

STREET LIGHTS:

1		100W. HRS LUMINAIRE W/11 GA. POLE	EA.	4	4			
2		1 1/4" PVC CONDUIT	L.F.	483	483			
3		3-1/2" PULLBOX	EA.	1	1			

MISCELLANEOUS:

1		6" D-3 STREET NAME SIGN	EA.	1	1			
---	--	-------------------------	-----	---	---	--	--	--

STORM DRAIN:

		TYPE 2 N.D.O.T. INLET	EA.	2		2		
		TYPE 2 N.D.O.T. INLET (BUBBLER)	EA.	1		1		
		TYPE II MH.	EA.	1		1		
		18" RCP	L.F.	253		253		
		6" PVC	L.F.	203		203		

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

JOB NO. 701.132

DEL WEBB COMMUNITIES, INC.
SUN CITY LAS VEGAS UNIT NO. 33A
ESTIMATE OF QUANTITIES

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RABBIT BLVD., LAS VEGAS, NEVADA 89102

RECOMMENDED
MICHAEL D. ROSS
P.E. NO. DATE

REV.	DATE	DESCRIPTION	C.L.K.	DATE

SHEET
3
OF 9 SHEETS